The X Keyboard Extension:

Library Specification

Amber J. Benson
Gary Aitken
Erik Fortune, Silicon Graphics, Inc
Donna Converse, X Consortium, Inc
George Sachs, Hewlett-Packard Company
Will Walker, Digital Equipment Corporation

The X Keyboard Extension:: Library Specification

by Amber J. Benson, Gary Aitken, Erik Fortune, Donna Converse, George Sachs, and Will Walker

X Version 11, Release 7.7

Table of Contents

List of Tables

Acknowledgement

This document is the result of a great deal of hard work by a great many people. Without Erik Fortune’s work as Architect of the X Keyboard Extension and the long-time support of Silicon Graphics Inc. there would not be a keyboard extension.

We gratefully thank Will Walker and George Sachs for their help and expertise in providing some of the content for this document, and Digital Equipment Corporation and Hewlett-Packard for allowing them to participate in this project, and we are deeply indebted to IBM for providing the funding to complete this library specification.

Most of all, we thank Gary Aitken and Amber J. Benson for their long hours and late nights as ultimate authors of this specification, and for serving as authors, document editors, and XKB protocol and implementation reviewers. Their commitment to accuracy and completeness, their attention to detail, their keen insight, and their good natures when working under tremendous pressure are in some measure responsible not only for the quality of this document, but for the quality of the Keyboard extension itself.

Matt Landau
Manager, X Window System
X Consortium Inc.

X Version 11, Release 7 addendum

This document is made available to you in modern formats such as HTML and PDF thanks to the efforts of Matt Dew, who converted the original troff sources to DocBook/XML and edited them into shape; Fernando Carrijo, who converted the images to SVG format; and Gaetan Nadon, who set up the formatting machinery in the libX11 builds and performed further editing of the DocBook markup.

Chapter 1. Overview

The X Keyboard Extension provides capabilities that are lacking or are cumbersome in the core X protocol.

Core X Protocol Support for Keyboards

The core X protocol specifies the ways that the *Shift*, *Control*, and *Lock* modifiers and the modifiers bound to the *Mode_switch* or *Num_Lock* keysyms interact to generate keysyms and characters. The core protocol also allows users to specify that a key affects one or more modifiers. This behavior is simple and fairly flexible, but it has a number of limitations that make it difficult or impossible to properly support many common varieties of keyboard behavior. The limitations of core protocol support for keyboards include:

- Use of a single, uniform, four-symbol mapping for all keyboard keys makes it difficult to properly support keyboard overlays, PC-style break keys, or keyboards that comply with ISO9995, or a host of other national and international standards.
- A second keyboard group may be specified using a modifier, but this has side effects that wreak havoc with client grabs and X toolkit translations. Furthermore, this approach limits the number of keyboard groups to two.
- Poorly specified locking key behavior requires X servers to look for a few "magic" keysyms to determine that keys should lock when pressed. This leads to incompatibilities between X servers with no way for clients to detect implementation differences.
- Poorly specified capitalization and control behavior requires modifications to X library source code to support new character sets or locales and can lead to incompatibilities between system wide and X library capitalization behavior.
- Limited interactions between modifiers specified by the core protocol make many common keyboard behaviors difficult or impossible to implement. For example, there is no reliable way to indicate whether or not the shift modifier should "cancel" the lock modifier.
- The lack of any explicit descriptions for indicators, most modifiers, and other aspects of the keyboard appearance requires clients that wish to clearly describe the keyboard to a user to resort to a mish-mash of prior knowledge and heuristics.

Xkb Keyboard Extension Support for Keyboards

The X Keyboard Extension makes it possible to clearly and explicitly specify most aspects of keyboard behavior on a per-key basis. It adds the notion of a keyboard group to the global keyboard state and provides mechanisms to more closely track the logical and physical state of the keyboard. For keyboard-control clients, Xkb provides descriptions and symbolic names for many aspects of keyboard appearance and behavior.

In addition, the X Keyboard Extension includes additional keyboard controls designed to make keyboards more accessible to people with movement impairments.

Xkb Extension Components

The Xkb extension is composed of two parts: a server extension, and a client-side X library extension. These consist of a loadable module that may be activated when an X server is started and a modified version of Xlib. Both server and Xlib versions must be at least X11 R6.

Figure 1.1 shows the overall structure of the Xkb extension:



Overall Xkb Structure

The server portion of the Xkb extension encompasses a database of named keyboard components, in unspecified format, that may be used to configure a keyboard. Internally, the server maintains a *keyboard description* that includes the keyboard state and configuration (mapping). By "keyboard" we mean the logical keyboard

device, which includes not only the physical keys, but also potentially a set of up to 32 indicators (usually LEDs) and bells.

The keyboard description is a composite of several different data structures, each of which may be manipulated separately. When manipulating the server components, the design allows partial components to be transmitted between the server and a client. The individual components are shown in Figure 1.1.

Client Map	The key mapping information needed to convert arbitrary keycodes to symbols.
Server Map	The key mapping information categorizing keys by functionality (which keys are modifiers, how keys behave, and so on).
Controls	Client configurable quantities effecting how the keyboard behaves, such as repeat behavior and modifications for people with movement impairments.
Indicators	The mapping of behavior to indicators.
Geometry	A complete description of the physical keyboard layout, sufficient to draw a representation of the keyboard.
Names	A mapping of names to various aspects of the keyboard such as individual virtual modifiers, indicators, and bells.
Compatibility Map	The definition of how to map core protocol keyboard state to Xkb keyboard state.

A client application interrogates and manipulates the keyboard by reading and writing portions of the server description for the keyboard. In a typical sequence a client would fetch the current information it is interested in, modify it, and write it back. If a client wishes to track some portion of the keyboard state, it typically maintains a local copy of the portion of the server keyboard description dealing with the items of interest and updates this local copy from events describing state transitions that are sent by the server.

A client may request the server to reconfigure the keyboard either by sending explicit reconfiguration instructions to it, or by telling it to load a new configuration from its database of named components. Partial reconfiguration and incremental reconfiguration are both supported.

Groups and Shift Levels

The graphic characters or control functions that may be accessed by one key are logically arranged in groups and levels. See section 14.1for a complete description of groups and levels.

Radio Groups

A radio group is a set of keys whose behavior simulates a set of radio buttons. Once a key in a radio group is pressed, it stays logically depressed until another key in the group is pressed, at which point the previously depressed key is logically released. Consequently, at most one key in a radio group can be logically depressed at one time. A radio group is defined by a radio group index, an optional name, and by

assigning each key in the radio group *XkbKB_RadioGroup* behavior and the radio group index.

Client Types

This specification differentiates between three different classes of client applications:

- Xkb-aware applications

  These applications make specific use of Xkb functionality and APIs not present in the core protocol.

- Xkb-capable applications

  These applications make no use of Xkb extended functionality and Application Programming Interfaces (APIs) directly. However, they are linked with a version of Xlib that includes Xkb and indirectly benefit from some of Xkb's features.

- Xkb-unaware applications

  These applications make no use of Xkb extended functionality or APIs and require Xkb's functionality to be mapped to core Xlib functionality to operate properly.

Compatibility With the Core Protocol

Because the Xkb extension allows a keyboard to be configured in ways not foreseen by the core protocol, and because Xkb-unaware clients are allowed to connect to a server using the Xkb extension, there must be a means of converting between the Xkb domain and the core protocol. The Xkb server extension maintains a compatibility map as part of its keyboard description; this map controls the conversion of Xkb generated events to core protocol events and the results of core protocol requests to appropriate Xkb state and configuration.

Additional Protocol Errors

The Xkb extension adds a single protocol error, *BadKeyboard* , to the core protocol error set. See section 2.6 for a discussion of the *BadKeyboard* protocol error.

Extension Library Functions

The X Keyboard Extension replaces the core protocol definition of a keyboard with a more comprehensive one. The X Keyboard Extension library interfaces are included in Xlib.[1]

Xlib detects the presence of the X Keyboard server extension and uses Xkb protocol to replace some standard X library functions related to the keyboard. If an application uses only standard X library functions to examine the keyboard or process key events, it should not need to be modified when linked with an X library containing

[1] X11R6.1 is the first release by the X Consortium, Inc.,that includes the X Keyboard Extension in Xlib. X11R6 included work in progress on this extension as nonstandard additions to the library.

the X keyboard extension. All of the keyboard-related X library functions have been modified to automatically use Xkb protocol when the server extension is present.

The Xkb extension adds library interfaces to allow a client application to directly manipulate the new capabilities.

Error Indications

Xkb functions that communicate with the X server check to be sure the Xkb extension has been properly initialized prior to doing any other operations. If the extension has not been properly initialized or the application, library, and server versions are incompatible, these functions return an error indication as shown in Table 1.1. Because of this test, *BadAccess* and *BadMatch* (due to incompatible versions) protocol errors should normally not be generated.

Table 1.1. Function Error Returns Due to Extension Problems

Functions return type	Return value
pointer to a structure	NULL
Bool	False
Status	BadAccess

Many Xkb functions do not actually communicate with the X server; they only require processing in the client-side portion of the library. Furthermore, some applications may never actually need to communicate with the server; they simply use the Xkb library capabilities. The functions that do not communicate with the server return either a pointer to a structure, a Bool, or a Status. These functions check that the application has queried the Xkb library version and return the values shown in Table 1.1 if it has not.

Chapter 2. Initialization and General Programming Information

Extension Header Files

The following include files are part of the Xkb standard:

- *<X11/XKBlib.h>*

  XKBlib.h is the main header file for Xkb; it declares constants, types, and functions.

- *<X11/extensions/XKBstr.h>*

  XKBstr.h declares types and constants for Xkb. It is included automatically from *<X11/XKBlib.h>* ; you should never need to reference it directly in your application code.

- *<X11/extensions/XKB.h>*

  XKB.h defines constants for Xkb. It is included automatically from *<X11/XKBstr.h>* ; you should never need to reference it directly in your application code.

- *<X11/extensions/XKBgeom.h>*

  XKBgeom.h declares types, symbolic constants, and functions for manipulating keyboard geometry descriptions.

Extension Name

The name of the Xkb extension is given in *<X11/extensions/Xkb.h>:*

#define XkbName "*XKEYBOARD*"

Most extensions to the X protocol are initialized by calling *XInitExtension* and passing the extension name. However, as explained in section 2.4, Xkb requires a more complex initialization sequence, and a client program should not call *XInitExtension* directly.

Determining Library Compatibility

If an application is dynamically linked, both the X server and the client-side X library must contain the Xkb extension in order for the client to use the Xkb extension capabilities. Therefore a dynamically linked application must check both the library and the server for compatibility before using Xkb function calls. A properly written program must check for compatibility between the version of the Xkb library that is dynamically loaded and the one used when the application was built. It must then check the server version for compatibility with the version of Xkb in the library.

If your application is statically linked, you must still check for server compatibility and may check library compatibility. (It is possible to compile against one set

of header files and link against a different, incompatible, version of the library, although this should not normally occur.)

To determine the compatibility of a library at runtime, call *XkbLibraryVersion*.

Bool *XkbLibraryVersion* (*lib_major_in_out* , *lib_minor_in_out*)
int * *lib_major_in_out;* /* specifies and returns the major Xkb library version. */
int * *lib_minor_in_out;* /* specifies and returns the minor Xkb library version. */

Pass the symbolic value *XkbMajorVersion* in *lib_major_in_out* and *XkbMinorVersion* in *lib_minor_in_out* . These arguments represent the version of the library used at compile time. The *XkbLibraryVersion* function backfills the major and minor version numbers of the library used at run time in *lib_major_in_out* and *lib_minor_in_out* . If the versions of the compile time and run time libraries are compatible, *XkbLibraryVersion* returns *True* , otherwise, it returns *False.*

In addition, in order to use the Xkb extension, you must ensure that the extension is present in the server and that the server supports the version of the extension expected by the client. Use *XkbQueryExtension* to do this, as described in the next section.

Initializing the Keyboard Extension

Call *XkbQueryExtension* to check for the presence and compatibility of the extension in the server and to initialize the extension. Because of potential version mismatches, you cannot use the generic extension mechanism functions (*XQueryExtension* and *XInitExtension*) for checking for the presence of, and initializing the Xkb extension.

You must call *XkbQueryExtension* or *XkbOpenDisplay* before using any other Xkb library interfaces, unless such usage is explicitly allowed in the interface description in this document. The exceptions are: *XkbIgnoreExtension* , *XkbLibraryVersion* , and a handful of audible-bell functions. You should not use any other Xkb functions if the extension is not present or is uninitialized. In general, calls to Xkb library functions made prior to initializing the Xkb extension cause *BadAccess* protocol errors.

XkbQueryExtension both determines whether a compatible Xkb extension is present in the X server and initializes the extension when it is present.

Bool *XkbQueryExtension* (*dpy, opcode_rtrn, event_rtrn, error_rtrn, major_in_out, minor_in_out*)
Display * *dpy;* /* connection to the X server */
int * *opcode_rtrn* ; /* backfilled with the major extension opcode */
int * *event_rtrn* ; /* backfilled with the extension base event code */
int * *error_rtrn* ; /* backfilled with the extension base error code */
int * *major_in_out* ; /* compile time lib major version in, server major version out */
int * *minor_in_out;* /* compile time lib min version in, server minor version out */

The *XkbQueryExtension* function determines whether a compatible version of the X Keyboard Extension is present in the server. If a compatible extension is present, *XkbQueryExtension* returns *True* ; otherwise, it returns *False* .

If a compatible version of Xkb is present, *XkbQueryExtension* initializes the extension. It backfills the major opcode for the keyboard extension in *opcode_rtrn* , the base event code in *event_rtrn , the base error code* in *error_rtrn* , and the major and minor version numbers of the extension in *major_in_out* and *minor_in_out* . The major opcode is reported in the *req_major* fields of some Xkb events. For a discussion of the base event code, see section 4.1.

As a convenience, you can use the function *XkbOpenDisplay* to perform these three tasks at once: open a connection to an X server, check for a compatible version of the Xkb extension in both the library and the server, and initialize the extension for use.

Display * *XkbOpenDisplay* (*display_name, event_rtrn, error_rtrn, major_in_out, minor_in_out, reason_rtrn)*

char * *display_name* ; /* hardware display name, which determines the display and communications domain to be used */

int * *event_rtrn* ; /* backfilled with the extension base event code */

int * *error_rtrn* ; /* backfilled with the extension base error code */

int * *major_in_out* ; /* compile time lib major version in, server major version out */

int * *minor_in_out* ; /* compile time lib minor version in, server minor version out */

int * *reason_rtrn* ; /* backfilled with a status code */

XkbOpenDisplay is a convenience function that opens an X display connection and initializes the X keyboard extension. In all cases, upon return *reason_rtrn* contains a status value indicating success or the type of failure. If *major_in_out* and *minor_in_out* are not *NULL* , *XkbOpenDisplay* first calls *XkbLibraryVersion* to determine whether the client library is compatible, passing it the values pointed to by *major_in_out* and *minor_in_out* . If the library is incompatible, *XkbOpenDisplay* backfills *major_in_out* and *minor_in_out* with the major and minor extension versions of the library being used and returns *NULL* . If the library is compatible, *XkbOpenDisplay* next calls *XOpenDisplay* with the *display_name* . If this fails, the function returns *NULL* . If successful, *XkbOpenDisplay* calls *XkbQueryExtension* and backfills the major and minor Xkb server extension version numbers in *major_in_out* and *minor_in_out* . If the server extension version is not compatible with the library extension version or if the server extension is not present, *XkbOpenDisplay* closes the display and returns *NULL* . When successful, the function returns the display connection .

The possible values for *reason_rtrn* are:

- *XkbOD_BadLibraryVersion* indicates *XkbLibraryVersion* returned *False*.
- *XkbOD_ConnectionRefused* indicates the display could not be opened.
- *XkbOD_BadServerVersion* indicates the library and the server have incompatible extension versions.
- *XkbOD_NonXkbServer* indicates the extension is not present in the X server.
- *XkbOD_Success* indicates that the function succeeded.

Disabling the Keyboard Extension

If a server supports the Xkb extension, the X library normally implements preXkb keyboard functions using the Xkb keyboard description and state. The server Xkb keyboard state may differ from the preXkb keyboard state. This difference does not affect most clients, but there are exceptions. To allow these clients to work properly, you may instruct the extension not to use Xkb functionality.

Call *XkbIgnoreExtension* to prevent core X library keyboard functions from using the X Keyboard Extension. You must call *XkbIgnoreExtension* before you open a server connection; Xkb does not provide a way to enable or disable use of the extension once a connection is established.

Bool *XkbIgnoreExtension* (*ignore*)
Bool *ignore* ; /* *True* means ignore the extension */

XkbIgnoreExtension tells the X library whether to use the X Keyboard Extension on any subsequently opened X display connections. If ignore is *True* , the library does not initialize the Xkb extension when it opens a new display. This forces the X server to use compatibility mode and communicate with the client using only core protocol requests and events. If ignore is *False* , the library treats subsequent calls to *XOpenDisplay* normally and uses Xkb extension requests, events, and state. Do not explicitly use Xkb on a connection for which it is disabled. *XkbIgnoreExtension* returns *False* if it was unable to apply the ignore request.

Protocol Errors

Many of the Xkb extension library functions described in this document can cause the X server to report an error, referred to in this document as a *BadXxx* protocol error, where *Xxx* is some name. These errors are fielded in the normal manner, by the default Xlib error handler or one replacing it. Note that X protocol errors are not necessarily reported immediately because of the buffering of X protocol requests in Xlib and the server.

Table 2.1 lists the protocol errors that can be generated, and their causes.

Table 2.1. Xkb Protocol Errors

Error	Cause
BadAccess	The Xkb extension has not been properly initialized
BadKeyboard	The device specified was not a valid core or input extension device
BadImplementation	Invalid reply from server
BadAlloc	Unable to allocate storage
BadMatch	A compatible version of Xkb was not available in the server or an argument has correct type and range, but is otherwise invalid
BadValue	An argument is out of range
BadAtom	A name is neither a valid Atom or *None*
BadDevice	Device, Feedback Class, or Feedback ID invalid

The Xkb extension adds a single protocol error, *BadKeyboard* , to the core protocol error set. This error code will be reported as the *error_rtrn* when *XkbQueryExtension* is called. When a *BadKeyboard* error is reported in an *XErrorEvent* , additional information is reported in the *resource_id* field. The most significant byte of the *resource_id* is a further refinement of the error cause, as defined in Table 2.2. The least significant byte will contain the device, class, or feedback ID as indicated in the table.

Table 2.2. BadKeyboard Protocol Error resource_id Values

high-order byte	value	meaning	low-order byte
XkbErr_BadDevice	0xff	device not found	device ID
XkbErr_BadClass	0xfe	device found, but it is of the wrong class	class ID
XkbErr_BadId	0xfd	device found, class ok, but device does not contain a feedback with the indicated ID	feedback ID

Display and Device Specifications in Function Calls

Where a connection to the server is passed as an argument (Display*) and an *XkbDescPtr* is also passed as an argument, the Display* argument must match the *dpy* field of the *XkbDescRec* pointed to by the *XkbDescPtr* argument, or else the *dpy* field of the *XkbDescRec* must be *NULL* . If they don't match or the *dpy* field is not *NULL* , a *BadMatch* error is returned (either in the return value or a backfilled *Status* variable). Upon successful return, the *dpy* field of the *XkbDescRec* always contains the Display* value passed in.

The Xkb extension can communicate with the X input extension if it is present. Consequently, there can potentially be more than one input device connected to the server. Most Xkb library calls that require communicating with the server involve both a server connection (Display * *dpy*) and a device identifier (unsigned int *device_spec*). In some cases, the device identifier is implicit and is taken as the *device_spec* field of an *XkbDescRec* structure passed as an argument.

The device identifier can specify any X input extension device with a *KeyClass* component, or it can specify the constant, *XkbUseCoreKbd* . The use of *XkbUseCoreKbd* allows applications to indicate the core keyboard without having to determine its device identifier.

Where an Xkb device identifier is passed as an argument and an *XkbDescPtr* is also passed as an argument, if either the argument or the *XkbDescRec* *device_spec* field is *XkbUseCoreKbd* , and if the function returns successfully, the *XkbDescPtr* *device_spec* field will have been converted from *XkbUseCoreKbd* to a real Xkb device ID. If the function does not complete successfully, the *device_spec* field remains unchanged. Subsequently, the device id argument must match the *device_spec* field of the *XkbDescPtr* argument. If they don't match, a *BadMatch* error is returned (either in the return value or a backfilled *Status* variable).

When the Xkb extension in the server hands an application a device identifier to use for the keyboard, that ID is the input extension identifier for the device if the server

supports the X Input Extension. If the server does not support the input extension, the meaning of the identifier is undefined — the only guarantee is that when you use *XkbUseCoreKbd* , *XkbUseCoreKbd* will work and the identifier returned by the server will refer to the core keyboard device.

Chapter 3. Data Structures

An Xkb keyboard description consists of a variety of data structures, each of which describes some aspect of the keyboard. Although each data structure has its own peculiarities, there are a number of features common to nearly all Xkb structures. This chapter describes these common features and techniques for manipulating them.

Many Xkb data structures are interdependent; changing a field in one might require changes to others. As an additional complication, some Xkb library functions allocate related components as a group to reduce fragmentation and allocator overhead. In these cases, simply allocating and freeing fields of Xkb structures might corrupt program memory. Creating and destroying such structures or keeping them properly synchronized during editing is complicated and error prone.

Xkb provides functions and macros to allocate and free all major data structures. You should use them instead of allocating and freeing the structures yourself.

Allocating Xkb Data Structures

Xkb provides functions, known as allocators, to create and initialize Xkb data structures. In most situations, the Xkb functions that read a keyboard description from the server call these allocators automatically. As a result, you will seldom have to directly allocate or initialize Xkb data structures.

However, if you need to enlarge an existing structure or construct a keyboard definition from scratch, you may need to allocate and initialize Xkb data structures directly. Each major Xkb data structure has its own unique allocator. The allocator functions share common features: allocator functions for structures with optional components take as an input argument a mask of subcomponents to be allocated. Allocators for data structures containing variable-length data take an argument specifying the initial length of the data.

You may call an allocator to change the size of the space allocated for variable-length data. When you call an allocator with an existing data structure as a parameter, the allocator does not change the data in any of the fields, with one exception: variable-length data might be moved. The allocator resizes the allocated memory if the current size is too small. This normally involves allocating new memory, copying existing data to the newly allocated memory, and freeing the original memory. This possible reallocation is important to note because local variables pointing into Xkb data structures might be invalidated by calls to allocator functions.

Adding Data and Editing Data Structures

You should edit most data structures via the Xkb-supplied helper functions and macros, although a few data structures can be edited directly. The helper functions and macros make sure everything is initialized and interdependent values are properly updated for those Xkb structures that have interdependencies. As a general rule, if there is a helper function or macro to edit the data structure, use it. For example, increasing the width of a type requires you to resize every key that uses that type. This is complicated and ugly, which is why there's an *XkbResizeKeyType* function.

Many Xkb data structures have arrays whose size is reported by two fields. The first field, whose name is usually prefixed by *sz_* , represents the total number of elements that can be stored in the array. The second field, whose name is usually prefixed by *num_* , specifies the number of elements currently stored there. These arrays typically represent data whose total size cannot always be determined when the array is created. In these instances, the usual way to allocate space and add data is as follows:

- Call the allocator function with some arbitrary size, as a hint.
- For those arrays that have an *Xkb...Add...* function, call it each time you want to add new data to the array. The function expands the array if necessary.

For example, call:

XkbAllocGeomShapes(geom,4)

to say "I'll need space for four new shapes in this geometry." This makes sure that *sz_shapes* - *num_shapes* >= 4, and resizes the shapes array if it isn't. If this function succeeds, you are guaranteed to have space for the number of shapes you need.

When you call an editing function for a structure, you do not need to check for space, because the function automatically checks the *sz_* and *num_* fields of the array, resizes the array if necessary, adds the entry to the array, and then updates the *num_* field.

Making Changes to the Server's Keyboard Description

In Xkb, as in the core protocol, the client and server have independent copies of the data structures that describe the keyboard. The recommended way to change some aspect of the keyboard mapping in the X server is to edit a local copy of the Xkb keyboard description and then send only the changes to the X server. This method helps eliminate the need to transfer the entire keyboard description or even an entire data structure for only minor changes.

To help you keep track of the changes you make to a local copy of the keyboard description, Xkb provides separate special *changes* data structures for each major Xkb data structure. These data structures do not contain the actual changed values: they only indicate the changes that have been made to the structures that actually describe the keyboard.

When you wish to change the keyboard description in the server, you first modify a local copy of the keyboard description and then flag the modifications in an appropriate changes data structure. When you finish editing the local copy of the keyboard description, you pass your modified version of the keyboard description and the modified changes data structure to an Xkb function. This function uses the modified keyboard description and changes structure to pass only the changed information to the server. Note that modifying the keyboard description but not setting the appropriate flags in the changes data structure causes indeterminate behavior.

Tracking Keyboard Changes in the Server

The server reports all changes in its keyboard description to any interested clients via special Xkb events. Just as clients use special changes data structures to change the keyboard description in the server, the server uses special changes data structures to tell a client what changed in the server's keyboard description.

Unlike clients, however, the server does not always pass the new values when it reports changes to its copy of the keyboard description. Instead, the server only passes a changes data structure when it reports changes to its keyboard description. This is done for efficiency reasons — some clients do not always need to update their copy of the keyboard description with every report from the server.

When your client application receives a report from the server indicating the keyboard description has changed, you can determine the set of changes by passing the event to an Xkb function that "notes" event information in the corresponding changes data structure. These "note changes" functions are defined for all major Xkb components, and their names have the form *XkbNote{Component}Changes* , where *Component* is the name of a major Xkb component such as *Map* or *Names* . When you want to copy these changes from the server into a local copy of the keyboard description, use the corresponding *XkbGet{Component}Changes* function , passing it the changes structure. The function then retrieves only the changed structures from the server and copies the modified pieces into the local keyboard description.

Freeing Data Structures

For the same reasons you should not directly use *malloc* to allocate Xkb data structures, you should not free Xkb data structures or components directly using *free* or *Xfree* . Xkb provides functions to free the various data structures and their components. Always use the free functions supplied by Xkb. There is no guarantee that any particular field can be safely freed by *free* or *Xfree* .

Chapter 4. Xkb Events

The primary way the X server communicates with clients is by sending X events to them. Some events are sent to all clients, while others are sent only to clients that have requested them. Some of the events that can be requested are associated with a particular window and are only sent to those clients who have both requested the event and specified the window in which the event occurred.

The Xkb extension uses events to communicate the keyboard status to interested clients. These events are not associated with a particular window. Instead, all Xkb keyboard status events are reported to all interested clients, regardless of which window currently has the keyboard focus and regardless of the grab state of the keyboard.[1]

The X server reports the events defined by the Xkb extension to your client application only if you have requested them. You may request Xkb events by calling either *XkbSelectEvents* or *XkbSelectEventDetails* . *XkbSelectEvents* requests Xkb events by their event type and causes them to be reported to your client application under all circumstances. You can specify a finer granularity for event reporting by using *XkbSelectEventDetails* ; in this case events are reported only when the specific detail conditions you specify have been met.

Xkb Event Types

The Xkb Extension adds new event types to the X protocol definition. An Xkb event type is defined by two fields in the X event data structure. One is the *type* field, containing the *base event code.* This base event code is a value the X server assigns to each X extension at runtime and thatidentifies the extension that generated the event; thus, the event code in the *type* field identifies the event as an Xkb extension event, rather than an event from another extension or a core X protocol event. You can obtain the base event code via a call to *XkbQueryExtension* or *XkbOpenDisplay* . The second field is the Xkb event type, which contains a value uniquely identifying each different Xkb event type. Possible values are defined by constants declared in the header file <X11/extensions/Xkb.h>.

Table 4.1 lists the categories of events defined by Xkb and their associated event types, as defined in *Xkb.h* . Each event is described in more detail in the section referenced for that event.

[1]The one exception to this rule is the XkbExtensionDeviceNotify event report that is sent when a client attempts to use an unsupported feature of an X Input Extension device (see section 21.4).

Table 4.1. Xkb Event Types

Event Type	Conditions Generating Event	Section	Page
XkbNewKeyboardNotify	Keyboard geometry; keycode range change	19	187
XkbMapNotify	Keyboard mapping change	14.4	122
XkbStateNotify	Keyboard state change	5.4	25
XkbControlsNotify	Keyboard controls state change	10.11	79
XkbIndicatorStateNotify	Keyboard indicators state change	8.5	45
XkbIndicatorMapNotify	Keyboard indicators map change	8.5	45
XkbNamesNotify	Keyboard name change	18.5	185
XkbCompatMapNotify	Keyboard compatibility map change	17.5	178
XkbBellNotify	Keyboard bell generated	9.4	52
XkbActionMessage	Keyboard action message	16.1.11	155
XkbAccessXNotify	AccessX state change	10.6.4	65
XkbExtensionDeviceNotify	Extension device change	21.6	207

Xkb Event Data Structures

Xkb reports each event it generates in a unique structure holding the data values needed to describe the conditions the event is reporting. However, all Xkb events have certain things in common. These common features are contained in the same fields at the beginning of all Xkb event structures and are described in the *XkbAnyEvent* structure:

```
typedef struct {
      int               type;        /* Xkb extension base event code */
      unsigned long     serial;      /* X server serial number for event */
      Bool              send_event;  /*  True => synthetically generated */
      Display *         display;     /* server connection where event
generated */
      Time              time;        /* server time when event generated */
      int               xkb_type;    /* Xkb minor event code */
      unsigned int      device;      /* Xkb device ID, will not be
                                        XkbUseCoreKbd */
} XkbAnyEvent
;
```

For any Xkb event, the *type* field is set to the base event code for the Xkb extension, assigned by the server to all Xkb extension events. The *serial* , *send_event* , and *display* fields are as described for all X11 events. The *time* field is set to the time when the event was generated and is expressed in milliseconds. The *xkb_type* field contains the minor extension event code, which is the extension event type, and is one of the values listed in Table 4.1. The *device* field contains the keyboard device identifier associated with the event. This is never *XkbUseCoreKbd* , even if the request that generated the event specified a device of *XkbUseCoreKbd* . If the request that generated the event specified *XkbUseCoreKbd* , *device* contains

a value assigned by the server to specify the core keyboard. If the request that generated the event specified an X input extension device, *device* contains that same identifier.

Other data fields specific to individual Xkb events are described in subsequent chapters where the events are described.

Selecting Xkb Events

Xkb events are selected using an event mask, much the same as normal core X events are selected. However, unlike selecting core X events, where you must specify the selection status (on or off) for all possible event types whenever you wish to change the selection criteria for any one event, Xkb allows you to restrict the specification to only the event types you wish to change. This means that you do not need to remember the event selection values for all possible types each time you want to change one of them.

Many Xkb event types are generated under several different circumstances. When selecting to receive an Xkb event, you may specify either that you want it delivered under all circumstances, or that you want it delivered only for a subset of the possible circumstances.

You can also deselect an event type that was previously selected for, using the same granularity.

Xkb provides two functions to select and deselect delivery of Xkb events. *XkbSelectEvents* allows you to select or deselect delivery of more than one Xkb event type at once. Events selected using *XkbSelectEvents* are delivered to your program under all circumstances that generate the events. To restrict delivery of an event to a subset of the conditions under which it occurs, use *XkbSelectEventDetails* . *XkbSelectEventDetails* only allows you to change the selection conditions for a single event at a time, but it provides a means of fine-tuning the conditions under which the event is delivered.

To select and / or deselect for delivery of one or more Xkb events and have them delivered under all conditions, use *XkbSelectEvents* .

Bool *XkbSelectEvents* (*display, device_spec, bits_to_change, values_for_bits*)

Display * *display* ; /* connection to the X server */

unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */

unsigned long int *bits_to_change;* /* determines events to be selected / deselected */

unsigned long int *values_for_bits* ; /* 1=>select, 0->deselect; for events in *bits_to_change* */

This request changes the Xkb event selection mask for the keyboard specified by *device_spec* .

Each Xkb event that can be selected is represented by a bit in the *bits_to_change* and *values_for_bits* masks. Only the event selection bits specified by the *bits_to_change* parameter are affected; any unspecified bits are left unchanged. To turn on event selection for an event, set the bit for the event in the *bits_to_change* parameter and set the corresponding bit in the *values_for_bits* parameter. To turn

off event selection for an event, set the bit for the event in the *bits_to_change* parameter and do not set the corresponding bit in the *values_for_bits* parameter. The valid values for both of these parameters are an inclusive bitwise OR of the masks shown in Table 4.2. There is no interface to return your client's current event selection mask. Clients cannot set other clients' event selection masks.

If a bit is not set in the *bits_to_change* parameter, but the corresponding bit is set in the *values_for_bits* parameter, a *BadMatch* protocol error results. If an undefined bit is set in either the *bits_to_change* or the *values_for_bits* parameter, a *BadValue* protocol error results.

All event selection bits are initially zero for clients using the Xkb extension. Once you set some bits, they remain set for your client until you clear them via another call to *XkbSelectEvents* .

XkbSelectEvents returns *False* if the Xkb extension has not been initilialized and *True* otherwise.

To select or deselect for a specific Xkb event and optionally place conditions on when events of that type are reported to your client, use *XkbSelectEventDetails* . This allows you to exercise a finer granularity of control over delivery of Xkb events with *XkbSelectEvents* .

Bool *XkbSelectEventDetails* (*display, device_spec, event_type, bits_to_change* , *values_for_bits*)

Display * *display* ; /* connection to the X server */

unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */

unsigned int *event_type* ; /* Xkb event type of interest */

unsigned long int *bits_to_change* ; /* event selection details */

unsigned long int *values_for_bits* ; /* values for bits selected by *bits_to_change* */

While *XkbSelectEvents* allows multiple events to be selected, *XkbSelectEventDetails* changes the selection criteria for a single type of Xkb event. The interpretation of the *bits_to_change* and *values_for_bits* masks depends on the event type in question.

XkbSelectEventDetails changes the Xkb event selection mask for the keyboard specified by *device_spec* and the Xkb event specified by *event_type* . To turn on event selection for an event detail, set the bit for the detail in the *bits_to_change* parameter and set the corresponding bit in the *values_for_bits* parameter. To turn off event detail selection for a detail, set the bit for the detail in the *bits_to_change* parameter and do not set the corresponding bit in the *values_for_bits* parameter.

If an invalid event type is specified, a *BadValue* protocol error results. If a bit is not set in the *bits_to_change* parameter, but the corresponding bit is set in the *values_for_bits* parameter, a *BadMatch* protocol error results. If an undefined bit is set in either the *bits_to_change* or the *values_for_bits* parameter, a *BadValue* protocol error results.

For each type of Xkb event, the legal event details that you can specify in the *XkbSelectEventDetails* request are listed in the chapters that describe each event in detail.

Event Masks

The X server reports the events defined by Xkb to your client application only if you have requested them via a call to *XkbSelectEvents* or *XkbSelectEventDetails* . Specify the event types in which you are interested in a mask, as described in section 4.3.

Table 4.2 lists the event mask constants that can be specified with the *XkbSelectEvents* request and the circumstances in which the mask should be specified.

Table 4.2. XkbSelectEvents Mask Constants

Event Mask	Value	Notification Wanted
XkbNewKeyboardNotifyMask	(1L<<0)	Keyboard geometry change
XkbMapNotifyMask	(1L<<1)	Keyboard mapping change
XkbStateNotifyMask	(1L<<2)	Keyboard state change
XkbControlsNotifyMask	(1L<<3)	Keyboard control change
XkbIndicatorStateNotifyMask	(1L<<4)	Keyboard indicator state change
XkbIndicatorMapNotifyMask	(1L<<5)	Keyboard indicator map change
XkbNamesNotifyMask	(1L<<6)	Keyboard name change
XkbCompatMapNotifyMask	(1L<<7)	Keyboard compat map change
XkbBellNotifyMask	(1L<<8)	Bell
XkbActionMessageMask	(1L<<9)	Action message
XkbAccessXNotifyMask	(1L<<10)	AccessX features
XkbExtensionDeviceNotifyMask	(1L<<11)	Extension device
XkbAllEventsMask	(0xFFF)	All Xkb events

Unified Xkb Event Type

The *XkbEvent* structure is a union of the individual structures declared for each Xkb event type and for the core protocol *XEvent* type. Given an *XkbEvent* structure, you may use the *type* field to determine if the event is an Xkb event (*type* equals the Xkb base event code; see section 2.4). If the event is an Xkb event, you may then use the *any.xkb_type* field to determine the type of Xkb event and thereafter access the event-dependent components using the union member corresponding to the particular Xkb event type.

```
typedef union _XkbEvent {
      int                         type;
      XkbAnyEvent                 any;
      XkbStateNotifyEvent         state;
      XkbMapNotifyEvent           map;
      XkbControlsNotifyEvent      ctrls;
      XkbIndicatorNotifyEvent     indicators;
      XkbBellNotifyEvent          bell;
      XkbAccessXNotifyEvent       accessx;
```

```
        XkbNamesNotifyEvent             names;
        XkbCompatMapNotifyEvent         compat;
        XkbActionMessageEvent           message;
        XkbExtensionDeviceNotifyEvent   device;
        XkbNewKeyboardNotifyEvent       new_kbd;
        XEvent                          core;
} XkbEvent;
```

This unified Xkb event type includes a normal *XEvent* as used by the core protocol, so it is straightforward for applications that use Xkb events to call the X library event functions without having to cast every reference. For example, to get the next event, you can simply declare a variable of type *XkbEvent* and call:

XNextEvent(dpy,&xkbev.core);

Chapter 5. Keyboard State

Keyboard state encompasses all of the transitory information necessary to map a physical key press or release to an appropriate event. The Xkb keyboard state consists of primitive components and additional derived components that are maintained for efficiency reasons. Figure 5.1 shows the components of Xkb keyboard state and their relationships.



Xkb State

Keyboard State Description

The Xkb keyboard state is comprised of the state of all keyboard modifiers, the keyboard group, and the state of the pointer buttons. These are grouped into the following components:

- The locked group and locked modifiers
- The latched group and latched modifiers
- The base group and base modifiers
- The effective group and effective modifiers
- The state of the core pointer buttons

The *modifiers* are *Shift* , *Lock* , *Control* , and *Mod1* - *Mod5* , as defined by the core protocol. A modifier can be thought of as a toggle that is either set or unset. All modifiers are initially unset. When a modifier is locked, it is set and remains set for all future key events, until it is explicitly unset. A latched modifier is set, but automatically unsets after the next key event that does not change the keyboard state. Locked and latched modifier state can be changed by keyboard activity or via Xkb extension library functions.

The Xkb extension provides support for *keysym groups* , as defined by ISO9995:

Group A logical state of a keyboard providing access to a collection of characters. A group usually contains a set of characters that logically belong together and that may be arranged on several shift levels within that group.

The Xkb extension supports up to four keysym groups. Groups are named beginning with one and indexed beginning with zero. All group states are indicated using the group index. At any point in time, there is zero or one locked group, zero or one latched group, and one base group. When a group is locked, it supersedes any previous locked group and remains the locked group for all future key events, until a new group is locked. A latched group applies only to the next key event that does not change the keyboard state. The locked and latched group can be changed by keyboard activity or via Xkb extension library functions.

Changing to a different group changes the keyboard state to produce characters from a different group. Groups are typically used to switch between keysyms of different languages and locales.

The *pointer buttons* are *Button1* - *Button5* , as defined by the core protocol.

The *base group* and *base modifiers* represent keys that are physically or logically down. These and the pointer buttons can be changed by keyboard activity and not by Xkb requests. It is possible for a key to be logically down, but not physically down, and neither latched nor locked. [1]

The *effective modifiers* are the bitwise union of the locked, latched, and the base modifiers.

[1] Keys may be logically down when they are physically up because of their electrical properties or because of the keyboard extension in the X server having filtered the key release, for esoteric reasons.

The *effective group* is the arithmetic sum of the group indices of the latched group, locked group, and base group, which is then normalized by some function. The result is a meaningful group index.

n = number of keyboard groups, 1<= n <= 4
0 <= any of locked, latched, or base group < n
effective group = f(locked group + latched group + base group)

The function f ensures that the effective group is within range. The precise function is specified for the keyboard and can be retrieved through the keyboard description. It may wrap around, clamp down, or default. Few applications will actually examine the effective group, and far fewer still will examine the locked, latched, and base groups.

There are two circumstances under which groups are normalized:

1. The global locked or effective group changes. In this case, the changed group is normalized into range according to the settings of the *groups_wrap* field of the *XkbControlsRec* structure for the keyboard (see section 10.7.1).

2. The Xkb library is interpreting an event with an effective group that is legal for the keyboard as a whole, but not for the key in question. In this case, the group to use for this event only is determined using the *group_info* field of the key symbol mapping (*XkbSymMapRec*) for the event key.

Each nonmodifier key on a keyboard has zero or more symbols, or keysyms, associated with it. These are the logical symbols that the key can generate when it is pressed. The set of all possible keysyms for a keyboard is divided into groups. Each key is associated with zero or more groups; each group contains one or more symbols. When a key is pressed, the determination of which symbol for the key is selected is based on the effective group and the shift level, which is determined by which modifiers are set.

A client that does not explicitly call Xkb functions, but that otherwise makes use of an X library containing the Xkb extension, will have keyboard state represented in bits 0 - 14 of the state field of events that report modifier and button state. Such a client is said to be *Xkb-capable* . A client that does explicitly call Xkb functions is an *Xkb-aware* client. The Xkb keyboard state includes information derived from the effective state and from two server parameters that can be set through the keyboard extension. The following components of keyboard state pertain to Xkb-capable and Xkb-aware clients:

• lookup state: lookup group and lookup modifiers

• grab state: grab group and grab modifiers

The *lookup modifiers* and *lookup group* are represented in the state field of core X events. The modifier state and keycode of a key event are used to determine the symbols associated with the event. For *KeyPress* and *KeyRelease* events, the lookup modifiers are computed as:

((base | latched | locked) & ~ *server_internal_modifiers*)

Otherwise the lookup modifiers are computed as:

(((base | latched | (locked & ~ *ignore_locks*)) & ~ *server_internal_modifiers*)

The lookup group is the same as the effective group.

When an Xkb-capable or Xkb-aware client wishes to map a keycode to a keysym, it should use the *lookup state* — the lookup group and the lookup modifiers.

The *grab state* is the state used when matching events to passive grabs. If the event activates a grab, the *grab modifiers* and *grab group* are represented in the state field of core X events; otherwise, the lookup state is used. The grab modifiers are computed as:

(((base | latched | (locked & ~ignore_locks)) & ~server_internal_modifiers)

If the server's *IgnoreGroupLock* control (see section 10.7.3) is not set, the grab group is the same as the effective group. Otherwise, the grab group is computed from the base group and latched group, ignoring the locked group.

The final three components of Xkb state are applicable to clients that are not linked with an Xlib containing the X keyboard extension library and therefore are not aware of the keyboard extension (*Xkb-unaware* clients):

- The compatibility modifier state
- The compatibility lookup modifier state
- The compatibility grab modifier state

The X11 protocol interpretation of modifiers does not include direct support for multiple groups. When an Xkb-extended X server connects to an Xkb-unaware client, the compatibility states remap the keyboard group into a core modifier whenever possible. The compatibility state corresponds to the effective modifier and effective group state, with the group remapped to a modifier. The compatibility lookup and grab states correspond to the lookup and grab states, respectively, with the group remapped to a modifier. The compatibility lookup state is reported in events that do not trigger passive grabs; otherwise, the compatibility grab state is reported.

Changing the Keyboard State

Changing Modifiers

The functions in this section that change the use of modifiers use a mask in the parameter *affect* . It is a bitwise inclusive OR of the legal modifier masks:

Table 5.1. Real Modifier Masks

Mask
ShiftMask
LockMask
ControlMask
Mod1Mask
Mod2Mask
Mod3Mask
Mod4Mask
Mod5Mask

To lock and unlock any of the eight real keyboard modifiers, use *XkbLockModifiers:*

```
Bool XkbLockModifiers ( display, device_spec, affect, values )
Display * display ; /* connection to the X server */
unsigned int device_spec ; /* device ID, or XkbUseCoreKbd */
unsigned int affect ; /* mask of real modifiers whose lock state is to change */
unsigned int values ; /* 1 => lock, 0 => unlock; only for modifiers selected by
affect */
```

XkbLockModifiers sends a request to the server to lock the real modifiers selected by both *affect* and *values* and to unlock the real modifiers selected by *affect* but not selected by *values* . *XkbLockModifiers* does not wait for a reply from the server. It returns *True* if the request was sent, and *False* otherwise.

To latch and unlatch any of the eight real keyboard modifiers, use *XkbLatchModifiers:*

```
Bool XkbLatchModifiers (d isplay, device_spec, affect, values )
Display * display ; /* connection to the X server */
unsigned int device_spec ; /* device ID, or XkbUseCoreKbd */
unsigned int affect ; /* mask of modifiers whose latch state is to change */
unsigned int values; /* 1 => latch, 0 => unlatch; only for mods selected by affect */
```

XkbLatchModifiers sends a request to the server to latch the real modifiers selected by both *affect* and *values* and to unlatch the real modifiers selected by *affect* but not selected by *values* . *XkbLatchModifiers* does not wait for a reply from the server. It returns *True* if the request was sent, and *False* otherwise.

Changing Groups

Reference the keysym group indices with these symbolic constants:

Table 5.2. Symbolic Group Names

Symbolic Name	Value
XkbGroup1Index	0
XkbGroup2Index	1
XkbGroup3Index	2
XkbGroup4Index	3

To lock the keysym group, use *XkbLockGroup.*

Bool *XkbLockGroup* (*display, device_spec, group*)
Display * *display* ; /* connection to the X server */
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
unsigned int *group* ; /* index of the keysym group to lock */

XkbLockGroup sends a request to the server to lock the specified *group* and does not wait for a reply. It returns *True* if the request was sent and *False* otherwise.

To latch the keysym group, use *XkbLatchGroup.*

Bool *XkbLatchGroup* (*display, device_spec, group*)
Display * *display* ; /* connection to the X server */
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
unsigned int *group* ; /* index of the keysym group to latch */

XkbLatchGroup sends a request to the server to latch the specified group and does not wait for a reply. It returns *True* if the request was sent and *False* otherwise.

Determining Keyboard State

Xkb keyboard state may be represented in an *XkbStateRec* structure:

```
typedef struct {
      unsigned char           group;              /* effective group index */
      unsigned char           base_group;         /* base group index */
      unsigned char           latched_group;      /* latched group index */
      unsigned char           locked_group;       /* locked group index */
      unsigned char           mods;               /* effective modifiers */
      unsigned char           base_mods;          /* base modifiers */
      unsigned char           latched_mods;       /* latched modifiers */
      unsigned char           locked_mods;        /* locked modifiers */
      unsigned char           compat_state;       /* effective group => modifie
      unsigned char           grab_mods;          /* modifiers used for grabs *
      unsigned char           compat_grab_mods;   /* mods used for compatibilit
      unsigned char           lookup_mods;        /* modifiers used to lookup s
      unsigned char           compat_lookup_mods; /* mods used for compatibilit
      unsigned short           ptr_buttons;       /* 1 bit => corresponding poi
}
XkbStateRec
```

```
,*XkbStatePtr;
```

To obtain the keyboard state, use *XkbGetState.*

Status *XkbGetState* (*display* , *device_spec* , *state_return*)
Display * *display* ; /* connection to the X server */
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
XkbStatePtr *state_return* ; /* backfilled with Xkb state */

The *XkbGetState* function queries the server for the current keyboard state, waits for a reply, and then backfills *state_return* with the results.

All group values are expressed as group indices in the range [0..3]. Modifiers and the compatibility modifier state values are expressed as the bitwise union of the core X11 modifier masks. The pointer button state is reported as in the core X11 protocol.

Tracking Keyboard State

The Xkb extension reports *XkbStateNotify* events to clients wanting notification whenever the Xkb state changes. The changes reported include changes to any aspect of the keyboard state: when a modifier is set or unset, when the current group changes, or when a pointer button is pressed or released. As with all Xkb events, *XkbStateNotify* events are reported to all interested clients without regard to the current keyboard input focus or grab state.

There are many different types of Xkb state changes. Xkb defines an event detail mask corresponding to each type of change. The event detail masks are listed in Table 5.3.

Table 5.3. XkbStateNotify Event Detail Masks

Mask	Value
XkbModifierStateMask	(1L << 0)
XkbModifierBaseMask	(1L << 1)
XkbModifierLatchMask	(1L << 2)
XkbModifierLockMask	(1L << 3)
XkbGroupStateMask	(1L << 4)
XkbGroupBaseMask	(1L << 5)
XkbGroupLatchMask	(1L << 6)
XkbGroupLockMask	(1L << 7)
XkbCompatStateMask	(1L << 8)
XkbGrabModsMask	(1L << 9)
XkbCompatGrabModsMask	(1L << 10)
XkbLookupModsMask	(1L << 11)
XkbCompatLookupModsMask	(1L << 12)
XkbPointerButtonMask	(1L << 13)
XkbAllStateComponentsMask	(0x3fff)

To track changes in the keyboard state for a particular device, select to receive *XkbStateNotify* events by calling either *XkbSelectEvents* or *XkbSelectEventDetails* (see section 4.3).

To receive *XkbStateNotify* events under all possible conditions, use *XkbSelectEvents* and pass *XkbStateNotifyMask* in both *bits_to_change* and *values_for_bits* .

To receive *XkbStateNotify* events only under certain conditions, use *XkbSelectEventDetails* using *XkbStateNotify* as the *event_type* and specifying the desired state changes in *bits_to_change* and *values_for_bits* using mask bits from Table 5.3.

The structure for *XkbStateNotify* events is:

```
typedef struct {
      int            type;           /* Xkb extension base event code */
      unsigned long  serial;         /* X server serial number for event */
      Bool           send_event;     /*  True => synthetically generated */
      Display *      display;        /* server connection where event generated *
      Time           time;           /* server time when event generated */
      int            xkb_type;       /*  XkbStateNotify */
      int            device;         /* Xkb device ID, will not be  XkbUseCoreKbd
      unsigned int   changed;        /* bits indicating what has changed */
      int            group;          /* group index of effective group */
      int            base_group;     /* group index of base group */
      int            latched_group;  /* group index of latched group */
      int            locked_group;   /* group index of locked group */
      unsigned int   mods;           /* effective modifiers */
      unsigned int   base_mods;      /* base modifiers */
      unsigned int   latched_mods;   /* latched modifiers */
      unsigned int   locked_mods;    /* locked modifiers */
      int            compat_state;   /* computed compatibility state */
      unsigned char  grab_mods;      /* modifiers used for grabs */
      unsigned char  compat_grab_mods;  /* modifiers used for compatibility grabs
      unsigned char  lookup_mods;    /* modifiers used to lookup symbols */
      unsigned char  compat_lookup_mods;                 /* mods used for compati
      int            ptr_buttons;    /* core pointer buttons */
      KeyCode        keycode;        /* keycode causing event, 0 if programmatic
      char           event_type;     /* core event if  req_major or
                                        req_minor non zero */
      char           req_major;      /* major request code if program trigger, el
      char           req_minor;      /* minor request code if program trigger, el
} XkbStateNotifyEvent
;
```

When you receive an *XkbStateNotify* event, the *changed* field indicates which elements of keyboard state have changed. This will be the bitwise inclusive OR of one or more of the *XkbStateNotify* event detail masks shown in Table 5.3. All fields reported in the event are valid, but only those indicated in *changed* have changed values.

The *group* field is the group index of the effective keysym group. The *base_group* , *latched_group* , and *locked_group* fields are set to a group index value representing

the base group, the latched group, and the locked group, respectively. The X server can set the modifier and compatibility state fields to a union of the core modifier mask bits; this union represents the corresponding modifier states. The *ptr_button* field gives the state of the core pointer buttons as a mask composed of an inclusive OR of zero or more of the core pointer button masks.

Xkb state changes can occur either in response to keyboard activity or under application control. If a key event caused the state change, the *keycode* field gives the keycode of the key event, and the *event_type* field is set to either *KeyPress* or *KeyRelease* . If a pointer button event caused the state change, the *keycode* field is zero, and the *event_type* field is set to either *ButtonPress* or *ButtonRelease* . Otherwise, the major and minor codes of the request that caused the state change are given in the *req_major* and *req_minor* fields, and the *keycode* field is zero. The *req_major* value is the same as the major extension opcode.

Chapter 6. Complete Keyboard Description

The complete Xkb description for a keyboard device is accessed using a single structure containing pointers to major Xkb components. This chapter describes this single structure and provides references to other sections of this document that discuss the major Xkb components in detail.

The XkbDescRec Structure

The complete description of an Xkb keyboard is given by an *XkbDescRec* . The component structures in the *XkbDescRec* represent the major Xkb components outlined in Figure 1.1.

```
typedef struct {
      struct _XDisplay *                  display;            /* connection to
X server */
      unsigned short                  flags;            /* private to Xkb, do
not modify */
      unsigned short                  device_spec;            /* device of
interest */
      KeyCode                 min_key_code;            /* minimum keycode for
device */
      KeyCode                 max_key_code;            /* maximum keycode for
device */
      XkbControlsPtr                  ctrls;            /* controls */
      XkbServerMapPtr                  server;           /* server keymap */
      XkbClientMapPtr                  map;           /* client keymap */
      XkbIndicatorPtr                  indicators;            /* indicator map
*/
      XkbNamesPtr                 names;           /* names for all
components */
      XkbCompatMapPtr                  compat;           /* compatibility map
*/
      XkbGeometryPtr                  geom;           /* physical geometry of
keyboard */
}
XkbDescRec
, *XkbDescPtr;
```

The *display* field points to an X display structure. The *flags* field is private to the library: modifying *flags* may yield unpredictable results. The *device_spec* field specifies the device identifier of the keyboard input device, or *XkbUseCoreKeyboard* , which specifies the core keyboard device. The *min_key_code* and *max_key_code* fields specify the least and greatest keycode that can be returned by the keyboard.

The other fields specify structure components of the keyboard description and are described in detail in other sections of this document. Table 6.1 identifies the subsequent sections of this document that discuss the individual components of the *XkbDescRec* .

Table 6.1. XkbDescRec Component References

XkbDescRec Field	For more info
ctrls	Chapter 10
server	Chapter 16
map	Chapter 15
indicators	Chapter 8
names	Chapter 18
compat	Chapter 17
geom	Chapter 13

Each structure component has a corresponding mask bit that is used in function calls to indicate that the structure should be manipulated in some manner, such as allocating it or freeing it. These masks and their relationships to the fields in the *XkbDescRec* are shown in Table 6.2.

Table 6.2. Mask Bits for XkbDescRec

Mask Bit	XkbDescRec Field	Value
XkbControlsMask	ctrls	(1L<<0)
XkbServerMapMask	server	(1L<<1)
XkbIClientMapMask	map	(1L<<2)
XkbIndicatorMapMask	indicators	(1L<<3)
XkbNamesMask	names	(1L<<4)
XkbCompatMapMask	compat	(1L<<5)
XkbGeometryMask	geom	(1L<<6)
XkbAllComponentsMask	All Fields	(0x7f)

Obtaining a Keyboard Description from the Server

To retrieve one or more components of a keyboard device description, use *XkbGetKeyboard* (see also *XkbGetKeyboardbyName*).

XkbDescPtr *XkbGetKeyboard* (*display, which, device_spec*)

Display * *display* ; /* connection to X server */

unsigned int *which* ; /* mask indicating components to return */

unsigned int *device_spec* ; /* device for which to fetch description, or *XkbUseCoreKbd* */

XkbGetKeyboard allocates and returns a pointer to a keyboard description. It queries the server for those components specified in the *which* parameter for device *device_spec* and copies the results to the *XkbDescRec* it allocated. The remaining fields in the keyboard description are set to *NULL* . The valid masks for *which* are those listed in Table 6.2.

XkbGetKeyboard can generate *BadAlloc* protocol errors.

To free the returned keyboard description, use *XkbFreeKeyboard* (see section 6.4).

Tracking Changes to the Keyboard Description in the Server

The server can generate events whenever its copy of the keyboard description for a device changes. Refer to section 14.4 for detailed information on tracking changes to the keyboard description.

Allocating and Freeing a Keyboard Description

Applications seldom need to directly allocate a keyboard description; calling *XkbGetKeyboard* usually suffices. In the event you need to create a keyboard description from scratch, however, use *XkbAllocKeyboard* rather than directly calling *malloc* or *Xmalloc* .

XkbDescRec * *XkbAllocKeyboard* (void)

If *XkbAllocKeyboard* fails to allocate the keyboard description, it returns *NULL* . Otherwise, it returns a pointer to an empty keyboard description structure. The *device_spec* field will have been initialized to *XkbUseCoreKbd* . You may then either fill in the structure components or use Xkb functions to obtain values for the structure components from a keyboard device.

To destroy either an entire an *XkbDescRec* or just some of its members, use *XkbFreeKeyboard.*

void *XkbFreeKeyboard* (*xkb, which, free_all*)
XkbDescPtr *xkb* ; /* keyboard description with components to free */
unsigned int *which* ; /* mask selecting components to free */
Bool *free_all* ; /* *True* => free all components and *xkb* */

XkbFreeKeyboard frees the components of *xkb* specified by *which* and sets the corresponding values to *NULL* . If *free_all* is *True* , *XkbFreeKeyboard* frees every non- *NULL* component of *xkb* and then frees the *xkb* structure itself.

Chapter 7. Virtual Modifiers

The core protocol specifies that certain keysyms, when bound to modifiers, affect the rules of keycode to keysym interpretation for all keys; for example, when the *Num_Lock* keysym is bound to some modifier, that modifier is used to select between shifted and unshifted state for the numeric keypad keys. The core protocol does not provide a convenient way to determine the mapping of modifier bits (in particular *Mod1* through *Mod5*) to keysyms such as *Num_Lock* and *Mode_switch* . Using the core protocol only, a client application must retrieve and search the modifier map to determine the keycodes bound to each modifier, and then retrieve and search the keyboard mapping to determine the keysyms bound to the keycodes. It must repeat this process for all modifiers whenever any part of the modifier mapping is changed.

Xkb alleviates these problems by defining virtual modifiers. In addition to the eight core modifiers, referred to as the *real modifiers* , Xkb provides a set of sixteen named *virtual modifiers* . Each virtual modifier can be bound to any set of the real modifiers (*Shift* , *Lock* , *Control,* and *Mod1* - *Mod5*).

The separation of function from physical modifier bindings makes it easier to specify more clearly the intent of a binding. X servers do not all assign modifiers the same way — for example, *Num_Lock* might be bound to *Mod2* for one vendor and to *Mod4* for another. This makes it cumbersome to automatically remap the keyboard to a desired configuration without some kind of prior knowledge about the keyboard layout and bindings. With XKB, applications can use virtual modifiers to specify the desired behavior, without regard for the actual physical bindings in effect.

Virtual Modifier Names and Masks

Virtual modifiers are named by converting their string name to an X *Atom* and storing the Atom in the *names.vmods* array in an *XkbDescRec* structure (see section 6.1). The position of a name Atom in the *names.vmods* array defines the bit position used to represent the virtual modifier and also the index used when accessing virtual modifier information in arrays: the name in the i-th (0 relative) entry of *names.vmods* is the i-th virtual modifier, represented by the mask (1<<i). Throughout Xkb, various functions have a parameter that is a mask representing virtual modifier choices. In each case, the i-th bit (0 relative) of the mask represents the i-th virtual modifier.

To set the name of a virtual modifier, use *XkbSetNames* , using *XkbVirtualMod-NamesMask* in *which* and the name in the *xkb* argument; to retrieve indicator names, use *XkbGetNames* . These functions are discussed in Chapter 18.

Modifier Definitions

An Xkb *modifier definition* enumerates a collection of real and virtual modifiers but does not in itself bind those modifiers to any particular key or to each other. Modifier definitions are included in a number of structures in the keyboard description to define the collection of modifiers that affect or are affected by some other entity. A modifier definition is relevant only in the context of some other entity such as an indicator map, a control, or a key type. (See sections 8.2.2, 10.8, and 15.2.)

```
typedef struct _XkbMods {
```

```
      unsigned char           mask;           /* real_mods | vmods mapped to
real modifiers */
      unsigned char           real_mods;           /* real modifier bits */
      unsigned short            vmods;           /* virtual modifier bits */
}
XkbModsRec
,*XkbModsPtr;
```

An Xkb modifier definition consists of a set of bit masks corresponding to the eight real modifiers (*real_mods*); a similar set of bitmasks corresponding to the 16 named virtual modifiers (*vmods*); and an effective mask (*mask*). The effective mask represents the set of all real modifiers that can logically be set either by setting any of the real modifiers or by setting any of the virtual modifiers in the definition. *mask* is derived from the real and virtual modifiers and should never be explicitly changed — it contains all of the real modifiers specified in the definition (*real_mods*) *plus* any real modifiers that are bound to the virtual modifiers specified in the definition (*vmods*). The binding of the virtual modifiers to real modifiers is exterior to the modifier definition. Xkb automatically recomputes the mask field of modifier definitions as necessary. Whenever you access a modifier definition that has been retrieved using an Xkb library function, the mask field will be correct for the keyboard mapping of interest.

Binding Virtual Modifiers to Real Modifiers

The binding of virtual modifiers to real modifiers is defined by the *server.vmods* array in an *XkbDescRec* structure. Each entry contains the real modifier bits that are bound to the virtual modifier corresponding to the entry. The overall relationship of fields dealing with virtual modifiers in the server keyboard description are shown in Figure 16.2.

Virtual Modifier Key Mapping

Xkb maintains a *virtual modifier mapping* , which lists the virtual modifiers associated with, or bound to, each key. The real modifiers bound to a virtual modifier always include all of the modifiers bound to any of the keys that specify that virtual modifier in their virtual modifier mapping. The *server.vmodmap* array indicates which virtual modifiers are bound to each key; each entry is a bitmask for the virtual modifier bits. The *server.vmodmap* array is indexed by keycode.

The *vmodmap* and *vmods* members of the server map are the "master" virtual modifier definitions. Xkb automatically propagates any changes to these fields to all other fields that use virtual modifier mappings (see section 16.4).

For example, if *Mod3* is bound to the *Num_Lock* key by the core protocol modifier mapping, and the *NumLock* virtual modifier is bound to they *Num_Lock* key by the virtual modifier mapping, *Mod3* is added to the set of modifiers associated with *NumLock* .

The virtual modifier mapping is normally updated whenever actions are automatically applied to symbols (see section 16.4 for details), and few applications should need to change the virtual modifier mapping explicitly.

Use *XkbGetMap* (see section 14.2) to get the virtual modifiers from the server or use *XkbGetVirtualMods* (see section 16.4.1) to update a local copy of the virtual

modifiers bindings from the server. To set the binding of a virtual modifier to a real modifier, use *XkbSetMap* (see section 14.3 *).*

To determine the mapping of virtual modifiers to core X protocol modifiers, use *XkbVirtualModsToReal* .

Bool *XkbVirtualModsToReal* (*xkb, virtual_mask, mask_rtrn*)
XkbDescPtr *xkb* ; /* keyboard description for input device */
unsigned int *virtual_mask* ; /* virtual modifier mask to translate */
unsigned int * *mask_rtrn* ; /* backfilled with real modifiers */

If the keyboard description defined by *xkb* includes bindings for virtual modifiers, *XkbVirtualModsToReal* uses those bindings to determine the set of real modifiers that correspond to the set of virtual modifiers specified in *virtual_mask* . The *virtual_mask* parameter is a mask specifying the virtual modifiers to translate; the i-th bit (0 relative) of the mask represents the i-th virtual modifier. If *mask_rtrn* is non- *NULL* , *XkbVirtualModsToReal* backfills it with the resulting real modifier mask. If the keyboard description in *xkb* does not include virtual modifier bindings, *XkbVirtualModsToReal* returns *False* ; otherwise, it returns *True* .

Note

It is possible for a local (client-side) keyboard description (the *xkb* parameter) to not contain any virtual modifier information (simply because the client has not requested it) while the server's corresponding definition may contain virtual modifier information.

Inactive Modifier Sets

An unbound virtual modifier is one that is not bound to any real modifier (*server -> vmods* [virtual_modifier_index] is zero).

Some Xkb operations ignore modifier definitions in which the virtual modifiers are unbound. Consider this example:

```
if (state matches {Shift}) Do OneThing;
if (state matches {Shift+NumLock}) Do Another;
```

If the *NumLock* virtual modifier is not bound to any real modifiers, the effective masks for these two cases are identical (that is, contain only *Shift*). When it is essential to distinguish between *OneThing* and Another, Xkb considers only those modifier definitions for which all virtual modifiers are bound.

Conventions

The Xkb extension does not require any specific virtual modifier names. However, everyone benefits if the same names are used for common modifiers. The following names are suggested:

NumLock

ScrollLock
Alt
Meta
AltGr
LevelThree

Example

If the second (0-relative) entry in *names.vmods* contains the Atom for "NumLock", then 0x4 (1<<2) is the virtual modifier bit for the *NumLock* virtual modifier. If *server.vmods* [2] contains *Mod3Mask* , then the *NumLock* virtual modifier is bound to the *Mod3* real modifier.

A virtual modifier definition for this example would have:

```
real_mods = 0
vmods = 0x4 (NumLock named virtual modifier)
mask = 0x20 (Mod3Mask)
```

Continuing the example, if the keyboard has a *Num_Lock* keysym bound to the key with keycode 14, and the *NumLock* virtual modifier is bound to this key, *server.vmodmap* [14] contains 0x4.

Finally, if the keyboard also used the real *Mod1* modifier for numeric lock operations, the modifier definition below would represent the situation where either the key bound to *Mod1* or the *NumLock* virtual modifier could be used for this purpose:

```
real_mods = 0x8 (Mod1Mask)
vmods = 0x4 (NumLock named virtual modifier)
mask = 0x28 (Mod1Mask | Mod3Mask)
```

Chapter 8. Indicators

Although the core X implementation supports up to 32 LEDs on an input device, it does not provide any linkage between the state of the LEDs and the logical state of the input device. For example, most keyboards have a *CapsLock* LED, but X does not provide a mechanism to make the LED automatically follow the logical state of the *CapsLock* key.

Furthermore, the core X implementation does not provide clients with the ability to determine what bits in the *led_mask* field of the *XKeyboardState* map to the particular LEDs on the keyboard. For example, X does not provide a method for a client to determine what bit to set in the *led_mask* field to turn on the *Scroll Lock* LED or whether the keyboard even has a *Scroll Lock* LED.

Xkb provides indicator names and programmable indicators to help solve these problems. Using Xkb, clients can determine the names of the various indicators, determine and control the way that the individual indicators should be updated to reflect keyboard changes, and determine which of the 32 keyboard indicators reported by the protocol are actually present on the keyboard. Clients may also request immediate notification of changes to the state of any subset of the keyboard indicators, which makes it straightforward to provide an on-screen "virtual" LED panel. This chapter describes Xkb indicators and the functions used for manipulating them.

Indicator Names

Xkb provides the capability of symbolically naming indicators. Xkb itself doesn't use these symbolic names for anything; they are there only to help make the keyboard description comprehensible to humans. To set the names of specific indicators, use *XkbSetNames* as discussed in Chapter 18. Then set the map using *XkbSetMap* (see section 14.3) or *XkbSetNamedIndicator* (below). To retrieve indicator names, use *XkbGetNames* (Chapter 18).

Indicator Data Structures

Use the indicator description record, *XkbIndicatorRec* , and its indicator map, *XkbIndicatorMapRec* , to inquire about and control most indicator properties and behaviors.

XkbIndicatorRec

The description for all the Xkb indicators is held in the *indicators* field of the complete keyboard description (see Chapter 6), which is defined as follows:

```
#define      XkbNumIndicators      32

typedef struct {
      unsigned long                   phys_indicators;        /* LEDs existence */
```

```
      XkbIndicatorMapRec              maps[XkbNumIndicators]; /* indicator maps */
} XkbIndicatorRec,*XkbIndicatorPtr;
```

This structure contains the *phys_indicators* field, which relates some information about the correspondence between indicators and physical LEDs on the keyboard, and an array of indicator *maps* , one map per indicator.

The *phys_indicators* field indicates which indicators are bound to physical LEDs on the keyboard; if a bit is set in *phys_indicators* , then the associated indicator has a physical LED associated with it. This field is necessary because some indicators may not have corresponding physical LEDs on the keyboard. For example, most keyboards have an LED for indicating the state of *CapsLock* , but most keyboards do not have an LED that indicates the current group. Because *phys_indicators* describes a physical characteristic of the keyboard, you cannot directly change it under program control. However, if a client program loads a completely new keyboard description via *XkbGetKeyboardByName* , or if a new keyboard is attached and the X implementation notices, *phys_indicators* changes if the indicators for the new keyboard are different.

XkbIndicatorMapRec

Each indicator has its own set of attributes that specify whether clients can explicitly set its state and whether it tracks the keyboard state. The attributes of each indicator are held in the *maps* array, which is an array of *XkbIndicatorRec* structures:

```
typedef struct {
      unsigned char    flags;         /* how the indicator can be changed */
      unsigned char    which_groups;  /* match criteria for groups */
      unsigned char    groups;        /* which keyboard groups the indicator watch
      unsigned char    which_mods;    /* match criteria for modifiers */
      XkbModsRec       mods;          /* which modifiers the indicator watches */
      unsigned int     ctrls;         /* which controls the indicator watches */
} XkbIndicatorMapRec, *XkbIndicatorMapPtr;
```

This indicator map specifies for each indicator:

- The conditions under which the keyboard modifier state affects the indicator
- The conditions under which the keyboard group state affects the indicator
- The conditions under which the state of the boolean controls affects the indicator
- The effect (if any) of attempts to explicitly change the state of the indicator using the functions *XkbSetControls* or *XChangeKeyboardControl*

For more information on the effects of explicit changes to indicators and the relationship to the indicator map, see section 8.4.1.

XkbIndicatorMapRec flags field

The *flags* field specifies the conditions under which the indicator can be changed and the effects of changing the indicator. The valid values for *flags* and their effects are shown in Table 8.1.

Table 8.1. XkbIndicatorMapRec flags Field

Value		Effect
XkbIM_NoExplicit	(1L<<7)	Client applications cannot change the state of the indicator.
XkbIM_NoAutomatic	(1L<<6)	Xkb does not automatically change the value of the indicator based upon a change in the keyboard state, regardless of the values for the other fields of the indicator map.
XkbIM_LEDDrivesKB	(1L<<5)	A client application changing the state of the indicator causes the state of the keyboard to change.

Note that if *XkbIM_NoAutomatic* is not set, by default the indicator follows the keyboard state.

If *XkbIM_LEDDrivesKB* is set and *XkbIM_NoExplicit* is not, and if you call a function which updates the server's image of the indicator map (such as *XkbSetIndicatorMap* or *XkbSetNamedIndicator*), Xkb changes the keyboard state and controls to reflect the other fields of the indicator map, as described in the remainder of this section. If you attempt to explicitly change the value of an indicator for which *XkbIM_LEDDrivesKB* is absent or for which *XkbIM_NoExplicit* is present, keyboard state or controls are unaffected.

For example, a keyboard designer may want to make the *CapsLock* LED controllable only by the server, but allow the *Scroll Lock* LED to be controlled by client applications. To do so, the keyboard designer could set the *XkbIM_NoExplicit* flag for the *CapsLock* LED, but not set it for the *Scroll Lock* LED. Or the keyboard designer may wish to allow the *CapsLock* LED to be controlled by both the server and client applications and also have the server to automatically change the *CapsLock* modifier state whenever a client application changes the *CapsLock* LED. To do so, the keyboard designer would not set the *XkbIM_NoExplicit* flag, but would instead set the *XkbIM_LEDDrivesKB* flag.

The remaining fields in the indicator map specify the conditions under which Xkb automatically turns an indicator on or off (only if *XkbIM_NoAutomatic* is not set). If these conditions match the keyboard state, Xkb turns the indicator on. If the conditions do not match, Xkb turns the indicator off.

XkbIndicatorMapRec which_groups and groups fields

The *which_groups* and the *groups* fields of an indicator map determine how the keyboard group state affects the corresponding indicator. The *which_groups* field controls the interpretation of *groups* and may contain any one of the following values:

```
#define XkbIM_UseNone             0
#define XkbIM_UseBase             (1L << 0)
#define XkbIM_UseLatched          (1L << 1)
#define XkbIM_UseLocked           (1L << 2)
#define XkbIM_UseEffective        (1L << 3)
```

```
#define XkbIM_UseAnyGroup         XkbIM_UseLatched | XkbIM_UseLocked |
                                  XkbIM_UseEffective
```

The *groups* field specifies what keyboard groups an indicator watches and is the bitwise inclusive OR of the following valid values:

```
#define XkbGroup1Mask             (1<<0)
#define XkbGroup2Mask             (1<<1)
#define XkbGroup3Mask             (1<<2)
#define XkbGroup4Mask             (1<<3)
#define XkbAnyGroupMask           (1<<7)
#define XkbAllGroupsMask          (0xf)
```

If *XkbIM_NoAutomatic* is not set (the keyboard drives the indicator), the effect of *which_groups* and *groups* is shown in Table 8.2.

Table 8.2. XkbIndicatorMapRec which_groups and groups, Keyboard Drives Indicator

which_groups	Effect
XkbIM_UseNone	The *groups* field and the current keyboard group state are ignored.
XkbIM_UseBase	If *groups* is nonzero, the indicator is lit whenever the base keyboard group is nonzero. If *groups* is zero, the indicator is lit whenever the base keyboard group is zero.
XkbIM_UseLatched	If *groups* is nonzero, the indicator is lit whenever the latched keyboard group is nonzero. If *groups* is zero, the indicator is lit whenever the latched keyboard group is zero.
XkbIM_UseLocked	The *groups* field is interpreted as a mask. The indicator is lit when the current locked keyboard group matches one of the bits that are set in *groups*.
XkbIM_UseEffective	The *groups* field is interpreted as a mask. The indicator is lit when the current effective keyboard group matches one of the bits that are set in *groups* .

The effect of *which_groups* and *groups* when you change an indicator for which *XkbIM_LEDDrivesKB* is set (the indicator drives the keyboard) is shown in Table 8.3. The "New State" column refers to the new state to which you set the indicator.

Table 8.3. XkbIndicatorMapRec which_groups and groups, Indicator Drives Keyboard

which_groups	New State	Effect on Keyboard Group State
XkbIM_UseNone	On or Off	No effect
XkbIM_UseBase	On or Off	No effect
XkbIM_UseLatched	On	The *groups* field is treated as a group mask. The keyboard group latch is changed to the lowest numbered group specified in *groups* ; if *groups* is empty, the keyboard group latch is changed to zero.
XkbIM_UseLatched	Off	The *groups* field is treated as a group mask. If the indicator is explicitly extinguished, keyboard group latch is changed to the lowest numbered group not specified in *groups* ; if *groups* is zero, the keyboard group latch is set to the index of the highest legal keyboard group.
XkbIM_UseLocked or XkbIM_UseEffective	On	If the *groups* mask is empty, group is not changed; otherwise, the locked keyboard group is changed to the lowest numbered group specified in *groups*.
XkbIM_UseLocked or XkbIM_UseEffective	Off	Locked keyboard group is changed to the lowest numbered group that is not specified in the *groups* mask, or to *Group1* if the *groups* mask contains all keyboard groups.

XkbIndicatorMapRec which_mods and mods fields

The *mods* field specifies what modifiers an indicator watches. The *mods* field is an Xkb modifier definition, *XkbModsRec* , as described in section 7.2, which can specify both real and virtual modifiers. The *mods* field takes effect even if some or all of the virtual indicators specified in *mods* are unbound. To specify the mods field, in general, assign the modifiers of interest to *mods.real_mods* and the virtual modifiers of interest to *mods.vmods* . You can disregard the *mods.mask* field unless your application needs to interpret the indicator map directly (that is, to simulate automatic indicator behavior on its own). Relatively few applications need to do so, but if you find it necessary, you can either read the indicator map back from the server after you update it (the server automatically updates the mask field whenever any of the real or virtual modifiers are changed in the modifier definition) or you can use *XkbVirtualModsToReal* to determine the proper contents for the mask field, assuming that the *XkbDescRec* contains the virtual modifier definitions.

which_mods specifies what criteria Xkb uses to determine a match with the corresponding *mods* field by specifying one or more components of the Xkb keyboard state. If *XkbIM_NoAutomatic* is not set (the keyboard drives the indicator), the indicator is lit whenever any of the modifiers specified in the *mask* field of the *mods* modifier definition are also set in any of the current keyboard state components specified by *which_mods* . Remember that the *mask* field is comprised of all of the

real modifiers specified in the definition plus any real modifiers that are bound to the virtual modifiers specified in the definition. (See Chapter 5 for more information on the keyboard state and Chapter 7 for more information on virtual modifiers.) Use a bitwise inclusive OR of the following values to compose a value for *which_mods*:

```
#define XkbIM_UseNone             0
#define XkbIM_UseBase             (1L << 0)
#define XkbIM_UseLatched          (1L << 1)
#define XkbIM_UseLocked           (1L << 2)
#define XkbIM_UseEffective        (1L << 3)
#define XkbIM_UseCompat           (1L << 4)
#define XkbIM_UseAnyMods          XkbIM_UseBase | XkbIM_UseLatched |
                                  XkbIM_UseLocked | XkbIM_UseEffective |
                                  XkbIM_UseCompat
```

If *XkbIM_NoAutomatic* is not set (the keyboard drives the indicator), the effect of *which_mods* and *mods* is shown in Table 8.4

Table 8.4. XkbIndicatorMapRec which_mods and mods, Keyboard Drives Indicator

which_mods	Effect on Keyboard Modifiers
XkbIM_UseNone	The mods field and the current keyboard modifier state are ignored.
XkbIM_UseBase	The indicator is lit when any of the modifiers specified in the *mask* field of *mods* are on in the keyboard base state. If both *mods.real_mods* and *mods.vmods* are zero, the indicator is lit when the base keyboard state contains no modifiers.
XkbIM_UseLatched	The indicator is lit when any of the modifiers specified in the *mask* field of *mods* are latched. If both *mods.real_mods* and *mods.vmods* are zero, the indicator is lit when none of the modifier keys are latched.
XkbIM_UseLocked	The indicator is lit when any of the modifiers specified in the *mask* field of *mods* are locked. If both *mods.real_mods* and *mods.vmods* are zero, the indicator is lit when none of the modifier keys are locked.
XkbIM_UseEffective	The indicator is lit when any of the modifiers specified in the *mask* field of *mods* are in the effective keyboard state. If both *mods.real_mods* and *mods.vmods* are zero, the indicator is lit when the effective keyboard state contains no modifiers.
XkbIM_UseCompat	The indicator is lit when any of the modifiers specified in the *mask* field of *mods* are in the keyboard compatibility state. If both *mods.real_mods* and *mods.vmods* are zero, the indicator is lit when the keyboard compatibility state contains no modifiers.

The effect on the keyboard modifiers of *which_mods* and *mods* when you change an indicator for which *XkbIM_LEDDrivesKB* is set (the indicator drives the keyboard)

is shown in Table 8.5. The "New State" column refers to the new state to which you set the indicator.

Table 8.5. XkbIndicatorMapRec which_mods and mods, Indicator Drives Keyboard

which_mods	New State	Effect on Keyboard Modifiers
XkbIM_UseNone or XkbIM_UseBase	On or Off	No Effect
XkbIM_UseLatched	On	Any modifiers specified in the *mask* field of *mods* are added to the latched modifiers.
XkbIM_UseLatched	Off	Any modifiers specified in the *mask* field of *mods* are removed from the latched modifiers.
XkbIM_UseLocked, XkbIM_UseCompat, or XkbIM_UseEffective	On	Any modifiers specified in the *mask* field of *mods* are added to the locked modifiers.
XkbIM_UseLocked	Off	Any modifiers specified in the *mask* field of *mods* are removed from the locked modifiers.
XkbIM_UseCompat or XkbIM_UseEffective	Off	Any modifiers specified in the *mask* field of *mods* are removed from both the locked and latched modifiers.

XkbIndicatorMapRec ctrls field

The *ctrls* field specifies what controls (see Chapter 10) the indicator watches and is composed using the bitwise inclusive OR of the following values:

```
#define XkbRepeatKeysMask           (1L << 0)
#define XkbSlowKeysMask             (1L << 1)
#define XkbBounceKeysMask           (1L << 2)
#define XkbStickyKeysMask           (1L << 3)
#define XkbMouseKeysMask            (1L << 4)
#define XkbMouseKeysAccelMask       (1L << 5)
#define XkbAccessXKeysMask          (1L << 6)
#define XkbAccessXTimeoutMask       (1L << 7)
#define XkbAccessXFeedbackMask      (1L << 8)
#define XkbAudibleBellMask          (1L << 9)
#define XkbOverlay1Mask             (1L << 10)
#define XkbOverlay2Mask             (1L << 11)
#define XkbAllBooleanCtrlsMask      (0x00001FFF)
```

Xkb lights the indicator whenever any of the boolean controls specified in *ctrls* is enabled.

Getting Information About Indicators

Xkb allows applications to obtain information about indicators using two different methods. The first method, which is similar to the core X implementation, uses a

mask to specify the indicators. The second method, which is more suitable for applications concerned with interoperability, uses indicator names. The correspondence between the indicator name and the bit position in masks is as follows: one of the parameters returned from *XkbGetNamedIndicators* is an index that is the bit position to use in any function call that requires a mask of indicator bits, as well as the indicator's index into the *XkbIndicatorRec* array of indicator maps.

Getting Indicator State

Because the state of the indicators is relatively volatile, the keyboard description does not hold the current state of the indicators. To obtain the current state of the keyboard indicators, use *XkbGetIndicatorState*.

Status *XkbGetIndicatorState* (*display* , *device_spec* , *state_return*)
Display * *display* ; /* connection to the X server */
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
unsigned int * *state_return* ; /* backfilled with a mask of the indicator state */

XkbGetIndicatorState queries the *display* for the state of the indicators on the device specified by the *device_spec* . For each indicator that is "turned on" on the device, the associated bit is set in *state_return* . If a compatible version of the Xkb extension is not available in the server, *XkbGetIndicatorState* returns a *BadMatch* error. Otherwise, it sends the request to the X server, places the state of the indicators into *state_return,* and returns *Success* . Thus the value reported by *XkbGetIndicatorState* is identical to the value reported by the core protocol.

Getting Indicator Information by Index

To get the map for one or more indicators, using a mask to specify the indicators, use *XkbGetIndicatorMap*.

Status *XkbGetIndicatorMap* (*dpy* , *which* , *desc*)
Display * *dpy* ; /* connection to the X server */
unsigned int *which* ; /* mask of indicators for which maps should be returned */
XkbDescPtr *desc* ; /* keyboard description to be updated */

XkbGetIndicatorMap obtains the maps from the server for only those indicators specified by the *which* mask and copies the values into the keyboard description specified by *desc* . If the *indicators* field of the *desc* parameter is *NULL* , *XkbGetIndicatorMap* allocates and initializes it.

XkbGetIndicatorMap can generate *BadAlloc* , *BadLength* , *BadMatch* , and *BadImplementation* errors.

To free the indicator maps, use *XkbFreeIndicatorMaps* (see section 8.6).

Getting Indicator Information by Name

Xkb also allows applications to refer to indicators by name. Use *XkbGetNames* to get the indicator names (see Chapter 18). Using names eliminates the need for

hard-coding bitmask values for particular keyboards. For example, instead of using vendor-specific constants such as *WSKBLed_ScrollLock* mask on Digital workstations or *XLED_SCROLL_LOCK* on Sun workstations, you can instead use *XkbGetNamedIndicator* to look up information on the indicator named "Scroll Lock."

Use *XkbGetNamedIndicator* to look up the indicator map and other information for an indicator by name.

Bool *XkbGetNamedIndicator* (*dpy* , *dev_spec* , *name* , *ndx_rtrn* , *state_rtrn* , *map_rtrn* , *real_rtrn*)

Display * *dpy* ; /* connection to the X server */

unsigned int *device_spec* ; /* keyboard device ID, or *XkbUseCoreKbd* */

Atom *name* ; /* name of the indicator to be retrieved */

int * *ndx_rtrn* ; /* backfilled with the index of the retrieved indicator */

Bool * *state_rtrn* ; /* backfilled with the current state of the retrieved indicator */

XkbIndicatorMapPtr *map_rtrn* ; /* backfilled with the mapping for the retrieved indicator */

Bool * *real_rtrn* ; /* backfilled with *True* if the named indicator is real (physical) */

If the device specified by *device_spec* has an indicator named *name* , *XkbGetNamedIndicator* returns *True* and populates the rest of the parameters with information about the indicator. Otherwise, *XkbGetNamedIndicator* returns *False* .

The *ndx_rtrn* field returns the zero-based index of the named indicator. This index is the bit position to use in any function call that requires a mask of indicator bits, as well as the indicator's index into the *XkbIndicatorRec* array of indicator maps. *state_rtrn* returns the current state of the named indicator (*True* = on, *False* = off). *map_rtrn* returns the indicator map for the named indicator. In addition, if the indicator is mapped to a physical LED, the *real_rtrn* parameter is set to *True* .

Each of the " *_rtrn* " arguments is optional; you can pass *NULL* for any unneeded " *_rtrn* " arguments.

XkbGetNamedIndicator can generate *BadAtom* and *BadImplementation* errors.

Changing Indicator Maps and State

Just as you can get the indicator map using a mask or using an indicator name, so you can change it using a mask or a name.

Note

You cannot change the *phys_indicators* field of the indicators structure. The only way to change the *phys_indicators* field is to change the keyboard map.

There are two ways to make changes to indicator maps and state: either change a local copy of the indicator maps and use *XkbSetIndicatorMap* or *XkbSetNamedIndicator* , or, to reduce network traffic, use an *XkbIndicatorChangesRec* structure and use *XkbChangeIndicators*.

Effects of Explicit Changes on Indicators

This section discusses the effects of explicitly changing indicators depending upon different settings in the indicator map. See Tables 8.3 and Table 8.5 for information on the effects of the indicator map fields when explicit changes are made.

If *XkbIM_LEDDrivesKB* is set and *XkbIM_NoExplicit* is not, and if you call a function that updates the server's image of the indicator map (such as *XkbSetIndicatorMap* or *XkbSetNamedIndicator*), Xkb changes the keyboard state and controls to reflect the other fields of the indicator map. If you attempt to explicitly change the value of an indicator for which *XkbIM_LEDDrivesKB* is absent or for which *XkbIM_NoExplicit* is present, keyboard state or controls are unaffected.

If neither *XkbIM_NoAutomatic* nor *XkbIM_NoExplicit* is set in an indicator map, Xkb honors any request to change the state of the indicator, but the new state might be immediately superseded by automatic changes to the indicator state if the keyboard state or controls change.

The effects of changing an indicator that drives the keyboard are cumulative; it is possible for a single change to affect keyboard group, modifiers, and controls simultaneously.

If you change an indicator for which both the *XkbIM_LEDDrivesKB* and *XkbIM_NoAutomatic* flags are specified, Xkb applies the keyboard changes specified in the other indicator map fields and changes the indicator to reflect the state that was explicitly requested. The indicator remains in the new state until it is explicitly changed again.

If the *XkbIM_NoAutomatic* flag is not set and *XkbIM_LEDDrivesKB* is set, Xkb applies the changes specified in the other indicator map fields and sets the state of the indicator to the values specified by the indicator map. Note that it is possible in this case for the indicator to end up in a different state than the one that was explicitly requested. For example, Xkb does not extinguish an indicator with *which_mods* of *XkbIM_UseBase* and *mods* of *Shift* if, at the time Xkb processes the request to extinguish the indicator, one of the *Shift* keys is physically depressed.

If you explicitly light an indicator for which *XkbIM_LEDDrivesKB* is set, Xkb enables all of the boolean controls specified in the *ctrls* field of its indicator map. Explicitly extinguishing such an indicator causes Xkb to disable all of the boolean controls specified in *ctrls* .

Changing Indicator Maps by Index

To update the maps for one or more indicators, first modify a local copy of the keyboard description, then use *XkbSetIndicatorMap* to download the changes to the server:

Bool *XkbSetIndicatorMap* (*dpy* , *which* , *desc*)

Display * *dpy* ; /* connection to the X server */

unsigned int *which* ; /* mask of indicators to change */

XkbDescPtr *desc* ; /* keyboard description from which the maps are taken */

For each bit set in the *which* parameter, *XkbSetIndicatorMap* sends the corresponding indicator map from the *desc* parameter to the server.

Changing Indicator Maps by Name

XkbSetNamedIndicator can do several related things:

- Name an indicator if it is not already named
- Toggle the state of the indicator
- Set the indicator to a specified state
- Set the indicator map for the indicator

Bool *XkbSetNamedIndicator* (*dpy* , *device_spec* , *name* , *change_state, state* , *create_new* , *map*)

Display * *dpy* ; /* connection to the X server */

unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */

Atom *name* ; /* name of the indicator to change */

Bool *change_state* ; /* whether to change the indicator state or not */

Bool *state* ; /* desired new state for the indicator */

Bool *create_new* ; /* whether a new indicator with the specified name should be created when necessary */

XkbIndicatorMapPtr *map* ; /* new map for the indicator */

If a compatible version of the Xkb extension is not available in the server, *XkbSetNamedIndicator* returns *False* . Otherwise, it sends a request to the X server to change the indicator specified by *name* and returns *True*.

If *change_state* is *True* , and the optional parameter, *state* , is not *NULL* , *XkbSetNamedIndicator* tells the server to change the state of the named indicator to the value specified by *state*.

If an indicator with the name specified by *name* does not already exist, the *create_new* parameter tells the server whether it should create a new named indicator. If *create_new* is *True* , the server finds the first indicator that doesn't have a name and gives it the name specified by *name*.

If the optional parameter, *map* , is not *NULL* , *XkbSetNamedIndicator* tells the server to change the indicator's map to the values specified in *map*.

XkbSetNamedIndicator can generate *BadAtom* and *BadImplementation* errors. In addition, it can also generate *XkbIndicatorStateNotify* (see section 8.5), *XkbIndicatorMapNotify* , and *XkbNamesNotify* events (see section 18.5).

The XkbIndicatorChangesRec Structure

The *XkbIndicatorChangesRec* identifies small modifications to the indicator map. Use it with the function *XkbChangeIndicators* to reduce the amount of traffic sent to the server.

```
typedef struct _XkbIndicatorChanges {
      unsigned int            state_changes;
```

```
      unsigned int            map_changes;
}
XkbIndicatorChangesRec,*XkbIndicatorChangesPtr;
```

The *state_changes* field is a mask that specifies the indicators that have changed state, and *map_changes* is a mask that specifies the indicators whose maps have changed.

To change indicator maps or state without passing the entire keyboard description, use *XkbChangeIndicators* .

Bool *XkbChangeIndicators* (*dpy, xkb, changes, state*)
Display * *dpy* ; /* connection to the X server */
XkbDescPtr *xkb* ; /* keyboard description from which names are to be
taken. */
XkbIndicatorChangesPtr *changes* ; /* indicators to be updated on the server */
unsigned int *state* ; /* new state of indicators listed in
changes -> state_changes */

XkbChangeIndicators copies any maps specified by *changes* from the keyboard description, *xkb* , to the server specified by *dpy* . If any bits are set in the *state_changes* field of *changes* , *XkbChangeIndicators* also sets the state of those indicators to the values specified in the *state* mask. A 1 bit in *state* turns the corresponding indicator on, a 0 bit turns it off.

XkbChangeIndicator s can generate *BadAtom* and *BadImplementation* errors. In addition, it can also generate *XkbIndicatorStateNotify* and *XkbIndicatorMapNotify* events (see section 8.5).

Tracking Changes to Indicator State or Map

Whenever an indicator changes state, the server sends *XkbIndicatorStateNotify* events to all interested clients. Similarly, whenever an indicator's map changes, the server sends *XkbIndicatorMapNotify* events to all interested clients.

To receive *XkbIndicatorStateNotify* events, use *XkbSelectEvents* (see section 4.3) with both the *bits_to_change* and *values_for_bits* parameters containing *XkbIndicatorStateNotifyMask* . To receive *XkbIndicatorMapNotify* events, use *XkbSelectEvents* with *XkbIndicatorMapNotifyMask* .

To receive events for only specific indicators, use *XkbSelectEventDetails* . Set the *event_type* parameter *to XkbIndicatorStateNotify* or *XkbIndicatorMapNotify* , and set both the *bits_to_change* and *values_for_bits* detail parameters to a mask where each bit specifies one indicator, turning on those bits that specify the indicators for which you want to receive events.

Both types of indicator events use the same structure:

```
typedef struct _XkbIndicatorNotify {
      int            type;        /* Xkb extension base event code */
      unsigned long  serial;      /* X server serial number for event */
```

```
    Bool           send_event;  /*  True => synthetically generated */
    Display *      display;     /* server connection where event generated */
    Time           time;        /* server time when event generated */
    int            xkb_type;    /* specifies state or map notify */
    int            device;      /* Xkb device ID, will not be  XkbUseCoreKbd */
    unsigned int   changed;     /* mask of indicators with new state or map */
    unsigned int   state;       /* current state of all indicators */
} XkbIndicatorNotifyEvent;
```

xkb_type is either *XkbIndicatorStateNotify* or *XkbIndicatorMapNotify* , depending on whether the event is a *kbIndicatorStateNotify* event or *kbIndicatorMapNotify* event.

The *changed* parameter is a mask that is the bitwise inclusive OR of the indicators that have changed. If the event is of type *XkbIndicatorMapNotify* , *changed* reports the maps that changed. If the event is of type *XkbIndicatorStateNotify* , *changed* reports the indicators that have changed state. *state* is a mask that specifies the current state of all indicators, whether they have changed or not, for both *XkbIndicatorStateNotify* and *IndicatorMapNotify* events.

When your client application receives either a *XkbIndicatorStateNotify* event or *XkbIndicatorMapNotify* event, you can note the changes in a changes structure by calling *XkbNoteIndicatorChanges*.

void *XkbNoteIndicatorChanges* (*old* , *new* , *wanted*)

XkbIndicatorChangesPtr *old* ; /* XkbIndicatorChanges structure to be updated */

XkbIndicatorNotifyEvent * *new* ; /* event from which changes are to be copied */

unsigned int *wanted* ; /* which changes are to be noted */

The *wanted* parameter is the bitwise inclusive OR of *XkbIndicatorMapMask* and *XkbIndicatorStateMask* . *XkbNoteIndicatorChanges* copies any changes reported in *new* and specified in *wanted* into the changes record specified by *old*.

To update a local copy of the keyboard description with the actual values, pass the results of one or more calls to *XkbNoteIndicatorChanges* to *XkbGetIndicatorChanges*:

Status *XkbGetIndicatorChanges* (*dpy* , *xkb* , *changes* , *state*)

Display * *dpy* ; /* connection to the X server */

XkbDescPtr *xkb* ; /* keyboard description to hold the new values */

XkbIndicatorChangesPtr *changes* ; /* indicator maps/state to be obtained from the server */

unsigned int * *state* ; /* backfilled with the state of the indicators */

XkbGetIndicatorChanges examines the *changes* parameter, pulls over the necessary information from the server, and copies the results into the *xkb* keyboard description. If any bits are set in the *state_changes* field of *changes* , *XkbGetIndicatorChanges* also places the state of those indicators in *state* . If the *indicators* field of *xkb* is *NULL* , *XkbGetIndicatorChanges* allocates and initializes it. To free the *indicators* field, use *XkbFreeIndicators* (see section 8.6).

XkbGetIndicatorChanges can generate *BadAlloc* , *BadImplementation,* and *BadMatch* errors.

Allocating and Freeing Indicator Maps

Most applications do not need to directly allocate the *indicators* member of the keyboard description record (the keyboard description record is described in Chapter 6). If the need arises, however, use *XkbAllocIndicatorMaps.*

Status *XkbAllocIndicatorMaps* (*xkb*)

XkbDescPtr *xkb* ; /* keyboard description structure */

The *xkb* parameter must point to a valid keyboard description. If it doesn't, *XkbAllocIndicatorMaps* returns a *BadMatch* error. Otherwise, *XkbAllocIndicatorMaps* allocates and initializes the *indicators* member of the keyboard description record and returns *Success* . If *XkbAllocIndicatorMaps* was unable to allocate the indicators record, it reports a Bad *Alloc* error.

To free memory used by the *indicators* member of an *XkbDescRec* structure, use *XkbFreeIndicatorMaps.*

void *XkbFreeIndicatorMaps* (*xkb*)

XkbDescPtr *xkb* ; /* keyboard description structure */

If the *indicators* member of the keyboard description record pointed to by *xkb* is not *NULL* , *XkbFreeIndicatorMaps* frees the memory associated with the *indicators* member of *xkb*.

Chapter 9. Bells

The core X protocol allows only applications to explicitly sound the system bell with a given duration, pitch, and volume. Xkb extends this capability by allowing clients to attach symbolic names to bells, disable audible bells, and receive an event whenever the keyboard bell is rung. For the purposes of this document, the *audible* bell is defined to be the system bell, or the default keyboard bell, as opposed to any other audible sound generated elsewhere in the system.

You can ask to receive *XkbBellNotify* events (see section 9.4) when any client rings any one of the following:

- The default bell
- Any bell on an input device that can be specified by a *bell_class* and *bell_id* pair
- Any bell specified only by an arbitrary name. (This is, from the server's point of view, merely a name, and not connected with any physical sound-generating device. Some client application must generate the sound, or visual feedback, if any, that is associated with the name.)

You can also ask to receive *XkbBellNotify* events when the server rings the default bell or if any client has requested events only (without the bell sounding) for any of the bell types previously listed.

You can disable audible bells on a global basis (to set the *AudibleBell* control, see Chapter 10). For example, a client that replaces the keyboard bell with some other audible cue might want to turn off the *AudibleBell* control to prevent the server from also generating a sound and avoid cacophony. If you disable audible bells and request to receive *XkbBellNotify* events, you can generate feedback different from the default bell.

You can, however, override the *AudibleBell* control by calling one of the functions that force the ringing of a bell in spite of the setting of the *AudibleBell* control — *XkbForceDeviceBell* or *XkbForceBell* (see section 9.3.3). In this case the server does not generate a bell event.

Just as some keyboards can produce keyclicks to indicate when a key is pressed or repeating, Xkb can provide feedback for the controls by using special beep codes. The *AccessXFeedback* control is used to configure the specific types of operations that generate feedback. See section 10.6.3 for a discussion on *AccessXFeedback* control.

This chapter describes bell names, the functions used to generate named bells, and the events the server generates for bells.

Bell Names

You can associate a name to an act of ringing a bell by converting the name to an Atom and then using this name when you call the functions listed in this chapter. If an event is generated as a result, the name is then passed to all other clients interested in receiving *XkbBellNotify* events. Note that these are arbitrary names and that there is no binding to any sounds. Any sounds or other effects (such as visual

bells on the screen) must be generated by a client application upon receipt of the bell event containing the name. There is no default name for the default keyboard bell. The server does generate some predefined bells for the AccessX controls (see section 10.6.3). These named bells are shown in Table 9.1; the name is included in any bell event sent to clients that have requested to receive *XkbBellNotify* events.

Table 9.1. Predefined Bells

Action	Named Bell
Indicator turned on	AX_IndicatorOn
Indicator turned off	AX_IndicatorOff
More than one indicator changed state	AX_IndicatorChange
Control turned on	AX_FeatureOn
Control turned off	AX_FeatureOff
More than one control changed state	AX_FeatureChange
SlowKeys and BounceKeys about to be turned on or off	AX_SlowKeysWarning
SlowKeys key pressed	AX_SlowKeyPress
SlowKeys key accepted	AX_SlowKeyAccept
SlowKeys key rejected	AX_SlowKeyReject
Accepted SlowKeys key released	AX_SlowKeyRelease
BounceKeys key rejected	AX_BounceKeyReject
StickyKeys key latched	AX_StickyLatch
StickyKeys key locked	AX_StickyLock
StickyKeys key unlocked	AX_StickyUnlock

Audible Bells

Using Xkb you can generate bell events that do not necessarily ring the system bell. This is useful if you need to use an audio server instead of the system beep. For example, when an audio client starts, it could disable the audible bell (the system bell) and then listen for *XkbBellNotify* events (see section 9.4). When it receives a *XkbBellNotify* event, the audio client could then send a request to an audio server to play a sound.

You can control the audible bells feature by passing the *XkbAudibleBellMask* to *XkbChangeEnabledControls* (see section 10.1.1). If you set *XkbAudibleBellMask* on, the server rings the system bell when a bell event occurs. This is the default. If you set *XkbAudibleBellMask* off and a bell event occurs, the server does not ring the system bell unless you call *XkbForceDeviceBell* or *XkbForceBell* (see section 9.3.3).

Audible bells are also part of the per-client auto-reset controls. For more information on auto-reset controls, see section 10.1.2.

Bell Functions

Use the functions described in this section to ring bells and to generate bell events.

The input extension has two types of feedbacks that can generate bells — bell feedback and keyboard feedback. Some of the functions in this section have *bell_class* and *bell_id* parameters; set them as follows: Set *bell_class* to *BellFeedbackClass* or *KbdFeedbackClass* . A device can have more than one feedback of each type; set *bell_id* to the particular bell feedback of *bell_class* type.

Table 9.2 shows the conditions that cause a bell to sound or an *XkbBellNotifyEvent* to be generated when a bell function is called.

Table 9.2. Bell Sounding and Bell Event Generating

Function called	AudibleBell	Server sounds a bell	Server sends an XkbBellNotifyEvent
XkbDeviceBell	On	Yes	Yes
XkbDeviceBell	Off	No	Yes
XkbBell	On	Yes	Yes
XkbBell	Off	No	Yes
XkbDeviceBellEvent	On or Off	No	Yes
XkbBellEvent	On or Off	No	Yes
XkbDeviceForceBell	On or Off	Yes	No
XkbForceBell	On or Off	Yes	No

Generating Named Bells

To ring the bell on an X input extension device or the default keyboard, use *XkbDeviceBell.*

Bool *XkbDeviceBell* (*display, window, device_id, bell_class, bell_id, percent, name*)

Display * *display* ; /* connection to the X server */

Window *window* ; /* window for which the bell is generated, or None */

unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */

unsigned int *bell_class* ; /* X input extension bell class of the bell to be rung */

unsigned int *bell_id* ; /* X input extension bell ID of the bell to be rung */

int *percent* ; /* bell volume, from -100 to 100 inclusive */

Atom *name* ; /* a name for the bell, or *NULL* */

Set *percent* to be the volume relative to the base volume for the keyboard as described for *XBell*.

Note that *bell_class* and *bell_id* indicate the bell to physically ring. *name* is simply an arbitrary moniker for the client application's use.

To determine the current feedback settings of an extension input device, use *XGetFeedbackControl* . See the X input extension documentation for more information on *XGetFeedbackControl* and related data structures.

If a compatible keyboard extension is not present in the X server, *XkbDeviceBell* immediately returns *False* . Otherwise, *XkbDeviceBell* rings the bell as specified for the display and keyboard device and returns *True* . If you have disabled the audible bell, the server does not ring the system bell, although it does generate a *XkbBellNotify* event.

You can call *XkbDeviceBell* without first initializing the keyboard extension.

As a convenience function, Xkb provides a function to ring the bell on the default keyboard: *XkbBell.*

Bool *XkbBell* (*display, window, percent, name*)
Display * *display* ; /* connection to the X server */
Window *window* ; /* event window, or None*/
int *percent* ; /* relative volume, which can range from -100 to 100 inclusive */
Atom *name* ; /* a bell name, or *NULL* */

If a compatible keyboard extension isn't present in the X server, *XkbBell* calls *XBell* with the specified *display* and *percent* , and returns *False* . Otherwise, *XkbBell* calls *XkbDeviceBell* with the specified *display, window, percent,* and *name* , a *device_spec* of *XkbUseCoreKbd* , a *bell_class* of *XkbDfltXIClass* , and a *bell_id* of *XkbDfltXIId,* and returns *True*.

If you have disabled the audible bell, the server does not ring the system bell, although it does generate a *XkbBellNotify* event.

You can call *XkbBell* without first initializing the keyboard extension.

Generating Named Bell Events

Using Xkb, you can also generate a named bell event that does not ring any bell. This allows you to do things such as generate events when your application starts.

For example, if an audio client listens for these types of bells, it can produce a "whoosh" sound when it receives a named bell event to indicate a client just started. In this manner, applications can generate start-up feedback and not worry about producing annoying beeps if an audio server is not running.

To cause a bell event for an X input extension device or for the keyboard, without ringing the corresponding bell, use *XkbDeviceBellEvent.*

Bool *XkbDeviceBellEvent* (*display, window, device_spec, bell_class, bell_id, percent, name*)
Display * *display* ; /* connection to the X server */
Window *window* ; /* event window, or None*/
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
unsigned int *bell_class;* /* input extension bell class for the event */
unsigned int *bell_id* ; /* input extension bell ID for the event */
int *percent* ; /* volume for the bell, which can range from -100 to 100 inclusive */
Atom *name* ; /* a bell name, or *NULL* */

If a compatible keyboard extension isn't present in the X server, *XkbDeviceBellEvent* immediately returns *False* . Otherwise, *XkbDeviceBellEvent* causes an *XkbBellNotify* event to be sent to all interested clients and returns *True* . Set *percent* to be the volume relative to the base volume for the keyboard as described for *XBell*.

In addition, *XkbDeviceBellEvent* may generate *Atom* protocol errors as well as *XkbBellNotify* events. You can call *XkbBell* without first initializing the keyboard extension.

As a convenience function, Xkb provides a function to cause a bell event for the keyboard without ringing the bell: *XkbBellEvent.*

Bool *XkbBellEvent* (*display, window, percent, name*)
Display * *display* ; /* connection to the X server */
Window *window* ; /* the event window, or None */
int *percent* ; /* relative volume, which can range from -100 to 100 inclusive */
Atom *name* ; /* a bell name, or *NULL* */

If a compatible keyboard extension isn't present in the X server, *XkbBellEvent* immediately returns *False* . Otherwise, *XkbBellEvent* calls *XkbDeviceBellEvent* with the specified *display, window, percent,* and *name* , a *device_spec* of *XkbUseCoreKbd* , a *bell_class* of *XkbDfltXIClass* , and a *bell_id* of *XkbDfltXIId,* and returns what *XkbDeviceBellEvent* returns.

XkbBellEvent generates a *XkbBellNotify* event.

You can call *XkbBellEvent* without first initializing the keyboard extension.

Forcing a Server-Generated Bell

To ring the bell on any keyboard, overriding user preference settings for audible bells, use *XkbForceDeviceBell*.

Bool *XkbForceDeviceBell* (*display, window, device_spec, bell_class, bell_id, percent*)
Display * *display* ; /* connection to the X server */
Window *window* ; /* event window, or None */
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
unsigned int *bell_class* ; /* input extension class of the bell to be rung */
unsigned int *bell_id* ; /* input extension ID of the bell to be rung */
int *percent* ; /* relative volume, which can range from -100 to 100 inclusive */

If a compatible keyboard extension isn't present in the X server, *XkbForceDeviceBell* immediately returns *False* . Otherwise, *XkbForceDeviceBell* rings the bell as specified for the display and keyboard device and returns *True* . Set *percent* to be the volume relative to the base volume for the keyboard as described for *XBell* . There is no *name* parameter because *XkbForceDeviceBell* does not cause an *XkbBellNotify* event.

You can call *XkbBell* without first initializing the keyboard extension.

To ring the bell on the default keyboard, overriding user preference settings for audible bells, use *XkbForceBell*.

Bool *XkbForceBell* (*display, percent)*
Display * *display* ; /* connection to the X server */
int *percent* ; /* volume for the bell, which can range from -100 to 100 inclusive */

If a compatible keyboard extension isn't present in the X server, *XkbForceBell* calls *XBell* with the specified *display* and *percent* and returns *False* . Otherwise, *XkbForceBell* calls *XkbForceDeviceBell* with the specified *display* and *percent* , *device_spec* = *XkbUseCoreKbd* , *bell_class* = *XkbDfltXIClass* , *bell_id* = *XkbDfltXIId*, *window* = None, and *name* = *NULL* , and returns what *XkbForceDeviceBell* returns.

XkbForceBell does not cause an *XkbBellNotify* event.

You can call *XkbBell* without first initializing the keyboard extension.

Detecting Bells

Xkb generates *XkbBellNotify* events for all bells except for those resulting from calls to *XkbForceDeviceBell* and *XkbForceBell* . To receive *XkbBellNotify* events under all possible conditions, pass *XkbBellNotifyMask* in both the *bits_to_change* and *values_for_bits* parameters to *XkbSelectEvents* (see section 4.3).

The *XkbBellNotify* event has no event details. It is either selected or it is not. However, you can call *XkbSelectEventDetails* using *XkbBellNotify* as the *event_type* and specifying *XkbAllBellNotifyMask* in *bits_to_change* and *values_for_bits*. This has the same effect as a call to *XkbSelectEvents*.

The structure for the *XkbBellNotify* event type contains:

```
typedef struct _XkbBellNotify {
      int             type;        /* Xkb extension base event code */
      unsigned long   serial;      /* X server serial number for event */
      Bool            send_event;  /*  True => synthetically generated */
      Display *       display;     /* server connection where event generated */
      Time            time;        /* server time when event generated */
      int             xkb_type;    /*  XkbBellNotify */
      unsigned int    device;      /* Xkb device ID, will not be  XkbUseCoreKbd */
      int             percent;     /* requested volume as % of max */
      int             pitch;       /* requested pitch in Hz */
      int             duration;    /* requested duration in microseconds */
      unsigned int    bell_class;  /* X input extension feedback class */
      unsigned int    bell_id;     /* X input extension feedback ID */
      Atom            name;        /* "name" of requested bell */
      Window          window;      /* window associated with event */
      Bool            event_only;  /*  False -> the server did not produce a beep
} XkbBellNotifyEvent;
```

If your application needs to generate visual bell feedback on the screen when it receives a bell event, use the window ID in the *XkbBellNotifyEvent* , if present.

Chapter 10. Keyboard Controls

The Xkb extension is composed of two parts: a server extension, and a client-side X library extension. This chapter discusses functions used to modify controls effecting the behavior of the server portion of the Xkb extension. Chapter 11 discusses functions used to modify controls that affect only the behavior of the client portion of the extension; those controls are known as Library Controls.

Xkb contains control features that affect the entire keyboard, known as global keyboard controls. Some of the controls may be selectively enabled and disabled; these controls are known as the *Boolean Controls* . Boolean Controls can be turned on or off under program control and can also be automatically set to an on or off condition when a client program exits. The remaining controls, known as the *Non-Boolean Controls* , are always active. The *XkbControlsRec* structure describes the current state of most of the global controls and the attributes effecting the behavior of each of these Xkb features. This chapter describes the Xkb controls and how to manipulate them.

There are two possible components for each of the Boolean Controls: attributes describing how the control should work, and a state describing whether the behavior as a whole is enabled or disabled. The attributes and state for most of these controls are held in the *XkbControlsRec* structure (see section 10.8).

You can manipulate the Xkb controls individually, via convenience functions, or as a whole. To treat them as a group, modify an *XkbControlsRec* structure to describe all of the changes to be made, and then pass that structure and appropriate flags to an Xkb library function, or use a *XkbControlsChangesRec* (see section 10.10.1) to reduce network traffic. When using a convenience function to manipulate one control individually, you do not use an *XkbControlsRec* structure directly.

The Xkb controls are grouped as shown in Table 10.1.

Table 10.1. Xkb Keyboard Controls

Type of Control	Control Name	Boolean Control?
Controls for enabling and disabling other controls	EnabledControls	No
	AutoReset	No
Control for bell behavior	AudibleBell	Boolean
Controls for repeat key behavior	PerKeyRepeat	No
	RepeatKeys	Boolean
	DetectableAutorepeat	Boolean
Controls for keyboard overlays	Overlay1	Boolean
	Overlay2	Boolean
Controls for using the mouse from the keyboard	MouseKeys	Boolean
	MouseKeysAccel	Boolean
Controls for better keyboard access by	AccessXFeedback	Boolean
physically impaired persons	AccessXKeys	Boolean
	AccessXTimeout	Boolean
	BounceKeys	Boolean
	SlowKeys	Boolean
	StickyKeys	Boolean
Controls for general keyboard mapping	GroupsWrap	No
	IgnoreGroupLock	Boolean
	IgnoreLockMods	No
	InternalMods	No
Miscellaneous per-client controls	GrabsUseXKBState	Boolean
	LookupStateWhenGrabbed	Boolean
	SendEventUsesXKBState	Boolean

The individual categories and controls are described first, together with functions for manipulating them. A description of the *XkbControlsRec* structure and the general functions for dealing with all of the controls at once follow at the end of the chapter.

Controls that Enable and Disable Other Controls

Enable and disable the boolean controls under program control by using the *EnabledControls* control; enable and disable them upon program exit by configuring the *AutoReset* control.

The EnabledControls Control

The *EnabledControls* control is a bit mask where each bit that is turned on means the corresponding control is enabled, and when turned off, disabled. It corresponds to the *enabled_ctrls* field of an *XkbControlsRec* structure (see section 10.8). The bits describing which controls are turned on or off are defined in Table 10.7.

Use *XkbChangeEnabledControls* to manipulate the *EnabledControls* control.

```
Bool XkbChangeEnabledControls ( dpy , device_spec , mask , values )
Display * dpy ; /* connection to X server */
unsigned int device_spec ; /* keyboard device to modify */
unsigned int mask ; /* 1 bit -> controls to enable / disable */
unsigned int values ; /* 1 bit => enable, 0 bit => disable */
```

The *mask* parameter specifies the boolean controls to be enabled or disabled, and the *values* mask specifies the new state for those controls. Valid values for both of these masks are composed of a bitwise inclusive OR of bits taken from the set of mask bits in Table 10.7, using only those masks with "ok" in the *enabled_ctrls* column.

If the X server does not support a compatible version of Xkb or the Xkb extension has not been properly initialized, *XkbChangeEnabledControls* returns *False* ; otherwise, it sends the request to the X server and returns *True* .

Note that the *EnabledControls* control only enables and disables controls; it does not configure them. Some controls, such as the *AudibleBell* control, have no configuration attributes and are therefore manipulated solely by enabling and disabling them. Others, however, have additional attributes to configure their behavior. For example, the *RepeatControl* control uses *repeat_delay* and *repeat_interval* fields to describe the timing behavior of keys that repeat. The *RepeatControl* behavior is turned on or off depending on the value of the *XkbRepeatKeysMask* bit, but you must use other means, as described in this chapter, to configure its behavior in detail.

The AutoReset Control

You can configure the boolean controls to automatically be enabled or disabled when a program exits. This capability is controlled via two masks maintained in the X server on a per-client basis. There is no client-side Xkb data structure corresponding to these masks. Whenever the client exits for any reason, any boolean controls specified in the *auto-reset mask* are set to the corresponding value from the *auto-reset values* mask. This makes it possible for clients to "clean up after themselves" automatically, even if abnormally terminated. The bits used in the masks correspond to the *EnabledControls* control bits.

For example, a client that replaces the keyboard bell with some other audible cue might want to turn off the *AudibleBell* control to prevent the server from also generating a sound and avoid cacophony. If the client were to exit without resetting the *AudibleBell* control, the user would be left without any feedback at all. Setting *AudibleBell* in both the auto-reset mask and auto-reset values guarantees that the audible bell will be turned back on when the client exits.

To get the current values of the auto-reset controls, use *XkbGetAutoResetControls* .

Bool *XkbGetAutoResetControls* (*dpy* , *auto_ctrls* , *auto_values*)
Display * *dpy* ; /* connection to X server */
unsigned int * *auto_ctrls* ; /* specifies which bits in *auto_values* are relevant */
unsigned int * *auto_values* ; /* 1 bit => corresponding control has auto-reset on */

XkbGetAutoResetControls backfills *auto_ctrls* and *auto_values* with the *AutoReset* control attributes for this particular client. It returns *True* if successful, and *False* otherwise.

To change the current values of the *AutoReset* control attributes, use *XkbSetAutoResetControls.*

Bool *XkbSetAutoResetControls* (*dpy* , *changes* , *auto_ctrls* , *auto_values*)
Display * *dpy* ; /* connection to X server */
unsigned int *changes* ; /* controls for which to change auto-reset values */
unsigned int * *auto_ctrls* ; /* controls from changes that should auto reset */
unsigned int * *auto_values* ; /* 1 bit => auto-reset on */

XkbSetAutoResetControls changes the auto-reset status and associated auto-reset values for the controls selected by changes . For any control selected by changes , if the corresponding bit is set in auto_ctrls , the control is configured to auto-reset when the client exits. If the corresponding bit in auto_values is on, the control is turned on when the client exits; if zero, the control is turned off when the client exits. For any control selected by *changes* , if the corresponding bit is not set in *auto_ctrls* , the control is configured to not reset when the client exits. For example:

To leave the auto-reset controls for StickyKeys the way they are:

```
ok = XkbSetAutoResetControls(dpy, 0, 0, 0);
```

To change the auto-reset controls so that StickyKeys are unaffected when the client exits:

```
ok = XkbSetAutoResetControls(dpy, XkbStickyKeysMask, 0, 0);
```

To change the auto-reset controls so that StickyKeys are turned off when the client exits:

```
ok = XkbSetAutoResetControls(dpy, XkbStickyKeysMask, XkbStickyKeysMask, 0);
```

To change the auto-reset controls so that StickyKeys are turned on when the client exits:

```
ok = XkbSetAutoResetControls(dpy, XkbStickyKeysMask, XkbStickyKeysMask,
```

```
XkbStickyKeysMask);
```

XkbSetAutoResetControls backfills *auto_ctrls* and *auto_values* with the auto-reset controls for this particular client. Note that all of the bits are valid in the returned values, not just the ones selected in the *changes* mask.

Control for Bell Behavior

The X server's generation of sounds is controlled by the *AudibleBell* control. Configuration of different bell sounds is discussed in Chapter 9.

The AudibleBell Control

The *AudibleBell* control is a boolean control that has no attributes. As such, you may enable and disable it using either the *EnabledControls* control or the *AutoReset* control discussed in section 10.1.1. When enabled, protocol requests to generate a sound result in the X server actually producing a real sound; when disabled, requests to the server to generate a sound are ignored unless the sound is forced. See section 9.2.

Controls for Repeat Key Behavior

The repeating behavior of keyboard keys is governed by three controls, the *PerKeyRepeat* control, which is always active, and the *RepeatKeys* and *DetectableAutorepeat* controls, which are boolean controls that may be enabled and disabled. *PerKeyRepeat* determines which keys are allowed to repeat. *RepeatKeys* governs the behavior of an individual key when it is repeating. *DetectableAutorepeat* allows a client to detect when a key is repeating as a result of being held down.

The PerKeyRepeat Control

The *PerKeyRepeat* control is a bitmask long enough to contain a bit for each key on the device; it determines which individual keys are allowed to repeat. The Xkb *PerKeyRepeat* control provides no functionality different from that available via the core X protocol. There are no convenience functions in Xkb for manipulating this control. The *PerKeyRepeat* control settings are carried in the *per_key_repeat* field of an *XkbControlsRec* structure, discussed in section 10.8.

The RepeatKeys Control

The core protocol allows only control over whether or not the entire keyboard or individual keys should auto-repeat when held down. *RepeatKeys* is a boolean control that extends this capability by adding control over the delay until a key begins to repeat and the rate at which it repeats. *RepeatKeys* is coupled with the core auto-repeat control: when *RepeatKeys* is enabled or disabled, the core auto-repeat is enabled or disabled and vice versa.

Auto-repeating keys are controlled by two attributes. The first, *timeout* , is the delay after the initial press of an auto-repeating key and the first generated repeat event. The second, *interval* , is the delay between all subsequent generated repeat events. As with all boolean controls, configuring the attributes that determine how the control operates does not automatically enable the control as a whole; see section 10.1.

To get the current attributes of the *RepeatKeys* control for a keyboard device, use *XkbGetAutoRepeatRate* .

```
Bool XkbGetAutoRepeatRate ( display, device_spec, timeout_rtrn, interval_rtrn )
Display * display ; /* connection to X server */
unsigned int device_spec ; /* desired device ID, or XkbUseCoreKbd */
unsigned int * timeout_rtrn ; /* backfilled with initial repeat delay, ms */
unsigned int * interval_rtrn ; /* backfilled with subsequent repeat delay, ms */
```

XkbGetAutoRepeatRate queries the server for the current values of the *RepeatControls* control attributes, backfills *timeout_rtrn* and *interval_rtrn* with them, and returns *True* . If a compatible version of the Xkb extension is not available in the server *XkbGetAutoRepeatRate* returns *False* .

To set the attributes of the RepeatKeys control for a keyboard device, use *XkbSetAutoRepeatRate* .

```
Bool XkbSetAutoRepeatRate ( display, device_spec, timeout, interval )
Display * display ; /* connection to X server */
unsigned int device_spec ; /* device to configure, or XkbUseCoreKbd */
unsigned int timeout ; /* initial delay, ms */
unsigned int interval ; /* delay between repeats, ms */
```

XkbSetAutoRepeatRate sends a request to the X server to configure the *AutoRepeat* control attributes to the values specified in *timeout* and *interval* .

XkbSetAutoRepeatRate does not wait for a reply; it normally returns *True* . Specifying a zero value for either *timeout* or *interval* causes the server to generate a *BadValue* protocol error. If a compatible version of the Xkb extension is not available in the server, *XkbSetAutoRepeatRate* returns *False* .

The DetectableAutorepeat Control

Auto-repeat is the generation of multiple key events by a keyboard when the user presses a key and holds it down. Keyboard hardware and device-dependent X server software often implement auto-repeat by generating multiple *KeyPress* events with no intervening *KeyRelease* event. The standard behavior of the X server is to generate a *KeyRelease* event for every *KeyPress* event. If the keyboard hardware and device-dependent software of the X server implement auto-repeat by generating multiple *KeyPress* events, the device-independent part of the X server by default synthetically generates a *KeyRelease* event after each *KeyPress* event. This provides predictable behavior for X clients, but does not allow those clients to detect the fact that a key is auto-repeating.

Xkb allows clients to request *detectable auto-repeat* . If a client requests and the server supports *DetectableAutorepeat* , Xkb generates *KeyRelease* events only when the key is physically released. If *DetectableAutorepeat* is not supported or has not been requested, the server synthesizes a *KeyRelease* event for each repeating *KeyPress* event it generates.

DetectableAutorepeat , unlike the other controls in this chapter, is not contained in the *XkbControlsRec* structure, nor can it be enabled or disabled via the *Enabled-*

Controls control. Instead, query and set *DetectableAutorepeat* using *XkbGetDetectableAutorepeat* and *XkbSetDetectableAutorepeat* .

DetectableAutorepeat is a condition that applies to all keyboard devices for a client's connection to a given X server; it cannot be selectively set for some devices and not for others. For this reason, none of the Xkb library functions involving *DetectableAutorepeat* involve a device specifier.

To determine whether or not the server supports *DetectableAutorepeat* , use *XkbGetDetectableAutorepeat* .

Bool *XkbGetDetectableAutorepeat* (*display, supported_rtrn*)
Display * *display* ; /* connection to X server */
Bool * *supported_rtrn* ; /* backfilled *True* if *DetectableAutorepeat* supported */

XkbGetDetectableAutorepeat queries the server for the current state of *DetectableAutorepeat* and waits for a reply. If *supported_rtrn* is not *NULL* , it backfills supported_rtrn with *True* if the server supports *DetectableAutorepeat* , and *False* otherwise. *XkbGetDetectableAutorepeat* returns the current state of *DetectableAutorepeat* for the requesting client: *True* if *DetectableAutorepeat* is set, and *False* otherwise.

To set *DetectableAutorepeat* , use *XkbSetDetectableAutorepeat* . This request affects all keyboard activity for the requesting client only; other clients still see the expected nondetectable auto-repeat behavior, unless they have requested otherwise.

Bool *XkbSetDetectableAutorepeat* (*display, detectable, supported_rtrn*)
Display * *display* ; /* connection to X server */
Bool *detectable* ; /* *True* => set *DetectableAutorepeat* */
Bool * *supported_rtrn* ; /* backfilled *True* if *DetectableAutorepeat* supported */

XkbSetDetectableAutorepeat sends a request to the server to set *DetectableAutorepeat* on for the current client if *detectable* is *True* , and off it *detectable* is *False* ; it then waits for a reply. If *supported_rtrn* is not *NULL* , *XkbSetDetectableAutorepeat* backfills *supported_rtrn* with *True* if the server supports *DetectableAutorepeat* , and *False* if it does not. *XkbSetDetectableAutorepeat* returns the current state of *DetectableAutorepeat* for the requesting client: *True* if *DetectableAutorepeat* is set, and *False* otherwise.

Controls for Keyboard Overlays (Overlay1 and Overlay2 Controls)

A keyboard overlay allows some subset of the keyboard to report alternate keycodes when the overlay is enabled. For example, a keyboard overlay can be used to simulate a numeric or editing keypad on a keyboard that does not actually have one by reusing some portion of the keyboard as an overlay. This technique is very common on portable computers and embedded systems with small keyboards.

Xkb includes direct support for two keyboard overlays, using the *Overlay1* and *Overlay2* controls. When *Overlay1* is enabled, all of the keys that are members of the

first keyboard overlay generate an alternate keycode. When *Overlay2* is enabled, all of the keys that are members of the second keyboard overlay generate an alternate keycode. The two overlays are mutually exclusive; any particular key may be in at most one overlay. *Overlay1* and *Overlay2* are boolean controls. As such, you may enable and disable them using either the *EnabledControls* control or the *AutoReset* control discussed in section 10.1.1.

To specify the overlay to which a key belongs and the alternate keycode it should generate when that overlay is enabled, assign it either the *XkbKB_Overlay1* or *XkbKB_Overlay2* key behaviors, as described in section 16.2.

Controls for Using the Mouse from the Keyboard

Using Xkb, it is possible to configure the keyboard to allow simulation of the X pointer device. This simulation includes both movement of the pointer itself and press and release events associated with the buttons on the pointer. Two controls affect this behavior: the *MouseKeys* control determines whether or not simulation of the pointer device is active, as well as configuring the default button; the *MouseKeysAccel* control determines the movement characteristics of the pointer when simulated via the keyboard. Both of them are boolean controls; as such, you may enable and disable them using either the *EnabledControls* control or the *AutoReset* control discussed in section 10.1.1. The individual keys that simulate different aspects of the pointer device are determined by the keyboard mapping, discussed in Chapter 16.

The MouseKeys Control

The *MouseKeys* control allows a user to control all the mouse functions from the keyboard. When *MouseKeys* are enabled, all keys with *MouseKeys* actions bound to them generate core pointer events instead of normal *KeyPress* and *KeyRelease* events.

The *MouseKeys* control has a single attribute, *mk_dflt_btn* that specifies the core button number to be used by mouse keys actions that do not explicitly specify a button. There is no convenience function for getting or setting the attribute; instead use *XkbGetControls* and *XkbSetControls* (see sections 10.9 and 10.10).

Note

MouseKeys can also be turned on and off by pressing the key combination necessary to produce an *XK_Pointer_EnableKeys* keysym. The de facto default standard for this is *Shift+Alt+NumLock* , but this may vary depending on the keymap.

The MouseKeysAccel Control

When the *MouseKeysAccel* control is enabled, the effect of a key-activated pointer motion action changes as a key is held down. If the control is disabled, pressing a mouse-pointer key yields one mouse event. When *MouseKeysAccel* is enabled, mouse movement is defined by an initial distance specified in the *XkbSA_MovePtr* action and the following fields in the *XkbControlsRec* structure (see section 10.8).

Table 10.2. MouseKeysAccel Fields

Field	Function
mk_delay	Time (ms) between the initial key press and the first repeated motion event
mk_interval	Time (ms) between repeated motion events
mk_time_to_max	Number of events (count) before the pointer reaches maximum speed
mk_max_speed	The maximum speed (in pixels per event) the pointer reaches
mk_curve	The ramp used to reach maximum pointer speed

There are no convenience functions to query or change the attributes of the *MouseKeysAccel* control; instead use *XkbGetControls* and *XkbSetControls* (see sections 10.9 and 10.10).

The effects of the attributes of the *MouseKeysAccel* control depend on whether the *XkbSA_MovePtr* action (see section 16.1) specifies relative or absolute pointer motion.

Absolute Pointer Motion

If an *XkbSA_MovePtr* action specifies an absolute position for one of the coordinates but still allows acceleration, all repeated events contain any absolute coordinates specified in the action. For example, if the *XkbSA_MovePtr* action specifies an absolute position for the X direction, but a relative motion for the Y direction, the pointer accelerates in the Y direction, but stays at the same X position.

Relative Pointer Motion

If the *XkbSA_MovePtr* action specifies relative motion, the initial event always moves the cursor the distance specified in the action. After *mk_delay* milliseconds, a second motion event is generated, and another occurs every *mk_interval* milliseconds until the user releases the key.

Between the time of the second motion event and *mk_time_to_max* intervals, the change in pointer distance per interval increases with each interval. After *mk_time_to_max* intervals have elapsed, the change in pointer distance per interval remains the same and is calculated by multiplying the original distance specified in the action by *mk_max_speed* .

For example, if the *XkbSA_MovePtr* action specifies a relative motion in the X direction of 5, *mk_delay* =160, *mk_interval* =40, *mk_time_to_max* =30, and *mk_max_speed* =30, the following happens when the user presses the key:

- The pointer immediately moves 5 pixels in the X direction when the key is pressed.
- After 160 milliseconds (*mk_delay*), and every 40 milliseconds thereafter (*mk_interval*), the pointer moves in the X direction.
- The distance in the X direction increases with each interval until 30 intervals (*mk_time_to_max*) have elapsed.

- After 30 intervals, the pointer stops accelerating, and moves 150 pixels (*mk_max_speed* * the original distance) every interval thereafter, until the key is released.

The increase in pointer difference for each interval is a function of *mk_curve.* Events after the first but before maximum acceleration has been achieved are accelerated according to the formula:

$$d(step) = action\_delta \times \left(\frac{max\_accel}{steps\_to\_max^{\,curveFactor}} \right) \times step^{\,curveFactor}$$

Where *action_delta* is the relative motion specified by the *XkbSA_MovePtr* action, *mk_max_speed* and *mk_time_to_max* are parameters to the *MouseKeysAccel* control, and the curveFactor is computed using the *MouseKeysAccel* *mk_curve* parameter as follows:

$$curveFactor(curve) = 1 + \frac{curve}{1000}$$

With the result that a *mk_curve* of zero causes the distance moved to increase linearly from *action_delta* to

$$(mk\_max\_speed \times action\_delta)$$

. A negative *mk_curve* causes an initial sharp increase in acceleration that tapers off, and a positive curve yields a slower initial increase in acceleration followed by a sharp increase as the number of pointer events generated by the action approaches *mk_time_to_max* . The legal values for *mk_curve* are between -1000 and 1000.

A distance vs. time graph of the pointer motion is shown in Figure 10.1.



MouseKeys Acceleration

Controls for Better Keyboard Access by Physically Impaired Persons

The Xkb extension includes several controls specifically aimed at making keyboard use more effective for physically impaired people. All of these controls are boolean controls and may be individually enabled and disabled, as well as configured to tune

their specific behavior. The behavior of these controls is based on the AccessDOS package [1].

The AccessXKeys Control

Enabling or disabling the keyboard controls through a graphical user interface may be impossible for people who need to use the controls. For example, a user who needs *SlowKeys* (see section 10.6.6) may not even be able to start the graphical application, let alone use it, if *SlowKeys* is not enabled. To allow easier access to some of the controls, the *AccessXKeys* control provides a set of special key sequences similar to those available in AccessDOS.

When the *AccessXKeys* control is enabled, the user can turn controls on or off from the keyboard by entering the following standard key sequences:

- Holding down a shift key by itself for eight seconds toggles the *SlowKeys* control.
- Pressing and releasing the left or right *Shift* key five times in a row, without any intervening key events and with less than 30 seconds delay between consecutive presses, toggles the state of the *StickyKeys* control.
- Simultaneously operating two or more modifier keys deactivates the *StickyKeys* control.

When the *AccessXKeys* control is disabled, Xkb does not look for the above special key sequences.

Some of these key sequences optionally generate audible feedback of the change in state, as described in section 10.6.3, or *XkbControlsNotify* events, described in section 10.11.

The AccessXTimeout Control

In environments where computers are shared, features such as *SlowKeys* present a problem: if *SlowKeys* is on, the keyboard can appear to be unresponsive because keys are not accepted until they are held for a certain period of time. To help solve this problem, Xkb provides an *AccessXTimeout* control to automatically change the enabled/disabled state of any boolean controls and to change the value of the *AccessXKeys* and *AccessXFeedback* control attributes if the keyboard is idle for a specified period of time.

When a timeout as specified by *AccessXTimeout* occurs and a control is consequently modified, Xkb generates an *XkbControlsNotify* event. For more information on *XkbControlsNotify* events, refer to section 10.11.

Use *XkbGetAccessXTimeout* to query the current *AccessXTimeout* options for a keyboard device.

[1] AccessDOS provides access to the DOS operating system for people with physical impairments and was developed by the Trace R&D Center at the University of Wisconsin. For more information on AccessDOS, contact the Trace R&D Center, Waisman Center and Department of Industrial Engineering, University of Wisconsin-Madison WI 53705-2280. Phone: 608-262-6966. e-mail: info@trace.wisc.edu.

Bool *XkbGetAccessXTimeout* (*display* , *device_spec* , *timeout_rtrn* , *ctrls_mask_rtrn* , *ctrls_values_rtrn* , *options_mask_rtrn, options_values_rtrn*)
Display * *display* ; /* connection to X server */
unsigned int *device_spec* ; /* device to query, or *XkbUseCoreKbd* */
unsigned short * *timeout_rtrn* ; /* delay until AccessXTimeout, seconds */
unsigned int * *ctrls_mask_rtrn* ; /* backfilled with controls to modify */
unsigned int * *ctrls_values_rtrn* ; /* backfilled with on/off status for controls */
unsigned short * *opts_mask_rtrn* ; /* backfilled with *ax_options* to modify */
unsigned short * *opts_values_rtrn* ; /* backfilled with values for *ax_options* */

XkbGetAccessXTimeout sends a request to the X server to obtain the current values for the *AccessXTimeout* attributes, waits for a reply, and backfills the values into the appropriate arguments. The parameters *opts_mask_rtrn* and *opts_values_rtrn* are backfilled with the options to modify and the values for *ax_options* , which is a field in the *XkbControlsRec* structure (see section 10.8). *XkbGetAccessXTimeout* returns *True* if successful; if a compatible version of the Xkb extension is not available in the server, *XkbGetAccessXTimeout* returns *False* .

To configure the *AccessXTimeout* options for a keyboard device, use *XkbSetAccessXTimeout* .

Bool *XkbSetAccessXTimeout* (*display* , *device_spec, timeout, ctrls_mask, ctrls_values, opts_mask, opts_values*)
Display * *display* ; /* connection to X server */
unsigned int *device_spec* ; /* device to configure, or *XkbUseCoreKbd* */
unsigned short *timeout* ; /* seconds idle until AccessXTimeout occurs */
unsigned int *ctrls_mask* ; /* boolean controls to modify */
unsigned int *ctrls_values* ; /* new bits for controls selected by *ctrls_mask* */
unsigned short *opts_mask* ; /* *ax_options* to change */
unsigned short *opts_values* ; /* new bits for *ax_options* selected by *opts_mask* */

timeout specifies the number of seconds the keyboard must be idle before the controls are modified. *ctrls_mask* specifies what controls are to be enabled or disabled, and *ctrls_values* specifies whether those controls are to be enabled or disabled. The bit values correspond to those for enabling and disabling boolean controls (see section 10.1.1). The *opts_mask* field specifies which attributes of the *AccessXKeys* and *AccessXFeedback* controls are to be changed, and *opts_values* specifies the new values for those options. The bit values correspond to those for the *ax_options* field of an *XkbDescRec* (see section 10.8).

XkbSetAccessXTimeout sends a request to configure the *AccessXTimeout* control to the server. It does not wait for a reply, and normally returns *True* . If a compatible version of the Xkb extension is not available in the server, *XkbSetAccessXTimeout* returns *False* .

The AccessXFeedback Control

Just as some keyboards can produce keyclicks to indicate when a key is pressed or repeating, Xkb can provide feedback for the controls by using special beep codes.

Use the *AccessXFeedback* control to configure the specific types of operations that generate feedback.

There is no convenience function for modifying the *AccessXFeedback* control, although the feedback as a whole can be enabled or disabled just as other boolean controls are (see section 10.1). Individual beep codes are turned on or off by modifying the following bits in the *ax_options* field of an *XkbControlsRec* structure and using *XkbSetControls* (see section 10.10):

Table 10.3. AccessXFeedback Masks

Action	Beep Code	ax_options bit
LED turned on	High-pitched beep	XkbAX_IndicatorFBMask
LED turned off	Low-pitched beep	XkbAX_IndicatorFBMask
More than one LED changed state	Two high-pitched beeps	XkbAX_IndicatorFBMask
Control turned on	Rising tone	XkbAX_FeatureFBMask
Control turned off	Falling tone	XkbAX_FeatureFBMask
More than one control changed state	Two high-pitched beeps	XkbAX_FeatureFBMask
SlowKeys and BounceKeys about to be turned on or off	Three high-pitched beeps	XkbAX_SlowWarnFBMask
SlowKeys key pressed	Medium-pitched beep	XkbAX_SKPressFBMask
SlowKeys key accepted	Medium-pitched beep	XkbAX_SKAcceptFBMask
SlowKeys key rejected	Low-pitched beep	XkbAX_SKRejectFBMask
Accepted SlowKeys key released	Medium-pitched beep	XkbAX_SKReleaseFBMask
BounceKeys key rejected	Low-pitched beep	XkbAX_BKRejectFBMask
StickyKeys key latched	Low-pitched beep followed by high-pitched beep	XkbAX_StickyKeysFBMask
StickyKeys key locked	High-pitched beep	XkbAX_StickyKeysFBMask
StickyKeys key unlocked	Low-pitched beep	XkbAX_StickyKeysFBMask

Implementations that cannot generate continuous tones may generate multiple beeps instead of falling and rising tones; for example, they can generate a high-pitched beep followed by a low-pitched beep instead of a continuous falling tone. Other implementations can only ring the bell with one fixed pitch. In these cases, use the *XkbAX_DumbBellFBMask* bit of *ax_options* to indicate that the bell can only ring with a fixed pitch.

When any of the above feedbacks occur, Xkb may generate a *XkbBellNotify* event (see section 9.4).

AccessXNotify Events

The server can generate *XkbAccessXNotify* events for some of the global keyboard controls. The structure for the *XkbAccessXNotify* event type is as follows:

```
typedef struct {
      int             type;           /* Xkb extension base event code */
      unsigned long   serial;         /* X server serial number for event */
      Bool            send_event;     /*  True => synthetically generated */
      Display *       display;        /* server connection where event generated
      Time            time;           /* server time when event generated */
      int             xkb_type;       /*  XkbAccessXNotify */
      int             device;         /* Xkb device ID, will not be  XkbUseCoreKb
      int             detail;         /* XkbAXN_* */
      KeyCode         keycode;        /* key of event */
      int             slowKeysDelay;  /* current SlowKeys delay */
      int             debounceDelay;  /* current debounce delay */
} XkbAccessXNotifyEvent;
```

The *detail* field describes what AccessX event just occurred and can be any of the values in Table 10.4.

Table 10.4. AccessXNotify Events

detail	Reason
XkbAXN_SKPress	A key was pressed when SlowKeys was enabled.
XkbAXN_SKAccept	A key was accepted (held longer than the SlowKeys delay).
XkbAXN_SKRelease	An accepted SlowKeys key was released.
XkbAXN_SKReject	A key was rejected (released before the SlowKeys delay expired).
XkbAXN_BKAccept	A key was accepted by BounceKeys.
XkbAXN_BKReject	A key was rejected (pressed before the BounceKeys delay expired).
XkbAXN_AXKWarning	AccessXKeys is about to turn on/off StickyKeys or BounceKeys.

The *keycode* field reports the keycode of the key for which the event occurred. If the action is related to *SlowKeys* , the *slowKeysDelay* field contains the current *SlowKeys* acceptance delay. If the action is related to *BounceKeys* , the *debounceDelay* field contains the current *BounceKeys* debounce delay.

Selecting for AccessX Events

To receive *XkbAccessXNotify* events under all possible conditions, use *XkbSelectEvents* (see section 4.3) and pass *XkbAccesXNotifyMask* in both *bits_to_change* and *values_for_bits* .

To receive *XkbStateNotify* events only under certain conditions, use *XkbSelectEventDetails* using *XkbAccessXNotify* as the *event_type* and specifying the desired state changes in *bits_to_change* and *values_for_bits* using mask bits from Table 10.5.

Table 10.5. AccessXNotify Event Details

XkbAccessXNotify Event Details	Value	Circumstances
XkbAXN_SKPressMask	(1<<0)	Slow key press notification wanted
XkbAXN_SKAcceptMask	(1<<1)	Slow key accept notification wanted
XkbAXN_SKRejectMask	(1<<2)	Slow key reject notification wanted
XkbAXN_SKReleaseMask	(1<<3)	Slow key release notification wanted
XkbAXN_BKAcceptMask	(1<<4)	Bounce key accept notification wanted
XkbAXN_BKRejectMask	(1<<5)	Bounce key reject notification wanted
XkbAXN_AXKWarningMask	(1<<6)	AccessX warning notification wanted
XkbAXN_AllEventsMask	(0x7f)	All AccessX features notifications wanted

StickyKeys, RepeatKeys, and MouseKeys Events

The *StickyKeys* , *RepeatKeys* , and *MouseKeys* controls do not generate specific events. Instead, the latching, unlatching, locking, or unlocking of modifiers using *StickyKeys* generates *XkbStateNotify* events as described in section 5.4. Repeating keys generate normal *KeyPress* and *KeyRelease* events, though the auto-repeat can be detected using *DetectableAutorepeat* (see section 10.3.3). Finally, *MouseKeys* generates pointer events identical to those of the core pointer device.

The SlowKeys Control

Some users may accidentally bump keys while moving a hand or typing stick toward the key they want. Usually, the keys that are accidentally bumped are just hit for a very short period of time. The *SlowKeys* control helps filter these accidental bumps by telling the server to wait a specified period, called the *SlowKeys acceptance delay* , before delivering key events. If the key is released before this period elapses, no key events are generated. Users can then bump any number of keys on their way to the one they want without accidentally getting those characters. Once they have reached the key they want, they can then hold the desired key long enough for the computer to accept it. *SlowKeys* is a boolean control with one configurable attribute.

When the *SlowKeys* control is active, the server reports the initial key press, subsequent acceptance or rejection, and release of any key to interested clients by sending an appropriate *AccessXNotify* event (see section 10.6.4).

To get the *SlowKeys* acceptance delay for a keyboard device, use *XkbGetSlowKeysDelay* .

Bool *XkbGetSlowKeysDelay* (*display* , *device_spec* , *delay_rtrn*)
Display * *display* ; /* connection to X server */
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
unsigned int * *delay_rtrn* ; /* backfilled with *SlowKeys* delay, ms */

XkbGetSlowKeysDelay requests the attributes of the *SlowKeys* control from the server, waits for a reply and backfills *delay_rtrn* with the *SlowKeys* delay attribute. *XkbGetSlowKeysDelay* returns *True* if successful; if a compatible version of the Xkb extension is not available in the server, *XkbGetSlowKeysDelay* returns *False* .

To set the *SlowKeys* acceptance delay for a keyboard device, use *XkbSetSlowKeys-Delay* .

Bool *XkbSetSlowKeysDelay* (*display* , *device_spec* , *delay*)
Display * *display* ; /* connection to X server */
unsigned int *device_spec* ; /* device to configure, or *XkbUseCoreKbd* */
unsigned int *delay* ; /* *SlowKeys* delay, ms */

XkbSetSlowKeysDelay sends a request to configure the *SlowKeys* control to the server. It does not wait for a reply, and normally returns *True* . Specifying a value of *0* for the *delay* parameter causes *XkbSetSlowKeys* to generate a *BadValue* protocol error. If a compatible version of the Xkb extension is not available in the server *XkbSetSlowKeysDelay* returns *False* .

The BounceKeys Control

Some users may accidentally "bounce" on a key when they release it. They press it once, then accidentally press it again after they release it. The *BounceKeys* control temporarily disables a key after it has been pressed, effectively "debouncing" the keyboard. The period of time the key is disabled after it is released is known as the *BounceKeys delay* . *BounceKeys* is a boolean control.

When the *BounceKeys* control is active, the server reports acceptance or rejection of any key to interested clients by sending an appropriate *AccessXNotify* event (see section 10.6.4).

Use *XkbGetBounceKeysDelay* to query the current *BounceKeys* delay for a key-board device.

Bool *XkbGetBounceKeysDelay* (*display* , *device_spec* , *delay_rtrn*)
Display * *display* ; /* connection to X server */
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
unsigned int * *delay_rtrn* ; /* backfilled with bounce keys delay, ms */

XkbGetBounceKeysDelay requests the attributes of the *BounceKeys* control from the server, waits for a reply, and backfills *delay_rtrn* with the *BounceKeys* delay attribute. *XkbGetBounceKeysDelay* returns *True* if successful; if a compatible version of the Xkb extension is not available in the server *XkbGetSlowKeysDelay* returns *False* .

To set the *BounceKeys* delay for a keyboard device, use *XkbSetBounceKeysDelay* .

Bool *XkbSetBounceKeysDelay* (*display* , *device_spec* , *delay*)
Display * *display* ; /* connection to X server */
unsigned int *device_spec* ; /* device to configure, or *XkbUseCoreKbd* */
unsigned int *delay* ; /* bounce keys delay, ms */

XkbSetBounceKeysDelay sends a request to configure the *BounceKeys* control to the server. It does not wait for a reply and normally returns *True* . Specifying a value of *zero* for the *delay* parameter causes *XkbSetBounceKeysDelay* to generate a *BadValue* protocol error. If a compatible version of the Xkb extension is not available in the server, *XkbSetBounceKeysDelay* returns *False* .

The StickyKeys Control

Some people find it difficult or even impossible to press two keys at once. For example, a one-fingered typist or someone using a mouth stick cannot press the *Shift* and *1* keys at the same time. The *StickyKeys* control solves this problem by changing the behavior of the modifier keys. With *StickyKeys* , the user can first press a modifier, release it, then press another key. For example, to get an exclamation point on a PC-style keyboard, the user can press the *Shift* key, release it, and then press the *1* key.

StickyKeys also allows users to lock modifier keys without requiring special locking keys. When *StickyKeys* is enabled, a modifier is latched when the user presses it just once. The user can press a modifier twice in a row to lock it, and then unlock it by pressing it one more time.

When a modifier is latched, it becomes unlatched when the user presses a nonmodifier key or a pointer button. For instance, to enter the sequence *Shift* + *Control* + *Z* the user could press and release the *Shift* key to latch it, then press and release the *Control* key to latch it, and finally press and release the Z key. Because the *Control* key is a modifier key, pressing it does not unlatch the *Shift* key. Thus, after the user presses the *Control* key, both the *Shift* and *Control* modifiers are latched. When the user presses the *Z* key, the effect is as though the user had pressed *Shift* + *Control* + *Z* . In addition, because the *Z* key is not a modifier key, the *Shift* and *Control* modifiers are unlatched.

Locking a modifier key means that the modifier affects any key or pointer button the user presses until the user unlocks it or it is unlocked programmatically. For example, to enter the sequence ("XKB") on a keyboard where ‘(’ is a shifted ‘9’, ‘)’ is a shifted ‘0’, and ‘"’ is a shifted single quote, the user could press and release the *Shift* key twice to lock the *Shift* modifier. Then, when the user presses the *9* , *'* , *x* , *k* , *b* , *'* , and *0* keys in sequence, it generates ("XKB"). To unlock the *Shift* modifier, the user can press and release the *Shift* key.

StickyKeys is a boolean control with two separate attributes that may be individually configured: one to automatically disable it, and one to control the latching behavior of modifier keys.

StickyKeys Options

The *StickyKeys* control has two options that can be accessed via the *ax_options* of an *XkbControlsRec* structure (see section 10.8). The first option, *TwoKeys* , specifies whether *StickyKeys* should automatically turn off when two keys are pressed at the same time. This feature is useful for shared computers so people who do not

want them do not need to turn *StickyKeys* off if a previous user left *StickyKeys* on. The second option, *LatchToLock* , specifies whether or not *StickyKeys* locks a modifier when pressed twice in a row.

Use *XkbGetStickyKeysOptions* to query the current *StickyKeys* attributes for a keyboard device.

Bool *XkbGetStickyKeysOptions* (*display* , *device_spec* , *options_rtrn*)
Display * *display* ; /* connection to X server */
unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */
unsigned int * *options_rtrn* ; /* backfilled with StickyKeys option mask */

XkbGetStickyKeysOptions requests the attributes of the *StickyKeys* control from the server, waits for a reply, and backfills *options_rtrn* with a mask indicating whether the individual *StickyKeys* options are on or off. Valid bits in *options_rtrn* are:

XkbAX_TwoKeysMask
XkbAX_LatchToLockMask

XkbGetStickyKeysOptions returns *True* if successful; if a compatible version of the Xkb extension is not available in the server *XkbGetStickyKeysOptions* returns *False* .

To set the *StickyKeys* attributes for a keyboard device, use *XkbSetStickyKeysOptions* .

Bool *XkbSetStickyKeysOptions* (*display* , *device_spec, mask, values*)
Display * *display* ; /* connection to X server */
unsigned int *device_spec* ; /* device to configure, or XkbUseCoreKbd */
unsigned int *mask* ; /* selects StickyKeys attributes to modify */
unsigned int *values;* /* values for selected attributes */

XkbSetStickyKeysOptions sends a request to configure the *StickyKeys* control to the server. It does not wait for a reply and normally returns *True* . The valid bits to use for both the *mask* and *values* parameters are:

XkbAX_TwoKeysMask
XkbAX_LatchToLockMask

If a compatible version of the Xkb extension is not available in the server, *XkbSetStickyKeysOptions* returns *False* .

Controls for General Keyboard Mapping

There are several controls that apply to the keyboard mapping in general. They control handling of out-of-range group indices and how modifiers are processed and consumed in the server. These are:

GroupsWrap
IgnoreGroupLock

```
IgnoreLockMods
InternalMods
```

IgnoreGroupLock is a boolean control; the rest are always active.

Without the modifier processing options provided by Xkb, passive grabs set via translations in a client (for example, *Alt<KeyPress>space*) do not trigger if any modifiers other than those specified by the translation are set. This results in problems in the user interface when either *NumLock* or a secondary keyboard group is active. The *IgnoreLockMods* and *IgnoreGroupLock* controls make it possible to avoid this behavior without exhaustively specifying a grab for every possible modifier combination.

The GroupsWrap Control

The *GroupsWrap* control determines how illegal groups are handled on a global basis. There are a number of valid keyboard sequences that can cause the effective group number to go out of range. When this happens, the group must be normalized back to a valid number. The *GroupsWrap* control specifies how this is done.

When dealing with group numbers, all computations are done using the group index, which is the group number minus one. There are three different algorithms; the *GroupsWrap* control specifies which one is used:

- XkbRedirectIntoRange

  All invalid group numbers are converted to a valid group number by taking the last four bits of the *GroupsWrap* control and using them as the group index. If the result is still out of range, Group one is used.

- XkbClampIntoRange

  All invalid group numbers are converted to the nearest valid group number. Group numbers larger than the highest supported group number are mapped to the highest supported group; those less than one are mapped to group one.

- XkbWrapIntoRange

  All invalid group numbers are converted to a valid group number using integer modulus applied to the group index.

There are no convenience functions for manipulating the *GroupsWrap* control. Manipulate the *GroupsWrap* control via the *groups_wrap* field in the *XkbControlsRec* structure, then use *XkbSetControls* and *XkbGetControls* (see section 10.9 and section 10.10) to query and change this control.

Note

See also section 15.3.2 or a discussion of the related field, *group_info* , which also normalizes a group under certain circumstances.

The IgnoreLockMods Control

The core protocol does not provide a way to exclude specific modifiers from grab calculations, with the result that locking modifiers sometimes have unanticipated side effects.

The *IgnoreLockMods* control specifies modifiers that should be excluded from grab calculations. These modifiers are also not reported in any core events except *KeyPress* and *KeyRelease* events that do not activate a passive grab and that do not occur while a grab is active.

Manipulate the *IgnoreLockMods* control via the *ignore_lock* field in the *XkbControlsRec* structure, then use *XkbSetControls* and *XkbGetControls* (see sections 10.9 and 10.10) to query and change this control. Alternatively, use *XkbSetIgnoreLockMods* .

To set the modifiers that, if locked, are not to be reported in matching events to passive grabs, use *XkbSetIgnoreLockMods.*

Bool *XkbSetIgnoreLockMods* (*display, device_spec, affect_real, real_values, affect_virtual, virtual_values*)

Display * *display* ; /* connection to the X server */

unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */

unsigned int *affect_real* ; /* mask of real modifiers affected by this call */

unsigned int *real_values* ; /* values for affected real modifiers (1=>set, 0=>unset) */

unsigned int *affect_virtual* ; /* mask of virtual modifiers affected by this call */

unsigned int *virtual_values* ; /* values for affected virtual modifiers (1=>set, 0=>unset) */

XkbSetIgnoreLockMods sends a request to the server to change the server's *IgnoreLockMods* control. *affect_real* and *real_values* are masks of real modifier bits indicating which real modifiers are to be added and removed from the server's *IgnoreLockMods* control. Modifiers selected by both *affect_real* and *real_values* are added to the server's *IgnoreLockMods* control; those selected by *affect_real* but not by *real_values* are removed from the server's *IgnoreLockMods* control. Valid values for *affect_real* and *real_values* consist of any combination of the eight core modifier bits: *ShiftMask* , *LockMask* , *ControlMask* , *Mod1Mask* - *Mod5Mask* . *affect_virtual* and *virtual_values* are masks of virtual modifier bits indicating which virtual modifiers are to be added and removed from the server's *IgnoreLockMods* control. Modifiers selected by both *affect_virtual* and *virtual_values* are added to the server's *IgnoreLockMods* control; those selected by *affect_virtual* but not by *virtual_values* are removed from the server's *IgnoreLockMods* control. See section 7.1 for a discussion of virtual modifier masks to use in *affect_virtual* and *virtual_values* . *XkbSetIgnoreLockMods* does not wait for a reply from the server. It returns *True* if the request was sent, and *False* otherwise.

The IgnoreGroupLock Control

The *IgnoreGroupLock* control is a boolean control with no attributes. If enabled, it specifies that the locked state of the keyboard group should not be considered when activating passive grabs.

Because *IgnoreGroupLock* is a boolean control with no attributes, use the general boolean controls functions (see section 10.1) to change its state.

The InternalMods Control

The core protocol does not provide any means to prevent a modifier from being reported in events sent to clients; Xkb, however makes this possible via the *InternalMods* control. It specifies modifiers that should be consumed by the server and not reported to clients. When a key is pressed and a modifier that has its bit set in the *InternalMods* control is reported to the server, the server uses the modifier when determining the actions to apply for the key. The server then clears the bit, so it is not actually reported to the client. In addition, modifiers specified in the *InternalMods* control are not used to determine grabs and are not used to calculate core protocol compatibility state.

Manipulate the *InternalMods* control via the *internal* field in the *XkbControlsRec* structure, using *XkbSetControls* and *XkbGetControls* (see sections10.9 and 10.10). Alternatively, use *XkbSetServerInternalMods* .

To set the modifiers that are consumed by the server before events are delivered to the client, use *XkbSetServerInternalMods.*

Bool *XkbSetServerInternalMods* (*display, device_spec, affect_real, real_values, affect_virtual, virtual_values*)

Display * *display* ; /* connection to the X server */

unsigned int *device_spec* ;‘ /* device ID, or *XkbUseCoreKbd* */

unsigned int *affect_real* ; /* mask of real modifiers affected by this call */

unsigned int *real_values* ; /* values for affected real modifiers (1=>set, 0=>unset) */

unsigned int *affect_virtual* ; /* mask of virtual modifiers affected by this call */

unsigned int *virtual_values* ; /* values for affected virtual modifiers (1=>set, 0=>unset) */

XkbSetServerInternalMods sends a request to the server to change the internal modifiers consumed by the server. *affect_real* and *real_values* are masks of real modifier bits indicating which real modifiers are to be added and removed from the server’s internal modifiers control. Modifiers selected by both *affect_real* and *real_values* are added to the server’s internal modifiers control; those selected by *affect_real* but not by *real_values* are removed from the server’s internal modifiers mask. Valid values for *affect_real* and *real_values* consist of any combination of the eight core modifier bits: *ShiftMask* , *LockMask* , *ControlMask* , *Mod1Mask* - *Mod5Mask* . *affect_virtual* and *virtual_values* are masks of virtual modifier bits indicating which virtual modifiers are to be added and removed from the server’s internal modifiers control. Modifiers selected by both *affect_virtual* and *virtual_values* are added to the server’s internal modifiers control; those selected by *affect_virtual* but not by *virtual_values* are removed from the server’s internal modifiers control. See section 7.1 for a discussion of virtual modifier masks to use in *affect_virtual* and *virtual_values* . *XkbSetServerInternalMods* does not wait for a reply from the server. It returns *True* if the request was sent and *False* otherwise.

The XkbControlsRec Structure

Many of the individual controls described in sections 10.1 through 10.7 may be manipulated via convenience functions discussed in those sections. Some of them, how-

ever, have no convenience functions. The *XkbControlsRec* structure allows the manipulation of one or more of the controls in a single operation and to track changes to any of them in conjunction with the *XkbGetControls* and *XkbSetControls* functions. This is the only way to manipulate those controls that have no convenience functions.

The *XkbControlsRec* structure is defined as follows:

```
#define      XkbMaxLegalKeyCode       255
#define      XkbPerKeyBitArraySize    ((XkbMaxLegalKeyCode+1)/8)


typedef struct {
      unsigned char        mk_dflt_btn;       /* default button for keyboard drive
      unsigned char        num_groups;        /* number of keyboard groups */
      unsigned char        groups_wrap;       /* how to wrap out-of-bounds groups
      XkbModsRec           internal;          /* defines server internal modifiers
      XkbModsRec           ignore_lock;       /* modifiers to ignore when checking
      unsigned int         enabled_ctrls;     /* 1 bit => corresponding boolean co
      unsigned short       repeat_delay;      /* ms delay until first repeat */
      unsigned short       repeat_interval;   /* ms delay between repeats */
      unsigned short       slow_keys_delay;   /* ms minimum time key must be down
      unsigned short       debounce_delay;    /* ms delay before key reactivated *
      unsigned short       mk_delay;          /* ms delay to second mouse motion e
      unsigned short       mk_interval;       /* ms delay between repeat mouse eve
      unsigned short       mk_time_to_max;    /* # intervals until constant mouse
      unsigned short       mk_max_speed;      /* multiplier for maximum mouse spee
      short                mk_curve;          /* determines mouse move curve type
      unsigned short       ax_options;        /* 1 bit => Access X option enabled
      unsigned short       ax_timeout;        /* seconds until Access X disabled *
      unsigned short       axt_opts_mask;     /* 1 bit => options to reset on Acce
      unsigned short       axt_opts_values;   /* 1 bit => turn option on, 0=> off
      unsigned int         axt_ctrls_mask;    /* which bits in  enabled_ctrls to m
      unsigned int         axt_ctrls_values;  /* values for new bits in  enabled_c
      unsigned char        per_key_repeat[XkbPerKeyBitArraySize];           /* per
} XkbControlsRec, *XkbControlsPtr;
```

The general-purpose functions that work with the *XkbControlsRec* structure use a mask to specify which controls are to be manipulated. Table 10.6 lists these controls, the masks used to select them in the general function calls (*which* parameter), and the data fields in the *XkbControlsRec* structure that comprise each of the individual controls. Also listed are the bit used to turn boolean controls on and off and the section where each control is described in more detail.

Table 10.6. Xkb Controls

Control	Control Selection Mask (which parameter)	Relevant XkbControlsRec Data Fields	Boolean Control enabled_ctrls bit	Section
AccessXFeedback	XkbAccessXFeedbackMask	ax_options: XkbAX_*FBMask	XkbAccessXFeedbackMask	10.6.3
AccessXKeys			XkbAccessXKeysMask	10.6.1

Control	Control Selection Mask (which parameter)	Relevant XkbControlsRec Data Fields	Boolean Control enabled_ctrls bit	Section
AccessXTimeout	XkbAccessXTimeoutMask	ax_timeout axt_opts_mask axt_opts_values axt_ctrls_mask axt_ctrls_values	XkbAccessXTimeoutMask	10.6.2
AudibleBell			XkbAudibleBellMask	9.2
AutoReset				10.1.2
BounceKeys	XkbBounceKeysMask	debounce_delay	XkbBounceKeysMask	10.6.7
Detectable-Autorepeat				10.3.3
EnabledControls	XkbControlsEnabledMask	enabled_ctrls	*Non-Boolean Control*	10.1.1
GroupsWrap	XkbGroupsWrapMask	groups_wrap	*Non-Boolean Control*	10.7.1
IgnoreGroupLock			XkbIgnoreGroupLockMask	10.7.3
IgnoreLockMods	XkbIgnoreLockModsMask	ignore_lock	*Non-Boolean Control*	5.1
InternalMods	XkbInternalModsMask	internal	*Non-Boolean Control*	5.1
MouseKeys	XkbMouseKeysMask	mk_dflt_btn	XkbMouseKeysMask	10.5.1
MouseKeysAccel	XkbMouseKeysAccelMask	mk_delay mk_interval mk_time_to_max mk_max_speed mk_curve	XkbMouseKeysAccelMask	10.5.2
Overlay1			XkbOverlay1Mask	10.4
Overlay2			XkbOverlay2Mask	10.4
PerKeyRepeat	XkbPerKeyRepeatMask	per_key_repeat	*Non-Boolean Control*	10.3.1
RepeatKeys	XkbRepeatKeysMask	repeat_delay repeat_interval	XkbRepeatKeysMask	10.3
SlowKeys	XkbSlowKeysMask	slow_keys_delay	XkbSlowKeysMask	10.6.6

Control	Control Selection Mask (which parameter)	Relevant XkbControlsRec Data Fields	Boolean Control enabled_ctrls bit	Section
StickyKeys	XkbStickyKeysMask	ax_options: XkbAX_TwoKeysMask XkbAX_LatchToLockMask	XkbStickyKeysMask	10.6.8

Table 10.7 shows the actual values for the individual mask bits used to select controls for modification and to enable and disable the control. Note that the same mask bit is used to specify general modifications to the parameters used to configure the control (*which*), and to enable and disable the control (*enabled_ctrls*). The anomalies in the table (no "ok" in column) are for controls that have no configurable attributes; and for controls that are not boolean controls and therefore cannot be enabled or disabled.

Table 10.7. Controls Mask Bits

Mask Bit	which or changed_ctrls	enabled_ctrls	Value
XkbRepeatKeysMask	ok	ok	(1L<<0)
XkbSlowKeysMask	ok	ok	(1L<<1)
XkbBounceKeysMask	ok	ok	(1L<<2)
XkbStickyKeysMask	ok	ok	(1L<<3)
XkbMouseKeysMask	ok	ok	(1L<<4)
XkbMouseKeysAccelMask	ok	ok	(1L<<5)
XkbAccessXKeysMask	ok	ok	(1L<<6)
XkbAccessXTimeoutMask	ok	ok	(1L<<7)
XkbAccessXFeedback-Mask	ok	ok	(1L<<8)
XkbAudibleBellMask		ok	(1L<<9)
XkbOverlay1Mask		ok	(1L<<10)
XkbOverlay2Mask		ok	(1L<<11)
XkbIgnoreGroupLock-Mask		ok	(1L<<12)
XkbGroupsWrapMask	ok		(1L<<27)
XkbInternalModsMask	ok		(1L<<28)
XkbIgnoreLockModsMask	ok		(1L<<29)
XkbPerKeyRepeatMask	ok		(1L<<30)
XkbControlsEnabledMask	ok		(1L<<31)
XkbAccessXOptionsMask	ok	ok	(XkbStick-yKeysMask | Xk-bAccessXFeedback-Mask)
XkbAllBooleanCtrlsMask		ok	(0x00001FFF)
XkbAllControlsMask	ok		(0xF8001FFF)

The individual fields of the *XkbControlsRec* structure are defined as follows.

mk_dflt_btn

mk_dflt_btn is an attribute of the MouseKeys control (see section 10.5 *). It* specifies the mouse button number to use for keyboard simulated mouse button operations. Its value should be one of the core symbols *Button1* - *Button5* .

num_groups

num_groups is not a part of any control, but is reported in the *XkbControlsRec* structure whenever any of its components are fetched from the server. It reports the number of groups the particular keyboard configuration uses and is computed automatically by the server whenever the keyboard mapping changes.

groups_wrap

groups_wrap is an attribute of the *GroupsWrap* control (see section 10.7.1). It specifies the handling of illegal groups on a global basis. Valid values for *groups_wrap* are shown in Table 10.8.

Table 10.8. GroupsWrap options (groups_wrap field)

groups_wrap symbolic name	value
XkbWrapIntoRange	(0x00)
XkbClampIntoRange	(0x40)
XkbRedirectIntoRange	(0x80)

When *groups_wrap* is set to *XkbRedirectIntoRange* , its four low-order bits specify the index of the group to use.

internal

internal is an attribute of the *InternalMods* control (see section 10.7.4). It specifies modifiers to be consumed in the server and not passed on to clients when events are reported. Valid values consist of any combination of the eight core modifier bits: *ShiftMask* , *LockMask* , *ControlMask* , *Mod1Mask* - *Mod5Mask* .

ignore_lock

ignore_lock is an attribute of the *IgnoreLockMods* control (see section 10.7.2). It specifies modifiers to be ignored in grab calculations. Valid values consist of any combination of the eight core modifier bits: *ShiftMask* , *LockMask* , *ControlMask* , *Mod1Mask* - *Mod5Mask* .

enabled_ctrls

enabled_ctrls is an attribute of the *EnabledControls* control (see section 10.1.1). It contains one bit per boolean control. Each bit determines whether the corresponding control is enabled or disabled; a one bit means the control is enabled. The mask bits used to enable these controls are listed in Table 10.7, using only those masks with "ok" in the *enabled_ctrls* column.

repeat_delay and repeat_interval

repeat_delay and *repeat_interval* are attributes of the *RepeatKeys* control (see section 10.3.2). *repeat_delay* is the initial delay before a key begins repeating, in milliseconds; *repeat_interval* is the delay between subsequent key events, in milliseconds.

slow_keys_delay

slow_keys_delay is an attribute of the *SlowKeys* control (see section 10.6.6). Its value specifies the *SlowKeys* acceptance delay period in milliseconds before a key press is accepted by the server.

debounce_delay

debounce_delay is an attribute of the *BounceKeys* control (see section 10.6.7). Its value specifies the *BounceKeys* delay period in milliseconds for which the key is disabled after having been pressed before another press of the same key is accepted by the server.

mk_delay, mk_interval, mk_time_to_max, mk_max_speed, and mk_curve

mk_delay , *mk_interval* , *mk_time_to_max* , *mk_max_speed* , and *mk_curve* are attributes of the *MouseKeysAccel* control. Refer to section 10.5.2 for a description of these fields and the units involved.

ax_options

The *ax_options* field contains attributes used to configure two different controls, the *StickyKeys* control (see section 10.6.8) and the *AccessXFeedback* control (see section 10.6.3). The *ax_options* field is a bitmask and may include any combination of the bits defined in Table 10.9.

Table 10.9. Access X Enable/Disable Bits (ax_options field)

Access X Control	ax_options bit	value
AccessXFeedback	XkbAX_SKPressFBMask	(1L<<0)
	XkbAX_SKAcceptFBMask	(1L << 1)
	XkbAX_FeatureFBMask	(1L << 2)
	XkbAX_SlowWarnFBMask	(1L << 3)
	XkbAX_IndicatorFBMask	(1L << 4)
	XkbAX_StickyKeysFBMask	(1L << 5)
	XkbAX_SKReleaseFBMask	(1L << 8)
	XkbAX_SKRejectFBMask	(1L << 9)
	XkbAX_BKRejectFBMask	(1L << 10)
	XkbAX_DumbBellFBMask	(1L << 11)
StickyKeys	XkbAX_TwoKeysMask	(1L << 6)
	XkbAX_LatchToLockMask	(1L << 7)
	XkbAX_AllOptionsMask	(0xFFF)

The fields pertaining to each control are relevant only when the control is enabled (*XkbAccessXFeedbackMask* or *XkbStickyKeysMask* bit is turned on in the *enabled_cntrls* field).

Xkb provides a set of convenience macros for working with the *ax_options* field of an *XkbControlsRec* structure:

```
#define      XkbAX_NeedOption
(c,w)      ((c)->ax_options&(w))
```

The *XkbAX_NeedOption* macro is useful for determining whether a particular AccessX option is enabled or not. It accepts a pointer to an *XkbControlsRec* structure and a valid mask bit from Table 10.9. If the specified mask bit in the *ax_options* field of the controls structure is set, the macro returns the mask bit. Otherwise, it returns zero. Thus,

XkbAX_NeedOption(ctlrec, XkbAX_LatchToLockMask)

is nonzero if the latch to lock transition for latching keys is enabled, and zero if it is disabled. Note that *XkbAX_NeedOption* only determines whether or not the particular capability is configured to operate; the *XkbAccessXFeedbackMask* bit must also be turned on in *enabled_ctrls* for the capability to actually be functioning.

```
#define      XkbAX_AnyFeedback
(c)      ((c)->enabled_ctrls&XkbAccessXFeedbackMask)
```

The *XkbAX_AnyFeeback* macro accepts a pointer to an *XkbControlsRec* structure and tells whether the *AccessXFeedback* control is enabled or not. If the *AccessXFeedback* control is enabled, the macro returns *XkbAccessXFeedbackMask* . Otherwise, it returns zero.

```
#define      XkbAX_NeedFeedback
(c,w)      (XkbAX_AnyFeedback(c)&&XkbAX_NeedOption(c,w))
```

The *XkbAX_NeedFeedback* macro is useful for determining if both the *AccessXFeedback* control and a particular AccessX feedback option are enabled. The macro accepts a pointer to an *XkbControlsRec* structure and a feedback option from the table above. If both the *AccessXFeedback* control and the specified feedback option are enabled, the macro returns *True* . Otherwise it returns *False* .

ax_timeout, axt_opts_mask, axt_opts_values, axt_ctrls_mask, and axt_ctrls_values

ax_timeout , *act_opts_mask* , *axt_opts_values* , *axt_ctrls_mask* , and *axt_ctrls_values* are attributes of the *AccessXTimeout* control. Refer to section 10.6.2 for a description of these fields and the units involved.

per_key_repeat

The *per_key_repeat* field mirrors the *auto_repeats* field of the core protocol *XKeyboardState* structure: changing the *auto_repeats* field automatically changes *per_key_repeat* and vice versa. It is provided for convenience and to reduce protocol traffic. For example, to obtain the individual repeat key behavior as well as the repeat delay and rate, use *XkbGetControls* . If the *per_key_repeat* were not in this structure, you would have to call both *XGetKeyboardControl* and *XkbGetControls* to get this information. The bits correspond to keycodes. The first seven keys (keycodes 1-7) are indicated in *per_key_repeat* [0], with bit position 0 (low order) corresponding to the fictitious keycode 0. Following array elements correspond to 8 keycodes per element. A 1 bit indicates that the key is a repeating key.

Querying Controls

Use *XkbGetControls* to find the current state of Xkb server controls.

Status *XkbGetControls* (*display, which, xkb)*

Display * *display* ; /* connection to X server */

unsigned long *which* ; /* mask of controls requested */

XkbDescPtr *xkb* ; /* keyboard description for controls information*/

XkbGetControls queries the server for the requested control information, waits for a reply, and then copies the server's values for the requested information into the *ctrls* structure of the *xkb* argument. Only those components specified by the *which* parameter are copied. Valid values for *which* are any combination of the masks listed in Table 10.7 that have "ok" in the *which* column.

If *xkb -> ctrls* is *NULL* , *XkbGetControls* allocates and initializes it before obtaining the values specified by *which* . If *xkb -> ctrls* is not *NULL* , *XkbGetControls* modifies only those portions of *xkb -> ctrls* corresponding to the values specified by *which* .

XkbGetControls returns *Success* if successful; otherwise, it returns *BadAlloc* if it cannot obtain sufficient storage, *BadMatch* if *xkb* is *NULL* or *which* is empty, or *BadImplementation* .

To free the *ctrls* member of a keyboard description, use *XkbFreeControls* (see section 10.12)

The *num_groups* field in the *ctrls* structure is always filled in by *XkbGetControls* , regardless of which bits are selected by *which* .

Changing Controls

There are two ways to make changes to controls: either change a local copy keyboard description and call *XkbSetControls* , or, to reduce network traffic, use an *XkbControlsChangesRec* structure and call *XkbChangeControls* .

To change the state of one or more controls, first modify the *ctrls* structure in a local copy of the keyboard description and then use *XkbSetControls* to copy those changes to the X server.

Bool *XkbSetControls* (*display, which, xkb)*

Display * *display* ; /* connection to X server */

unsigned long *which* ; /* mask of controls to change */

XkbDescPtr *xkb* ; /* *ctrls* field contains new values to be set */

For each bit that is set in the *which* parameter, *XkbSetControls* sends the corresponding values from the *xkb -> ctrls* field to the server. Valid values for *which* are any combination of the masks listed in Table 10.7 that have "ok" in the *which* column.

If *xkb -> ctrls* is *NULL* , the server does not support a compatible version of Xkb, or the Xkb extension has not been properly initialized, *XkbSetControls* returns *False* . Otherwise, it sends the request to the X server and returns *True* .

Note that changes to attributes of controls in the *XkbControlsRec* structure are apparent only when the associated control is enabled, although the corresponding values are still updated in the X server. For example, the *repeat_delay* and

repeat_interval fields are ignored unless the *RepeatKeys* control is enabled (that is, the X server's equivalent of *xkb->ctrls* has *XkbRepeatKeyMask* set in *enabled_ctrls*). It is permissible to modify the attributes of a control in one call to XkbSetControls and enable the control in a subsequent call. See section 10.1.1 for more information on enabling and disabling controls.

Note that the *enabled_ctrls* field is itself a control — the *EnabledControls* control. As such, to set a specific configuration of enabled and disabled boolean controls, you must set *enabled_ctrls* to the appropriate bits to enable only the controls you want and disable all others, then specify the *XkbControlsEnabledMask* in a call to *XkbSetControls* . Because this is somewhat awkward if all you want to do is enable and disable controls, and not modify any of their attributes, a convenience function is also provided for this purpose (*XkbChangeEnabledControls* , section 10.1.1).

The XkbControlsChangesRec Structure

The *XkbControlsChangesRec* structure allows applications to track modifications to an *XkbControlsRec* structure and thereby reduce the amount of traffic sent to the server. The same *XkbControlsChangesRec* structure may be used in several successive modifications to the same *XkbControlsRec* structure, then subsequently used to cause all of the changes, and only the changes, to be propagated to the server. The *XkbControlsChangesRec* structure is defined as follows:

```
typedef struct _XkbControlsChanges {
      unsigned int changed_ctrls;          /* bits indicating changed control data
      unsigned int enabled_ctrls_changes;  /* bits indicating enabled/disabled con
      Bool         num_groups_changed;     /*  True if
                                              number of keyboard groups changed */
} XkbControlsChangesRec,*XkbControlsChangesPtr;
```

The *changed_ctrls* field is a mask specifying which logical sets of data in the controls structure have been modified. In this context, modified means *set* , that is, if a value is set to the same value it previously contained, it has still been modified, and is noted as changed. Valid values for *changed_ctrls* are any combination of the masks listed in Table 10.7 that have "ok" in the *changed_ctrls* column. Setting a bit implies the corresponding data fields from the "Relevant XkbControlsRec Data Fields" column in Table 10.6 have been modified. The *enabled_ctrls_changes* field specifies which bits in the *enabled_ctrls* field have changed. If the number of keyboard groups has changed, the *num_groups_changed* field is set to *True*.

If you have an Xkb description with controls that have been modified and an *XkbControlsChangesRec* that describes the changes that have been made, the *XkbChangeControls* function provides a flexible method for updating the controls in a server to match those in the changed keyboard description.

Bool *XkbChangeControls* (*dpy, xkb, changes*)

Display * *dpy* ; /* connection to X server */

XkbDescPtr *xkb* ; /* keyboard description with changed *xkb->ctrls* */

XkbControlsChangesPtr *changes* ; /* which parts of *xkb->ctrls* have changed */

XkbChangeControls copies any controls fields specified by *changes* from the keyboard description controls structure, *xkb -> ctrls* , to the server specified by *dpy* .

Tracking Changes to Keyboard Controls

Whenever a field in the controls structure changes in the server's keyboard description, the server sends an *XkbControlsNotify* event to all interested clients.To receive *XkbControlsNotify* events under all possible conditions, use *XkbSelectEvents* (see section 4.3) and pass *XkbControlsNotifyMask* in both *bits_to_change* and *values_for_bits* .

To receive *XkbControlsNotify* events only under certain conditions, use *XkbSelectEventDetails* using *XkbControlsNotify* as the *event_type* and specifying the desired state changes in *bits_to_change* and *values_for_bits* using mask bits from Table 10.7.

The structure for the *XkbControlsNotify* event is defined as follows:

```
typedef struct {
      int             type;             /* Xkb extension base event code */
      unsigned long   serial;           /* X server serial number for event */
      Bool            send_event;       /*  True => synthetically generated */
      Display *       display;          /* server connection where event generated *
      Time            time;             /* server time when event generated */
      int             xkb_type;         /*  XkbCompatMapNotify */
      int             device;           /* Xkb device ID, will not be  XkbUseCoreKbd
      unsigned int    changed_ctrls;    /* bits indicating which controls data have
      unsigned int    enabled_ctrls;    /* controls currently enabled in server */
      unsigned int    enabled_ctrl_changes;  /* bits indicating enabled/disabled co
      int             num_groups;       /* current number of keyboard groups */
      KeyCode         keycode;          /* != 0 => keycode of key causing change */
      char            event_type;       /* Type of event causing change */
      char            req_major;        /* major event code of event causing change
      char            req_minor;        /* minor event code of event causing change
} XkbControlsNotifyEvent;
```

The *changed_ctrls* field specifies the controls components that have changed and consists of bits taken from the masks defined in Table 10.7 with "ok" in the *changed_ctrls* column.

The controls currently enabled in the server are reported in the *enabled_ctrls* field. If any controls were just enabled or disabled (that is, the contents of the *enabled_ctrls* field changed), they are flagged in the *enabled_ctrl_changes* field. The valid bits for these fields are the masks listed in Table 10.7 with "ok" in the *enabled_ctrls* column. The *num_groups* field reports the number of groups bound to the key belonging to the most number of groups and is automatically updated when the keyboard mapping changes.

If the change was caused by a request from a client, the *keycode* and *event_type* fields are set to *zero* and the *req_major* and *req_minor* fields identify the request. The *req_major* value is the same as the major extension opcode. Otherwise, *event_type* is set to the type of event that caused the change (one of *KeyPress* , *KeyRelease* , *DeviceKeyPress* , *DeviceKeyRelease* , *ButtonPress* or *ButtonRelease*), and *req_major* and *req_minor* are undefined. If *event_type* is *KeyPress* , *KeyRelease* , *DeviceKeyPress* , or *DeviceKeyRelease* , the *keycode* field is set to the key that caused the change. If *event_type* is *ButtonPress* or *ButtonRelease* , *keycode* contains the button number.

When a client receives an *XkbControlsNotify* event, it can note the changes in a changes structure using *XkbNoteControlsChanges* .

void *XkbNoteControlsChanges* (*changes* , *new* , *wanted*)
XkbControlsChangesPtr *changes* ; /* records changes indicated by new */
XkbControlsNotifyEvent * *new* ; /* tells which things have changed */
unsigned int *wanted* ; /* tells which parts of new to record in changes */

The *wanted* parameter is a bitwise inclusive OR of bits taken from the set of masks specified in Table 10.7 with "ok" in the *changed_ctrls* column. *XkbNoteControlsChanges* copies any changes reported in *new* and specified in *wanted* into the changes record specified by *old* .

Use *XkbGetControlsChanges* to update a local copy of a keyboard description with the changes previously noted by one or more calls to *XkbNoteControlsChanges.*

Status *XkbGetControlsChanges* (*dpy* , *xkb* , *changes*)
Display * *dpy* ; /* connection to X server */
XkbDescPtr *xkb* ; /* *xkb->ctrls* will be updated */
XkbNameChangesPtr *changes* ; /* indicates which parts of *xkb->ctrls* to update */

XkbGetControlsChanges examines the *changes* parameter, queries the server for the necessary information, and copies the results into the *xkb -> ctrls* keyboard description. If the *ctrls* field of *xkb* is *NULL* , *XkbGetControlsChanges* allocates and initializes it. To free the *ctrls* field, use *XkbFreeControls* (see section 10.12).

XkbGetControlsChanges returns *Success* if successful and can generate *BadAlloc* , *BadImplementation,* and *BadMatch* errors.

Allocating and Freeing an XkbControlsRec

The need to allocate an *XkbControlsRec* structure seldom arises; Xkb creates one when an application calls *XkbGetControls* or a related function. For those situations where there is not an *XkbControlsRec* structure allocated in the *XkbDescRec* , allocate one by calling *XkbAllocControls* .

Status *XkbAllocControls* (*xkb, which*)
XkbDescPtr *xkb* ; /* Xkb description in which to allocate ctrls rec */
unsigned int *which* ; /* mask of components of *ctrls* to allocate */

XkbAllocControls allocates the *ctrls* field of the *xkb* parameter, initializes all fields to zero, and returns *Success* . If the *ctrls* field is not *NULL* , *XkbAllocControls* simply returns *Success* . If *xkb* is *NULL* , *XkbAllocControls* reports a *BadMatch* error. If the *ctrls* field could not be allocated, it reports a *BadAlloc* error.

The *which* mask specifies the individual fields of the *ctrls* structure to be allocated and can contain any of the valid masks defined in Table 10.7. Because none of the currently existing controls have any structures associated with them, which is currently of little practical value in this call.

To free memory used by the *ctrls* member of an *XkbDescRec* structure, use *XkbFreeControls:*

void *XkbFreeControls* (*xkb, which, free_all*)
XkbDescPtr *xkb* ; /* Xkb description in which to free controls components */
unsigned int *which* ; /* mask of components of *ctrls* to free */
Bool *free_all* ; /* *True* => free everything + ctrls itself */

XkbFreeControls frees the specified components of the *ctrls* field in the *xkb* keyboard description and sets the corresponding structure component values to *NULL* or *zero* . The *which* mask specifies the fields of *ctrls* to be freed and can contain any of the controls components specified in Table 10.7.

If *free_all* is *True* , *XkbFreeControls* frees every non- *NULL* structure component in the controls, frees the *XkbControlsRec* structure referenced by the *ctrls* member of *xkb* , and sets *ctrls* to *NULL.*

The Miscellaneous Per-client Controls

You can configure the boolean per-client controls which affect the state reported in button and key events. See section 12.1.1, 12.3, 12.5, and 16.3.11 of the XKB Protocol specification for more details.

To get the current values of the *per-client* controls, use *XkbGetPerClientControls* .

Bool *XkbGetPerClientControls* (*dpy* , *ctrls*)
Display * *dpy* ; /* connection to X server */
unsigned int * *ctrls* ; /* 1 bit => corresponding control is on */

XkbGetPerClientControls backfills *ctrls* with the *per-client* control attributes for this particular client. It returns *True* if successful, and *False* otherwise.

To change the current values of the *per-client* control attributes, use *XkbSetPerClientControls.*

Bool *XkbSetPerClientControls* (*dpy* , *ctrls*)
Display * *dpy* ; /* connection to X server */
unsigned int *change* ; /* 1 bit => change control */
unsigned int * *value* ; /* 1 bit => control on */

XkbSetPerClientControls changes the per-client values for the controls selected by change to the corresponding value in value. Legal values for change and value are: XkbPCF_GrabsUseXKBStateMask, XkbPCF_LookupStateWhenGrabbed, and XkbPCF_SendEventUsesXKBState. More than one control may be changed at one time by OR-ing the values together. XkbSetPerClientControls backfills value with the per-client control attributes for this particular client. It returns *True* if successful, and *False* otherwise.

Chapter 11. X Library Controls

The Xkb extension is composed of two parts: a server extension, and a client-side X library extension. Chapter 10 discusses functions used to modify controls affecting the behavior of the server portion of the Xkb extension. This chapter discusses functions used to modify controls that affect only the behavior of the client portion of the extension; these controls are known as Library Controls.

All of the Library Controls are boolean flags that may be enabled and disabled. The controls can be divided into several categories:

- Controls affecting general string lookups
- Controls affecting compose processing
- Controls affecting event delivery

There are two types of string lookups performed by *XLookupString* . The first type involves translating a single keycode into a string; the controls in the first category affect this type of lookup. The second type involves translating a series of keysyms into a string; the controls in the second category affect this type of lookup.

An Xkb implementation is required to support the programming interface for all of the controls. However, an implementation may choose not to support the semantics associated with the controls that deal with compose processing. In this case, a program that accesses these controls should still function normally; however, the feedback that would normally occur with the controls enabled may be missing.

Controls Affecting Keycode-to-String Translation

The first type of string lookups, which are here called *simple string lookups* , involves translating a single keycode into a string. Because these simple lookups involve only a single keycode, all of the information needed to do the translation is contained in the keyboard state in a single event. The controls affecting simple string lookups are:

```
ForceLatin1Lookup
ConsumeLookupMods
LevelOneUsesShiftAndLock
```

ForceLatin1Lookup

If the *ForceLatin1Lookup* control is enabled, *XLookupString* only returns strings using the Latin1 character set. If *ForceLatin1Lookup* is not enabled, *XLookupString* can return characters that are not in the Latin1 set. By default, this control is disabled, allowing characters outside of the Latin1 set to be returned.

ConsumeLookupMods

Simple string lookups in *XLookupString* involve two different translation phases. The first phase translates raw device keycodes to individual keysyms. The second

phase attempts to map the resulting keysym into a string of one or more characters. In the first phase, some of the modifiers are normally used to determine the appropriate shift level for a key.

The *ConsumeLookupMods* control determines whether or not *XLookupString consumes* the modifiers it uses during the first phase of processing (mapping a keycode to a keysym). When a modifier is consumed, it is effectively removed from the working copy of the keyboard state information *XLookupString* is using and appears to be unset for the remainder of the processing.

If the *ConsumeLookupMods* control is enabled, *XLookupString* does not use the modifiers used to translate the keycode of the event to a keysym when it is determining the string associated with a keysym. For example, assume the keymap for the 'A' key only contains the shift modifier and the *ConsumeLookupMods* control is enabled. If a user presses the *Shift* key and the *A* key while the *Num_Lock* key is locked, *XLookupString* uses the *Shift* modifier when mapping the keycode for the 'a' key to the keysym for 'A'; subsequently, it only uses the *NumLock* modifier when determining the string associated with the keysym 'A'.

If the *ConsumeLookupMods* control is not enabled, *XLookupString* uses all of the event modifiers to determine the string associated with a keysym. This behavior mirrors the behavior of *XLookupString* in the core implementation.

The *ConsumeLookupMods* control is unset by default. For more information on modifier consumption, refer to Chapter 12.

AlwaysConsumeShiftAndLock

The *AlwaysConsumeShiftAndLock* control, if enabled, forces *XLookupString* to consume the *Shift* and *Lock* modifiers when processing all keys, even if the definition for the key type does not specify these modifiers. The *AlwaysConsumeShiftAndLock* control is unset by default. See section 15.2 for a discussion of key types.

Controls Affecting Compose Processing

The second type of string lookup performed by *XLookupString* involves translating a series of keysyms into a string. Because these lookups can involve more than one key event, they require *XLookupString* to retain some state information between successive calls. The process of mapping a series of keysyms to a string is known as *compose processing* . The controls affecting compose processing are:

ConsumeKeysOnComposeFail
ComposeLED
BeepOnComposeFail

Because different vendors have historically used different algorithms to implement compose processing, and these algorithms may be incompatible with the semantics required by the Xkb compose processing controls, implementation of the compose processing controls is optional in an Xkb implementation.

ConsumeKeysOnComposeFail

Some compose processing algorithms signal the start of a compose sequence by a key event meaning "start compose". [1] The subsequent key events should normally result in a valid composition yielding a valid translation to a string. If the subsequent key events do not have a valid translation, some decision must be made about what to do with the key events that were processed while attempting the compose. The *ConsumeKeysOnComposeFail* control allows a client to specify what happens with the key events *XLookupString* has been considering when it reaches a dead end in a compose sequence.

If the *ConsumeKeysOnComposeFail* control is set, all keys associated with a failed compose sequence should be consumed (discarded). If the *ConsumeKeysOnComposeFail* control is not set, the key events associated with a failed compose sequence should be processed as a normal sequence of key events.

The *ConsumeKeysOnComposeFail* control is disabled by default.

ComposeLED

The *ComposeLED* control allows a client to specify whether or not an indicator should be set and cleared to provide feedback when compose processing is in progress. The control does not specify which indicator should be used; the mapping for this is up to the individual implementation. If the *ComposeLED* control is enabled, it specifies that an indicator should be set when a compose sequence is in progress and cleared when one is not in progress. The *ComposeLED* control is disabled by default.

While the Xkb extension does not specify the type of type of indicator to be used when the *ComposeLED* control is implemented, a consistent convention between implementations is to everyone’s benefit. If a named indicator is used for this purpose, the recommended name is " *Compose* ". Note that some implementations may use an unnamed, custom hardware LED for this purpose.

BeepOnComposeFail

The *BeepOnComposeFail* control allows a client to specify whether or not a bell should be activated to provide feedback when a compose sequence fails. The control does not specify the type of bell that should be used; the mapping for this is up to the individual implementation. If the *BeepOnComposeFail* control is enabled, it specifies that a bell should be activated when a compose sequence fails. The *BeepOnComposeFail* control is disabled by default. If implemented, the bell should be activated using *XkbBell* or *XkbDeviceBell* .

While the Xkb extension does not specify the type of bell to be used when the *BeepOnComposeFail* control is implemented, a consistent convention between implementations is to everyone’s benefit. If a named bell is used for this purpose, the recommended name is " *ComposeFail* ".

[1] Another possibility is to have the compose processing simply be the result of a finite state acceptor; a compose sequence would never fail for a properly written finite state acceptor.

Controls Effecting Event Delivery

IgnoreNewKeyboards

When Xkb is initialized, it implicitly forces requests for *NewKeyboardNotify* events. These events may be used by the Xkb library extension internally; they are normally translated into core protocol *MappingNotify* events before being passed to the client. While delivering the event to the client is appropriate in most cases, it is not appropriate for some clients that maintain per-key data structures. This is because once the server has sent a *NewKeyboardNotify* event, it is free to send the client events for all keys in the new range and that range may be outside of the per-key data structures the client is maintaining.

The *IgnoreNewKeyboards* control, if enabled, prevents Xkb from mapping *NewKeyboardNotify* events to core *MappingNotify* events and passing them to the client. The control is initially disabled.

Manipulating the Library Controls

The Library Controls are manipulated using functions that deal with bitmasks to indicate which controls to manipulate. The controls are identified by the masks defined in Table 11.1.

Table 11.1. Library Control Masks

Library Control Mask	Value
XkbLC_ForceLatin1Lookup	(1 << 0)
XkbLC_ConsumeLookupMods	(1 << 1)
XkbLC_AlwaysConsumeShiftAndLock	(1 << 2)
XkbLC_IgnoreNewKeyboards	(1 << 3)
XkbLC_ConsumeKeysOnComposeFail	(1 << 29)
XkbLC_ComposeLED	(1 << 30)
XkbLC_BeepOnComposeFail	(1 << 31)
XkbLC_AllControls	(0xc0000007)

Determining Which Library Controls are Implemented

To determine which Library Controls are actually implemented, use *XkbXlibControlsImplemented*.

unsigned int *XkbXlibControlsImplemented* (*display*)

Display * *display* ; /* connection to X server */

XkbXlibControlsImplemented returns a bitmask indicating the controls actually implemented in the Xkb library and is composed of an inclusive OR of bits from Table 11.1.

Determining the State of the Library Controls

To determine the current state of the Library Controls, use *XkbGetXlibControls* .

unsigned int *XkbGetXlibControls* (*display*)
Display * *display* ; /* connection to X server */

XkbGetXlibControls returns the current state of the Library Controls as a bit mask that is an inclusive OR of the control masks from Table 11.1 for the controls that are enabled. For the optional compose processing controls, the fact that a control is enabled does not imply that it is actually implemented.

Changing the State of the Library Controls

To change the state of the Library Controls, use *XkbSetXlibControls*.

Bool *XkbSetXlibControls* (*display, bits_to_change, values_for_bits*)
Display * *display* ; /* connection to X server */
unsigned long *bits_to_change* ; /* selects controls to be modified */
unsigned long *values_for_bits* ; /* turns selected controls on (1) or off (0) */

XkbSetXlibControls modifies the state of the controls selected by *bits_to_change* ; only the controls selected by *bits_to_change* are modified. If the bit corresponding to a control is on in *bits_to_change* and also on in values_for_bits, the control is enabled. If the bit corresponding to a control is on in *bits_to_change* but off in *values_for_bits* , the control is disabled. *bits_to_change* should be an inclusive OR of bits from Table 11.1.

Chapter 12. Interpreting Key Events

Xkb provides functions to help developers interpret key events without having to directly interpret Xkb data structures. Xkb also modifies the behavior of several core X library functions.

Effects of Xkb on the Core X Library

When support for Xkb is built into the X library, the *XOpenDisplay* function looks for a compatible version of Xkb on the server. If it finds a compatible version, it initializes the extension and enables *implicit support* for Xkb in a number of X library functions. This makes it possible for clients to take advantage of nearly all Xkb features without having to be rewritten or even recompiled, if they are built with shared libraries. This implicit support is invisible to most clients, but it can have side effects, so the extension includes ways to control or disable it.

Effects of Xkb on Event State

Because *XOpenDisplay* initializes Xkb, some events contain an Xkb description of the keyboard state instead of that normally used by the core protocol. See section 17.1.1 for more information about the differences between Xkb keyboard state and that reported by the core protocol.

Effects of Xkb on MappingNotify Events

When Xkb is missing or disabled, the X library tracks changes to the keyboard mapping using *MappingNotify* events. Whenever the keyboard mapping is changed, the server sends all clients a *MappingNotify* event to report the change. When a client receives a *MappingNotify* event, it is supposed to call *XRefreshKeyboardMapping* to update the keyboard description used internally by the X library.

The X Keyboard Extension uses *XkbMapNotify* and *XkbNewKeyboardNotify* events to track changes to the keyboard mapping. When an Xkb-aware client receives either event, it should call *XkbRefreshKeyboardMapping* to update the keyboard description used internally by the X library. To avoid duplicate events, the X server does not send core protocol *MappingNotify* events to a client that has selected for *XkbMapNotify* events.

The implicit support for Xkb selects for *XkbMapNotify* events. This means that clients that do not explicitly use Xkb but that are using a version of the X library that has implicit support for Xkb do not receive *MappingNotify* events over the wire. Clients that were not written with Xkb in mind do not recognize or properly handle the new Xkb events, so the implicit support converts them to *MappingNotify* events that report approximately the same information, unless the client has explicitly selected for the Xkb version of the event.

An Xkb-capable X server does not send events from keys that fall outside the legal range of keycodes expected by that client. Once the server sends a client an *XkbNewKeyboardNotify* event, it reports events from all keys because it assumes that any client that has receieved an *XkbNewKeyboardNotify* event expects key events from the new range of keycodes. The implicit support for Xkb asks for *XkbNewKeyboardNotify* events, so the range of keycodes reported to the client might vary without the client’s knowledge. Most clients don’t really care about the range

of legal keycodes, but some clients maintain information about each key and might have problems with events that come from unexpected keys. Such clients can set the *XkbLC_IgnoreNewKeyboards* library control (see section 11.3.1) to prevent the implicit support from requesting notification of changes to the legal range of keycodes.

X Library Functions Affected by Xkb

The following X library functions are modified by Xkb:

XKeycodeToKeysym
XKeysymToKeycode
XLookupKeysym
XLookupString
XRefreshKeyboardMapping
XRebindKeysym

The implicit support for Xkb replaces a number of X library functions with versions that understand and use the X Keyboard Extension. In most cases, the semantics of the new versions are identical to those of the old, but there are occasional visible differences. This section lists all of the functions that are affected and the differences in behavior, if any, that are visible to clients.

The *XKeycodeToKeysym* function reports the keysym associated with a particular index for a single key. The index specifies a column of symbols in the core keyboard mapping (that is, as reported by the core protocol *GetKeyboardMapping* request). The order of the symbols in the core mapping does not necessarily correspond to the order of the symbols used by Xkb; section 17.1.3 describes the differences.

The *XKeysymToKeycode* function reports a keycode to which a particular keysym is bound. When Xkb is missing or disabled, this function looks in each column of the core keyboard mapping in turn and returns the lowest numbered key that matches in the lowest numbered group. When Xkb is present, this function uses the Xkb ordering for symbols instead.

The *XLookupKeysym* function reports the symbol in a specific column of the key associated with an event. Whether or not Xkb is present, the column specifies an index into the core symbol mapping.

The *XLookupString* function reports the symbol and string associated with a key event, taking into account the keycode and keyboard state as reported in the event. When Xkb is disabled or missing, *XLookupString* uses the rules specified by the core protocol and reports only ISO Latin-1 characters. When Xkb is present, *XLookupString* uses the explicit keyboard group, key types, and rules specified by Xkb. When Xkb is present, *XLookupString* is allowed, but not required, to return strings in character sets other than ISO Latin-1, depending on the current locale. If any key bindings are defined, *XLookupString* does not use any consumed modifiers (see sections 11.1.2 and 15.2) to determine matching bindings.

The *XRefreshKeyboardMapping* function updates the X library's internal representation of the keyboard to reflect changes reported via *MappingNotify* events. When Xkb is missing or disabled, this function reloads the entire modifier map or keyboard mapping. When Xkb is present, the implicit Xkb support keeps track of the changed components reported by each *XkbMapNotify* event and updates only those pieces

of the keyboard description that have changed. If the implicit support has not noted any keyboard mapping changes, *XRefreshKeyboardMapping* updates the entire keyboard description.

The *XRebindKeysym* function associates a string with a keysym and a set of modifiers. Xkb does not directly change this function, but it does affect the way that the state reported in the event is compared to the state specified to *XRebindKeysym* . When Xkb is missing or disabled, *XLookupString* returns the specified string if the modifiers in the event exactly match the modifiers from this call. When Xkb is present, any modifiers used to determine the keysym are consumed and are not used to look up the string.

Xkb Event and Keymap Functions

To find the keysym bound to a particular key at a specified group and shift level, use *XkbKeycodeToKeysym*.

KeySym *XkbKeycodeToKeysym* (*dpy, kc, group, level*)
Display * dpy; /* connection to X server */
KeyCode kc; /* key of interest */
unsigned int group; /* group of interest */
unsigned int level; /* shift level of interest */

XkbKeycodeToKeysym returns the keysym bound to a particular group and shift level for a particular key on the core keyboard. If *kc* is not a legal keycode for the core keyboard, or if *group* or *level* are out of range for the specified key, *XkbKeycodeToKeysym* returns *NoSymbol* .

To find the set of modifiers bound to a particular keysym on the core keyboard, use *XkbKeysymToModifiers* .

unsigned int *XkbKeysymToModifiers* (*dpy* , *ks*)
Display * *dpy* ; /* connection to X server */
KeySym *ks* ; /* keysym of interest */

XkbKeysymToModifiers finds the set of modifiers currently bound to the keysym *ks* on the core keyboard. The value returned is the mask of modifiers bound to the keysym *ks* . If no modifiers are bound to the keysym, *XkbKeysymToModifiers* returns zero; otherwise, it returns the inclusive OR of zero or more of the following: *ShiftMask* , *ControlMask* , *LockMask* , *Mod1Mask* , *Mod2Mask* , *Mod3Mask* , *Mod4Mask,* and *Mod5Mask* .

Use *XkbLookupKeySym* to find the symbol associated with a key for a particular state.

Bool *XkbLookupKeySym* (*dpy* , *key* , *state* , *mods_rtrn* , *sym_rtrn*)
Display * *dpy* ; /* connection to X server */
KeyCode *key* ; /* key for which symbols are to be found */
unsigned int *state* ; /* state for which symbol should be found */
unsigned int * *mods_rtrn* ; /* backfilled with unconsumed modifiers */
KeySym * *sym_rtrn* ; /* backfilled with symbol associated with key + state */

XkbLookupKeySym is the equivalent of the core *XLookupKeySym* function. For the core keyboard, given a keycode *key* and an Xkb state *state* , *XkbLookupKeySym* returns the symbol associated with the key in *sym_rtrn* and the list of modifiers that should still be applied in *mods_rtrn* . The *state* parameter is the state from a *KeyPress* or *KeyRelease* event. *XkbLookupKeySym* returns *True* if it succeeds.

Use *XkbLookupKeyBinding* to find the string bound to a key by *XRebindKeySym* . *XkbLookupKeyBinding* is the equivalent of the core *XLookupString* function.

int *XkbLookupKeyBinding* (*dpy* , *sym* , *state* , *buf* , *nbytes* , *extra_rtrn*)
Display * *dpy* ; /* connection to server */
KeySym *sym* ; /* symbol to be looked up */
unsigned int *state* ; /* state for which string is to be looked up */
char * *buf* ; /* buffer into which returned string is written */
int *nbytes* ; /* size of buffer in bytes */
int * *extra_rtrn* ; /* backfilled with number bytes overflow */

XRebindKeysym binds an ASCII string to a specified keysym, so that the string and keysym are returned when the key is pressed and a specified list of modifiers are also being held down. *XkbLookupKeyBinding* returns in *buf* the string associated with the keysym *sym* and modifier state *state* . *buf* is *NULL* terminated unless there's an overflow. If the string returned is larger than *nbytes* , a count of bytes that does not fit into the buffer is returned in extra_rtrn. *XkbTranslateKeySym* returns the number of bytes that it placed into *buf* .

To find the string and symbol associated with a keysym for a given keyboard state, use *XkbTranslateKeySym* .

int *XkbTranslateKeySym* (*dpy* , *sym_inout* , *mods* , *buf* , *nbytes* , *extra_rtrn*)
Display * *dpy* ; /* connection to X server */
KeySym * *sym_inout* ; /* symbol to be translated; result of translation */
unsigned int *mods* ; /* modifiers to apply to *sym_inout* */
char * *buf* ; /* buffer into which returned string is written */
int *nbytes* ; /* size of buffer in bytes */
int * *extra_rtrn* ; /* number of bytes overflow*/

XkbTranslateKeySym applies the transformations specified in *mods* to the symbol specified by *sym_inout* . It returns in *buf* the string, if any, associated with the keysym for the current locale. If the transformations in *mods* changes the keysym, *sym_inout* is updated accordingly. If the string returned is larger than *nbytes* , a count of bytes that does not fit into the buffer is returned in extra_rtrn. *XkbTranslateKeySym* returns the number of bytes it placed into *buf* .

To update the keyboard description that is internal to the X library, use *XkbRefreshKeyboardMapping* .

Status *XkbRefreshKeyboardMapping* (*event)*
XkbMapNotifyEvent * *event* ; /* event initiating remapping */

XkbRefreshKeyboardMapping is the Xkb equivalent of the core *XRefreshKeyboardMapping* function. It requests that the X server send the current key mapping

information to this client. A client usually invokes *XkbRefreshKeyboardMapping* after receiving an *XkbMapNotify* event. *XkbRefreshKeyboardMapping* returns *Success* if it succeeds and *BadMatch* if the event is not an Xkb event.

The *XkbMapNotify* event can be generated when some client calls *XkbSetMap* , *XkbChangeMap* , *XkbGetKeyboardByName* , or any of the standard X library functions that change the keyboard mapping or modifier mapping.

To translate a keycode to a key symbol and modifiers, use *XkbTranslateKeyCode* .

```
Booll XkbTranslateKeyCode ( xkb, key, mods, mods_rtrn, keysym_rtrn)
XkbDescPtr xkb ; /* keyboard description to use for translation */
KeyCode key ; /* keycode to translate */
unsigned int mods ; /* modifiers to apply when translating key */
unsigned int * mods_rtrn ; /* backfilled with unconsumed modifiers */
KeySym * keysym_rtrn ; /* keysym resulting from translation */
```

mods_rtrn is backfilled with the modifiers consumed by the translation process. *mods* is a bitwise inclusive OR of the legal modifier masks: *ShiftMask* , *LockMask* , *ControlMask* , *Mod1Mask* , *Mod2Mask* , *Mod3Mask* , *Mod4Mask* , *Mod5Mask* .The *AlwaysConsumeShiftAndLock* library control (see section 11.1.3), if enabled, causes *XkbTranslateKeyCode* to consume shift and lock. *XkbTranslateKeyCode* returns *True* if the translation resulted in a keysym, and *False* if it resulted in *NoSymbol* .

Chapter 13. Keyboard Geometry

The Xkb description of a keyboard includes an optional keyboard geometry that describes the physical appearance of the keyboard. Keyboard geometry describes the shape, location, and color of all keyboard keys or other visible keyboard components such as indicators. The information contained in a keyboard geometry is sufficient to allow a client program to draw an accurate two-dimensional image of the keyboard.

You can retrieve a keyboard geometry from an X server that supports Xkb, or you can allocate it from scratch and initialize it in a client program. The keyboard geometry need not have any correspondence with the physical keyboard that is connected to the X server.

Geometry measurements are specified in mm/10 units. The origin (0,0) is in the top left corner of the keyboard image. A component's own origin is also its upper left corner. In some cases a component needs to be drawn rotated. For example, a special keyboard may have a section of keys arranged in rows in a rectangular area, but the entire rectangle may not be in alignment with the rest of the keyboard, and instead, it is rotated from horizontal by 30 *o* . Rotation for a geometry object is specified in 1/10 o increments about its origin. An example of a keyboard with rotated sections is shown in Figure 13.1.



Rotated Keyboard Sections

Some geometry components include a *priority* , which indicates the order in which overlapping objects should be drawn. Objects should be drawn in order from highest priority (0) to lowest (255).

The keyboard geometry's top-level description is stored in a *XkbGeometryRec* structure. This structure contains three types of information:

1. Lists of items, not used to draw the basic keyboard, but indexed by the geometry descriptions that comprise the entire keyboard geometry (colors, geometry properties, key aliases, shapes)

2. A number of singleton items that describe the keyboard as a whole (keyboard name, width and height, a color for the keyboard as a whole, and a color for keyboard key labels)

3. A list of the keyboard's sections and nonkey doodads

The top-level geometry is described in more detail in the following.

The lists of items used by components of the keyboard geometry description is as follows:

- The top-level keyboard geometry description includes a list of up to *MaxColors* (32) *color names* . A color name is a string whose interpretation is not specified by Xkb. The *XkbColorRec* structure provides a field for this name as well as a pixel field. The pixel field is a convenient place for an application to store a pixel value or color definition, if it needs to. All other geometry data structures refer to colors using their indices in this global list.

- The top-level keyboard geometry description includes a list of *geometry properties* . A geometry property associates an arbitrary string with an equally arbitrary name. Geometry properties can be used to provide hints to programs that display images of keyboards, but they are not interpreted by Xkb. No other geometry structures refer to geometry properties. As an example of a possible use of *properties* , consider the pause/break key on most PC keyboards: the "break" symbol is usually on the front of the key and is often a different color. A program might set a property to:

  LBL_PAUS = "{Pause/top/black,Break/front/red}"

  and use the property information to draw the key with a front label as well as a top label.

- The top-level keyboard geometry description includes a list of *key aliases* (see Chapter 18). Key aliases allow the keyboard layout designer to assign multiple key names to a single key.

  ## Note

  Key aliases defined in the geometry component of a keyboard mapping override those defined in the keycodes component of the server database, which are stored in the *XkbNamesRec* (*xkb->names*). Therefore, consider the key aliases defined by the geometry before considering key aliases supplied by the keycodes.

- The top-level keyboard geometry description includes a list of *shapes* ; other keyboard components refer to shapes by their index in this list. A shape consists of an arbitrary name of type Atom and one or more closed-polygon *outlines* . All points in an outline are specified relative to the origin of its enclosing shape, that is, whichever shape that contains this outline in its list of outlines. One outline is the primary outline. The primary outline is by default the first outline, or it can be optionally specified by the *primary* field in the *XkbShapeRec* structure. A keyboard display application can generate a simpler but still accurate keyboard image by displaying only the primary outlines for each shape. Nonrectangular keys must include a rectangular *approximation* as one of the outlines associated with the shape. The approximation is not normally displayed but can be used by very sim-

ple keyboard display applications to generate a recognizable but degraded image of the keyboard.

The *XkbGeometryRec* top-level geometry description contains the following information that pertains to the keyboard as a whole:

- A *keyboard symbolic name* of type Atom to help users identify the keyboard.
- The *width* and *height* of the keyboard, in mm/10. For nonrectangular keyboards, the width and height describe the smallest bounding box that encloses the outline of the keyboard.
- The *base color* of the keyboard is the predominant color on the keyboard and is used as the default color for any components whose color is not explicitly specified.
- The *label color* is the color used to draw the labels on most of the keyboard keys.
- The *label font* is a string that describes the font used to draw labels on most keys; label fonts are arbitrary strings, because Xkb does not specify the format or name space for font names.

The keyboard is subdivided into named *sections* of related keys and doodads. The sections and doodads on the keyboard are listed in the *XkbGeometryRec* top-level keyboard geometry description. A section is composed of keys that are physically together and logically related. Figure 13.2 shows a keyboard that is divided into four sections. A *doodad* describes some visible aspect of the keyboard that is not a key and is not a section.



Keyboard with Four Sections

Shapes and Outlines

A *shape* , used to draw keyboard components and stored in a *XkbShapeRec* structure, has:

- An arbitrary name of type Atom.
- Bounds (two x and y coordinates) that describe the corners of a rectangle containing the shape's top surface outline.
- A list of one or more outlines (described below).
- Optional pointers to a primary and an approximation outline (described below). If either of these pointers is *NULL* , the default primary/approximation outline is the first one in the list of outlines for the shape.

An *outline* , stored in a *XkbOutlineRec* structure, is a list of one or more points that describes a single closed-polygon, as follows:

- A list with a single point describes a rectangle with one corner at the origin of the shape (0,0) and the opposite corner at the specified point.
- A list of two points describes a rectangle with one corner at the position specified by the first point and the opposite corner at the position specified by the second point.
- A list of three or more points describes an arbitrary polygon. If necessary, the polygon is automatically closed by connecting the last point in the list with the first.
- A nonzero value for the *corner_radius* field specifies that the corners of the polygon should be drawn as circles with the specified radius.

All points in an outline are specified relative to the origin of the enclosing shape. Points in an outline may have negative values for the X and Y coordinate.

One outline is the primary outline; a keyboard display application can generate a simple but still accurate keyboard image by displaying only the primary outlines for each shape. The default primary outline is the first in a shape's list of outlines. If the *primary* field of the *XkbShapeRec* structure is not *NULL* , it points to the primary outline. A rectangular *approximation* must be included for nonrectangular keys as one of the outlines associated with the shape; the approximation is not normally displayed but can be used by very simple keyboard display applications to generate a recognizable but degraded image of the keyboard.

Sections

As previously noted, a keyboard is subdivided into *sections* of related keys. Each section has its own coordinate system — if a section is rotated, the coordinates of any components within the section are interpreted relative to the edges that were on the top and left before rotation. The components that make up a section, stored in a *XkbSectionRec* , include:

- An arbitrary name of type Atom.
- A priority, to indicate drawing order. 0 is the highest priority, 255 the lowest.

- Origin of the section, relative to the origin of the keyboard.
- The width and height and the angle of rotation.
- A list of *rows* . A row is a list of horizontally or vertically adjacent keys. Horizontal rows parallel the (prerotation) top of the section, and vertical rows parallel the (prerotation) left of the section. All keys in a horizontal row share a common top coordinate; all keys in a vertical row share a left coordinate. Figure 13.3 shows the alpha section from the keyboard shown in Figure 13.2, divided into rows. Rows and keys are defined below.



Rows in a Section

- An optional list of *doodads* ; any type of doodad can be enclosed within a section. Position and angle of rotation are relative to the origin and angle of rotation of the sections that contain them. Priority for doodads in a section is relative to the other components of the section, not to the keyboard as a whole.
- An optional *overlay* with a name of type Atom and a list of overlay rows (described below).
- Bounds (two x and y coordinates) that describe the corners of a rectangle containing the entire section.

Rows and Keys

A row description (*XkbRowRec*) consists of the coordinates of its origin relative to its enclosing section, a flag indicating whether the row is horizontal or vertical, and a list of keys in the row.

A key description (*XkbKeyRec*) consists of a key name, a shape, a key color, and a gap. The key name should correspond to one of the keys named in the keyboard names description, the shape specifies the appearance of the key, and the key color specifies the color of the key (not the label on the key; the label color is stored in the *XkbGeometryRec*). Keys are normally drawn immediately adjacent to one another from left to right (or top to bottom) within a row. The gap field specifies the distance between a key and its predecessor.

Doodads

Doodads can be global to the keyboard or part of a section. Doodads have symbolic names of arbitrary length. The only doodad name whose interpretation is specified by Xkb is "Edges", which, if present, describes the outline of the entire keyboard.

Each doodad's origin is stored in fields named *left* and *top* , which are the coordinates of the doodad's origin relative to its enclosing object, whether it be a section or the top-level keyboard. The priority for doodads that are listed in the top-level geometry is relative to the other doodads listed in the top-level geometry and the sections listed in the top-level geometry. The priority for doodads listed in a section are relative to the other components of the section. Each doodad is stored in a structure with a *type* field, which specifies the type of doodad.

Xkb supports five types of doodads:

- An *indicator doodad* describes one of the physical keyboard indicators. Indicator doodads specify the shape of the indicator, the indicator color when it is lit (*on_color*) and the indicator color when it is dark (*off_color*).
- An *outline doodad* describes some aspect of the keyboard to be drawn as one or more hollow, closed polygons. Outline doodads specify the shape, color, and angle of rotation about the doodad origin at which they should be drawn.
- A *solid doodad* describes some aspect of the keyboard to be drawn as one or more filled polygons. Solid doodads specify the shape, color, and angle of rotation about the doodad origin at which they should be drawn.
- A *text doodad* describes a text label somewhere on the keyboard. Text doodads specify the label string, the font and color to use when drawing the label, and the angle of rotation of the doodad about its origin.
- A *logo doodad* is a catch-all, which describes some other visible element of the keyboard. A logo doodad is essentially an outline doodad with an additional symbolic name that describes the element to be drawn. If a keyboard display program recognizes the symbolic name, it can draw something appropriate within the bounding region of the shape specified in the doodad. If the symbolic name does not describe a recognizable image, it should draw an outline using the specified shape, outline, and angle of rotation. The Xkb extension does not specify the interpretation of logo names.

The structures these doodads are stored in and the values of the *type* fields are shown in Table 13.1.

Table 13.1. Doodad Types

Doodad	Structure	Type
indicator doodad	*XkbIndicatorDoodadRec*	*XkbIndicatorDoodad*
outline doodad	*XkbShapeDoodadRec*	*XkbOutlineDoodad*
solid doodad	*XkbShapeDoodadRec*	*XkbSolidDoodad*
text doodad	*XkbTextDoodadRec*	*XkbTextDoodad*
logo doodad	*XkbLogoDoodadRec*	*XkbLogoDoodad*

Overlay Rows and Overlay Keys

An *overlay row* (*XkbOverlayRowRec*) contains a pointer to the row it overlays and a list of *overlay keys* .

Each overlay key definition (*XkbOverlayKeyRec*) indicates a key that can yield multiple keycodes and consists of a field named *under* , which specifies the primary name of the key and a field named *over* , which specifies the name for the key when the overlay keycode is selected. The key specified in *under* must be a member of the section that contains the overlay key definition, while the key specified in over must not be.

Drawing a Keyboard Representation

To draw a representation of the keyboard, draw in the following order:

```
Draw the top-level keyboard as a rectangle, using its width and height.
For each component (section or doodad) of the top-level geometry, in priority
   If component is a section
      For each row, in the order it appears in the section
         Draw keys in the order they appear in the row
      Draw doodads within the section in priority order.
   Else draw doodad
```

Geometry Data Structures

In the following figures, a solid arrow denotes a pointer to an array of structures or a singleton structure. A dotted arrow denotes an index or a pointer into the array.



Xkb Geometry Data Structures


. . .
label_color
base_color
. . .
properties
colors
shapes
sections
doodads
key_aliases
XkbGeometryRec
XkbGeometryRec, XkbColorRec, and XkbShapeRec repeated from Figure 16.4
. . .
color_ndx
shape_ndx
XkbShapeDoodadRec(s)
XkbColorRec(s) (array)
. . .
color_ndx
XkbTextDoodadRec(s)
doodads array may contain any of these doodad types
. . .
shape_ndx
on_color_ndx
off_color_ndx
XkbIndicatorDoodadRec(s)
. . .
outlines
approx
primary
bounds
XkbShapeRec(s) (array)
. . .
color_ndx
shape_ndx
XkbLogoDoodadRec(s)

Xkb Geometry Data Structures (Doodads)



Xkb Geometry Data Structures (Overlays)

```
typedef struct _XkbGeometry {              /* top-level keyboard geometry structur
      Atom                name;            /* keyboard name */
      unsigned short      width_mm;        /* keyboard width in  mm / 10 */
      unsigned short      height_mm;       /* keyboard height in  mm / 10 */
```

```
      char *             label_font;      /* font for key labels */
      XkbColorPtr        label_color;     /* color for key labels - pointer into
      XkbColorPtr        base_color;      /* color for basic keyboard - pointer i
      unsigned short     sz_properties;   /* size of properties array */
      unsigned short     sz_colors;       /* size of colors array */
      unsigned short     sz_shapes;       /* size of shapes array */
      unsigned short     sz_sections;     /* size of sections array */
      unsigned short     sz_doodads;      /* size of doodads array */
      unsigned short     sz_key_aliases;  /* size of key aliases array */
      unsigned short     num_properties;  /* number of properties in the properti
      unsigned short     num_colors;      /* number of colors in the colors array
      unsigned short     num_shapes;      /* number of shapes in the shapes array
      unsigned short     num_sections;    /* number of sections in the sections a
      unsigned short     num_doodads;     /* number of doodads in the doodads arr
      unsigned short     num_key_aliases; /* number of key aliases in the key */
      XkbPropertyPtr     properties;      /* properties array */
      XkbColorPtr        colors;          /* colors array */
      XkbShapePtr        shapes;          /* shapes array */
      XkbSectionPtr      sections;        /* sections array */
      XkbDoodadPtr       doodads;         /* doodads array */
      XkbKeyAliasPtr     key_aliases;     /* key aliases array */
} XkbGeometryRec*XkbGeometryPtr;
```

The *doodads* array is only for doodads not contained in any of the *sections* that has its own *doodads* . The key aliases contained in the *key_aliases* array take precedence over any defined in the keycodes component of the keyboard description.

```
typedef struct _XkbProperty {
      char *      name;            /* property name */
      char *      value;           /* property value */
} XkbPropertyRec,*XkbPropertyPtr;


typedef struct _XkbColor {
      unsigned int      pixel;     /* color */
      char *            spec;      /* color name */
} XkbColorRec,*XkbColorPtr;


typedef struct _XkbKeyAliasRec {
      char      real[XkbKeyNameLength];   /* real name of the key */
      char      alias[XkbKeyNameLength];  /* alias for the key */
} XkbKeyAliasRec,*XkbKeyAliasPtr;


typedef struct _XkbPoint {                /* x,y coordinates */
      short      x;
      short      y;
} XkbPointRec, *XkbPointPtr;


typedef struct _XkbOutline {
      unsigned short      num_points;     /* number of points in the outline */
      unsigned short      sz_points;      /* size of the points array */
```

```
      unsigned short      corner_radius;  /* draw corners as circles with this rad
      XkbPointPtr         points;         /* array of points defining the outline
} XkbOutlineRec, *XkbOutlinePtr;


typedef struct _XkbBounds {
      short      x1,y1;            /* upper left corner of the bounds,
                                      in mm/10 */
       short      x2,y2;           /* lower right corner of the bounds, in
                                      mm/10 */
} XkbBoundsRec, *XkbBoundsPtr;


typedef struct _XkbShape {
      Atom              name;           /* shape's name */
      unsigned short    num_outlines;   /* number of outlines for the shape */
      unsigned short    sz_outlines;    /* size of the outlines array */
      XkbOutlinePtr     outlines;       /* array of outlines for the shape */
      XkbOutlinePtr     approx;         /* pointer into the array to the approxima
      XkbOutlinePtr     primary;        /* pointer into the array to the primary o
      XkbBoundsRec      bounds;         /* bounding box for the shape; encompasses
} XkbShapeRec, *XkbShapePtr;
```

If *approx* and/or *primary* is *NULL* , the default value is used. The default primary outline is the first element in the outlines array, as is the default approximating outline.

```
typedef struct _XkbKey {         /* key in a row */
      XkbKeyNameRec    name;     /* key name */
      short            gap;      /* gap in mm/10 from previous key in row */
      unsigned char    shape_ndx;      /* index of shape for key */
      unsigned char    color_ndx;      /* index of color for key body */
} XkbKeyRec, *XkbKeyPtr;


typedef struct _XkbRow {             /* row in a section */
      short               top;       /* top coordinate of row origin, relative to
      short               left;      /* left coordinate of row origin, relative to
      unsigned short      num_keys;  /* number of keys in the keys array */
      unsigned short      sz_keys;   /* size of the keys array */
      int                 vertical;  /* True =>vertical row,
                                        False =>horizontal row */
      XkbKeyPtr           keys;      /* array of keys in the row*/
      XkbBoundsRec        bounds;    /* bounding box for the row */
} XkbRowRec, *XkbRowPtr;
```

top and *left* are in *mm* / *10* .

```
typedef struct _XkbOverlayRec {
      Atom              name;           /* overlay name */
      XkbSectionPtr     section_under;  /* the section under this overlay */
      unsigned short    num_rows;       /* number of rows in the rows array */
      unsigned short    sz_rows;        /* size of the rows array */
      XkbOverlayRowPtr  rows;           /* array of rows in the overlay */
```

```
      XkbBoundsPtr      bounds;         /* bounding box for the overlay */
} XkbOverlayRec,*XkbOverlayPtr;


typedef struct _XkbOverlayRow {
      unsigned short      row_under;     /* index into the row under this overlay
      unsigned short      num_keys;      /* number of keys in the keys array */
      unsigned short      sz_keys;       /* size of the keys array */
      XkbOverlayKeyPtr    keys;          /* array of keys in the overlay row */
} XkbOverlayRowRec,*XkbOverlayRowPtr;
```

row_under is an index into the array of *rows* in the section under this overlay. The section under this overlay row is the one pointed to by *section_under* in this overlay row's *XkbOverlayRec* .

```
typedef struct _XkbOverlayKey {
      XkbKeyNameRec      over;      /* name of this overlay key */
      XkbKeyNameRec      under;     /* name of the key under this overlay key */
} XkbOverlayKeyRec,*XkbOverlayKeyPtr;


typedef struct _XkbSection {
      Atom            name;          /* section name */
      unsigned char   priority;      /* drawing priority, 0=>highest, 255=>lowest
      short           top;           /* top coordinate of section origin */
      short           left;          /* left coordinate of row origin */
      unsigned short  width;         /* section width, in mm/10 */
      unsigned short  height;        /* section height, in mm/10 */
      short           angle;         /* angle of section rotation, counterclockwis
      unsigned short  num_rows;      /* number of rows in the rows array */
      unsigned short  num_doodads;   /* number of doodads in the doodads array */
      unsigned short  num_overlays;  /* number of overlays in the overlays array *
      unsigned short  sz_rows;       /* size of the rows array */
      unsigned short  sz_doodads;    /* size of the doodads array */
      unsigned short  sz_overlays;   /* size of the overlays array */
      XkbRowPtr       rows;          /* section rows array */
      XkbDoodadPtr    doodads;       /* section doodads array */
      XkbBoundsRec    bounds;        /* bounding box for the section, before rotat
      XkbOverlayPtr   overlays;      /* section overlays array */
} XkbSectionRec, *XkbSectionPtr;
```

top and *left* are the origin of the section, relative to the origin of the keyboard, in *mm* / *10* . *angle* is in *1* / *10* degrees.

DoodadRec Structures

The doodad arrays in the *XkbGeometryRec* and the *XkbSectionRec* may contain any of the doodad structures and types shown in Table 13.1.

The doodad structures form a union:

```
typedef union _XkbDoodad {
        XkbAnyDoodadRec        any;
        XkbShapeDoodadRec      shape;
```

```
        XkbTextDoodadRec       text;
        XkbIndicatorDoodadRec  indicator;
        XkbLogoDoodadRec       logo;
} XkbDoodadRec, *XkbDoodadPtr;
```

The *top* and *left* coordinates of each doodad are the coordinates of the origin of the doodad relative to the keyboard's origin if the doodad is in the *XkbGeometryRec* doodad array, and with respect to the section's origin if the doodad is in a *XkbSectionRec* doodad array. The *color_ndx* or *on_color_ndx* and *off_color_ndx* fields are color indices into the *XkbGeometryRec* 's color array and are the colors to draw the doodads with. Similarly, the *shape_ndx* fields are indices into the *XkbGeometryRec* 's shape array.

```
typedef struct _XkbShapeDoodad {
      Atom       name;                /* doodad name */
      unsigned char      type;        /* XkbOutlineDoodad
                                         or XkbSolidDoodad */
      unsigned char      priority;    /* drawing priority,
                                         0=>highest, 255=>lowest */
      short      top;                 /* top coordinate, in mm/10 */
      short      left;                /* left coordinate, in mm/10 */
      short      angle;               /* angle of rotation, clockwise, in 1/10 deg
      unsigned short      color_ndx;  /* doodad color */
      unsigned short      shape_ndx;  /* doodad shape */
} XkbShapeDoodadRec, *XkbShapeDoodadPtr;


typedef struct _XkbTextDoodad {
      Atom            name;          /* doodad name */
      unsigned char   type;          /*  XkbTextDoodad */
      unsigned char   priority;      /* drawing priority,
                                        0=>highest, 255=>lowest */
      short           top;           /* top coordinate, in mm/10 */
      short           left;          /* left coordinate, in mm/10 */
      short           angle;         /* angle of rotation, clockwise, in 1/10 degre
      short           width;         /* width in mm/10 */
      short           height;        /* height in mm/10 */
      unsigned short  color_ndx;     /* doodad color */
      char *           text;         /* doodad text */
      char *           font;         /* arbitrary font name for doodad text */
} XkbTextDoodadRec, *XkbTextDoodadPtr;


typedef struct _XkbIndicatorDoodad {
      Atom           name;           /* doodad name */
      unsigned char  type;           /* XkbIndicatorDoodad */
      unsigned char  priority;       /* drawing priority, 0=>highest, 255=>lowest *
      short          top;            /* top coordinate, in mm/10 */
      short          left;           /* left coordinate, in mm/10 */
      short          angle;          /* angle of rotation, clockwise, in 1/10 degre
      unsigned short shape_ndx;      /* doodad shape */
      unsigned short on_color_ndx;   /* color for doodad if indicator is on */
      unsigned short off_color_ndx; /* color for doodad if indicator is off */
} XkbIndicatorDoodadRec, *XkbIndicatorDoodadPtr;
```

```
typedef struct _XkbLogoDoodad {
      Atom               name;        /* doodad name */
      unsigned char      type;        /*  XkbLogoDoodad */
      unsigned char      priority;    /* drawing priority, 0=>highest, 255=>lowest
      short              top;         /* top coordinate, in mm/10 */
      short              left;        /* left coordinate, in mm/10 */
      short              angle;       /* angle of rotation, clockwise, in 1/10 deg
      unsigned short      color_ndx;  /* doodad color */
      unsigned short      shape_ndx;  /* doodad shape */
      char *      logo_name;          /* text for logo */
} XkbLogoDoodadRec, *XkbLogoDoodadPtr
```

Getting Keyboard Geometry From the Server

You can load a keyboard geometry as part of the keyboard description returned by *XkbGetKeyboard* . However, if a keyboard description has been previously loaded, you can instead obtain the geometry by calling the *XkbGetGeometry* . In this case, the geometry returned is the one associated with the keyboard whose device ID is contained in the keyboard description.

To load a keyboard geometry if you already have the keyboard description, use *XkbGetGeometry*.

Status *XkbGetGeometry* (*dpy* , *xkb*)

Display * *dpy* ; /* connection to the X server */

XkbDescPtr *xkb* ; /* keyboard description that contains the ID for the keyboard and into which the geometry should be loaded */

XkbGetGeometry can return *BadValue* , *BadImplementation* , *BadName* , *BadAlloc,* or *BadLength* errors or *Success* if it succeeds.

It is also possible to load a keyboard geometry by name. The X server maintains a database of keyboard components (see Chapter 20). To load a keyboard geometry description from this database by name, use *XkbGetNamedGeometry*.

Status *XkbGetNamedGeometry* (*dpy* , *xkb* , *name*)

Display * *dpy* ; /* connection to the X server */

XkbDescPtr *xkb* ; /* keyboard description into which the geometry should be loaded */

Atom *name* ; /* name of the geometry to be loaded */

XkbGetNamedGeometry can return *BadName* if the *name* cannot be found.

Using Keyboard Geometry

Xkb provides a number of convenience functions to help use a keyboard geometry. These include functions to return the bounding box of a shape’s top surface and to update the bounding box of a shape row or section.

A shape is made up of a number of outlines. Each outline is a polygon made up of a number of points. The bounding box of a shape is a rectangle that contains all the outlines of that shape.



Key Surface, Shape Outlines, and Bounding Box

To determine the bounding box of the top surface of a shape, use *XkbComputeShapeTop*.

Bool *XkbComputeShapeTop* (*shape* , *bounds_rtrn*)
XkbShapePtr *shape* ; /* shape to be examined */
XkbBoundsPtr *bounds_rtrn* /* backfilled with the bounding box for the shape */

XkbComputeShapeTop returns a *BoundsRec* that contains two x and y coordinates. These coordinates describe the corners of a rectangle that contains the outline that describes the top surface of the shape. The top surface is defined to be the approximating outline if the *approx* field of *shape* is not *NULL* . If *approx* is *NULL* , the top surface is defined as the last outline in the *shape* 's array of outlines. *XkbComputeShapeTop* returns *False* if *shape* is *NULL* or if there are no outlines for the shape; otherwise, it returns *True*.

A *ShapeRec* contains a *BoundsRec* that describes the bounds of the shape. If you add or delete an outline to or from a shape, the bounding box must be updated. To update the bounding box of a shape, use *XkbComputeShapeBounds*.

Bool *XkbComputeShapeBounds* (*shape*)
XkbShapePtr *shape* ; /* shape to be examined */

XkbComputeShapeBounds updates the *BoundsRec* contained in the *shape* by examining all the outlines of the shape and setting the *BoundsRec* to the minimum x and minimum y, and maximum x and maximum y values found in those outlines. *XkbComputeShapeBounds* returns *False* if *shape* is *NULL* or if there are no outlines for the shape; otherwise, it returns *True* .

If you add or delete a key to or from a row, or if you update the shape of one of the keys in that row, you may need to update the bounding box of that row. To update the bounding box of a row, use *XkbComputeRowBounds*.

Bool *XkbComputeRowBounds* (*geom* , *section* , *row*)
XkbGeometryPtr *geom* ; /* geometry that contains the *section* */
XkbSectionPtr *section* ; /* section that contains the row */
XkbRowPtr *row* ; /* row to be examined and updated */

XkbComputeRowBounds checks the bounds of all keys in the *row* and updates the bounding box of the row if necessary. *XkbComputeRowBounds* returns *False* if any of the arguments is *NULL* ; otherwise, it returns *True* .

If you add or delete a row to or from a section, or if you change the geometry of any of the rows in that section, you may need to update the bounding box for that section. To update the bounding box of a section, use *XkbComputeSectionBounds*.

Bool *XkbComputeSectionBounds* (*geom* , *section*)
XkbGeometryPtr *geom* ; /* geometry that contains the *section* */
XkbSectionPtr *section* ; /* section to be examined and updated */

XkbComputeSectionBounds examines all the rows of the *section* and updates the bounding box of that section so that it contains all rows. *XkbComputeSectionBounds* returns *False* if any of the arguments is *NULL* ; otherwise, it returns *True* .

Keys that can generate multiple keycodes may be associated with multiple names. Such keys have a primary name and an alternate name. To find the alternate name by using the primary name for a key that is part of an overlay, use *XkbFindOverlayForKey*.

char * *XkbFindOverlayForKey* (*geom* , *section* , *under*)
XkbGeometryPtr *geom* ; /* geometry that contains the *section* */
XkbSectionPtr *section* ; /* section to be searched for matching keys */
char * *under* . /* primary name of the key to be considered */

XkbFindOverlayForKey uses the primary name of the key, *under* , to look up the alternate name, which it returns.

Adding Elements to a Keyboard Geometry

Xkb provides functions to add a single new element to the top-level keyboard geometry. In each case the *num_* * fields of the corresponding structure is incremented by 1. These functions do not change *sz_* * unless there is no more room in the array. Some of these functions fill in the values of the element's structure from the arguments. For other functions, you must explicitly write code to fill the structure's elements.

The top-level geometry description includes a list of *geometry properties* . A geometry property associates an arbitrary string with an equally arbitrary name. Programs that display images of keyboards can use geometry properties as hints, but they are not interpreted by Xkb. No other geometry structures refer to geometry properties.

To add one property to an existing keyboard geometry description, use *XkbAddGeomProperty* .

XkbPropertyPtr *XkbAddGeomProperty* (*geom* , *name* , *value*)
XkbGeometryPtr *geom* ; /* geometry to be updated */
char * *name* ; /* name of the new property */
char * *value* ; /* value for the new property */

XkbAddGeomProperty adds one property with the specified *name* and *value* to the keyboard geometry specified by geom. *XkbAddGeomProperty* returns *NULL* if any of the parameters is empty or if it was not able to allocate space for the property. To allocate space for an arbitrary number of properties, use the XkbAllocGeomProps function.

To add one key alias to an existing keyboard geometry description, use *XkbAddGeomKeyAlias* .

XkbKeyAliasPtr *XkbAddGeomKeyAlias* (*geom* , *alias, real*)
XkbGeometryPtr *geom* ; /* geometry to be updated */
char * *alias* ; /* alias to be added */
char * *real* ; /* real name to be bound to the new alias */

XkbAddGeomKeyAlias adds one key alias with the value alias to the geometry geom, and associates it with the key whose real name is real. *XkbAddGeomKeyAlias* returns *NULL* if any of the parameters is empty or if it was not able to allocate space for the alias. To allocate space for an arbitrary number of aliases, use the XkbAllocGeomKeyAliases function.

To add one color name to an existing keyboard geometry description, use *XkbAddGeomColor* .

XkbColorPtr *XkbAddGeomColor* (*geom* , *spec* , *pixel*)
XkbGeometryPtr *geom* ; /* geometry to be updated */
char * *spec* ; /* color to be added */
unsigned int *pixel* ; /* color to be added */

XkbAddGeomColor adds the specified color *name* and *pixel* to the specified geometry *geom* . The top-level geometry description includes a list of up to *MaxColors* (32) *color names* . A color *name* is a string whose interpretation is not specified by Xkb and neither is the *pixel* value's interpretation. All other geometry data structures refer to colors using their indices in this global list or pointers to colors in this list. *XkbAddGeomColor* returns *NULL* if any of the parameters is empty or if it was not able to allocate space for the color. To allocate space for an arbitrary number of colors to a geometry, use the *XkbAllocGeomColors* function.

To add one outline to an existing shape, use *XkbAddGeomOutline*.

XkbOutlinePtr *XkbAddGeomOutline* (*shape* , *sz_points*)
XkbShapePtr *shape* ; /* shape to be updated */
int *sz_points* ; /* number of points to be reserved */

An outline consists of an arbitrary number of points. *XkbAddGeomOutline* adds an outline to the specified *shape* by reserving *sz_points* points for it. The new outline is allocated and zeroed. *XkbAddGeomOutline* returns *NULL* if any of the parameters is empty or if it was not able to allocate space. To allocate space for an arbitrary number of outlines to a shape, use XkbAllocGeomOutlines.

To add a shape to a keyboard geometry, use *XkbAddGeomShape* .

XkbShapePtr *XkbAddGeomShape* (*geom* , *name* , *sz_outlines*)

XkbGeometryPtr *geom* ; /* geometry to be updated */

Atom *name* ; /* name of the new shape */

int *sz_outlines* ; /* number of outlines to be reserved */

A geometry contains an arbitrary number of shapes, each of which is made up of an arbitrary number of outlines. *XkbAddGeomShape* adds a shape to a geometry *geom* by allocating space for *sz_outlines* outlines for it and giving it the name specified by name. If a shape with name *name* already exists in the geometry, a pointer to the existing shape is returned. *XkbAddGeomShape* returns *NULL* if any of the parameters is empty or if it was not able to allocate space. To allocate space for an arbitrary number of geometry shapes, use *XkbAllocGeomShapes* .

To add one key at the end of an existing row of keys, use *XkbAddGeomKey* .

XkbKeyPtr *XkbAddGeomKey* (*row*)

XkbRowPtr *row* ; /* row to be updated */

Keys are grouped into rows. *XkbAddGeomKey* adds one key to the end of the specified *row* . The key is allocated and zeroed. *XkbAddGeomKey* returns *NULL* if *row* is empty or if it was not able to allocate space for the key. To allocate space for an arbitrary number of keys to a row, use XkbAllocGeomKeys.

To add one section to an existing keyboard geometry, use *XkbAddGeomSection* .

XkbSectionPtr *XkbAddGeomSection* (*geom* , *name* , *sz_rows* , *sz_doodads* , *sz_overlays*)

XkbGeometryPtr *geom* ; /* geometry to be updated */

Atom *name* ; /* name of the new section */

int *sz_rows* ; /* number of rows to reserve in the section */

int *sz_doodads* ; /* number of doodads to reserve in the section */

int *sz_overlays* ; /* number of overlays to reserve in the section */

A keyboard geometry contains an arbitrary number of sections. *XkbAddGeomSection* adds one section to an existing keyboard geometry *geom* . The new section contains space for the number of rows, doodads, and overlays specified by *sz_rows* , *sz_doodads* , and *sz_overlays* . The new section is allocated and zeroed and given the name specified by *name* . If a section with name *name* already exists in the geometry, a pointer to the existing section is returned. *XkbAddGeomSection* returns *NULL* if any of the parameters is empty or if it was not able to allocate space for the section. To allocate space for an arbitrary number of sections to a geometry, use XkbAllocGeomSections.

To add a row to a section, use *XkbAddGeomRow* .

XkbRowPtr *XkbAddGeomRow* (*section* , *sz_keys*)

XkbSectionPtr *section* ; /* section to be updated */

int *sz_keys* ; /* number of keys to be reserved */

One of the components of a keyboard geometry section is one or more rows of keys. *XkbAddGeomRow* adds one row to the specified *section* . The newly created row

contains space for the number of keys specified in *sz_keys* . They are allocated and zeroed, but otherwise uninitialized. *XkbAddGeomRow* returns *NULL* if any of the parameters is empty or if it was not able to allocate space for the row. To allocate space for an arbitrary number of rows to a section, use the XkbAllocGeomRows function.

To add one doodad to a section of a keyboard geometry or to the top-level geometry, use *XkbAddGeomDoodad* .

XkbDoodadPtr *XkbAddGeomDoodad* (*geom* , *section* , *name*)

XkbGeometryPtr *geom* ; /* geometry to which the doodad is added */

XkbSectionPtr *section* ; /* section, if any, to which the doodad is added */

Atom *name* ; /* name of the new doodad */

A *doodad* describes some visible aspect of the keyboard that is not a key and is not a section. *XkbAddGeomDoodad* adds a doodad with name specified by name to the geometry *geom* if section is *NULL* or to the section of the geometry specified by section if *section* is not *NULL* . *XkbAddGeomDoodad* returns *NULL* if any of the parameters is empty or if it was not able to allocate space for the doodad. If there is already a doodad with the name *name* in the doodad array for the geometry (if *section* is *NULL*) or the section (if *section* is non- *NULL*), a pointer to that doodad is returned. To allocate space for an arbitrary number of doodads to a section, use the XkbAllocGeomSectionDoodads function. To allocate space for an arbitrary number of doodads to a keyboard geometry, use the XkbAllocGeomDoodads function.

To add one overlay to a section, use *XkbAddGeomOverlay* .

XkbOverlayPtr *XkbAddGeomOverlay* (*section* , *name* , *sz_rows*)

XkbSectionPtr *section* ; /* section to which an overlay will be added */

Atom *name* ; /* name of the overlay */

int *sz_rows* ; /* number of rows to reserve in the overlay */

XkbAddGeomOverlay adds an overlay with the specified name to the specified *section* . The new overlay is created with space allocated for sz_rows rows. If an overlay with name *name* already exists in the section, a pointer to the existing overlay is returned. *XkbAddGeomOverlay* returns *NULL* if any of the parameters is empty or if it was not able to allocate space for the overlay. To allocate space for an arbitrary number of overlays to a section, use the XkbAllocGeomOverlay function.

To add a row to an existing overlay, use *XkbAddGeomOverlayRow* .

XkbOverlayRowPtr *XkbAddGeomOverlayRow* (*overlay* , *row_under, sz_keys*)

XkbOverlayPtr *overlay* ; /* overlay to be updated */

XkbRowPtr *row_under* ; /* row to be overlayed in the section *overlay* overlays */

int *sz_keys* ; /* number of keys to reserve in the row */

XkbAddGeomOverlayRow adds one row to the *overlay* . The new row contains space for *sz_keys* keys. If *row_under* specifies a row that doesn't exist on the underlying section, *XkbAddGeomOverlayRow* returns *NULL* and doesn't change the overlay. *XkbAddGeomOverlayRow* returns *NULL* if any of the parameters is empty or if it was not able to allocate space for the overlay.

To add a key to an existing overlay row, use *XkbAddGeomOverlayKey* .

XkbOverlayKeyPtr *XkbAddGeomOverlayKey* (*overlay* , *row, under*)
XkbOverlayPtr *overlay* ; /* overlay to be updated */
XkbRowPtr *row* ; /* row in overlay to be updated */
char * *under* ; /* primary name of the key to be considered */

XkbAddGeomOverlayKey adds one key to the *row* in the *overlay* . If there is no key named *under* in the row of the underlying section, *XkbAddGeomOverlayKey* returns *NULL* .

Allocating and Freeing Geometry Components

Xkb provides a number of functions to allocate and free subcomponents of a keyboard geometry. Use these functions to create or modify keyboard geometries. Note that these functions merely allocate space for the new element(s), and it is up to you to fill in the values explicitly in your code. These allocation functions increase *sz_* * but never touch *num_* * (unless there is an allocation failure, in which case they reset both *sz_* * and *num_* * to zero). These functions return *Success* if they succeed, *BadAlloc* if they are not able to allocate space, or *BadValue* if a parameter is not as expected.

To allocate space for an arbitrary number of outlines to a shape, use XkbAllocGeomOutlines.

Status *XkbAllocGeomOutlines* (*shape* , *num_needed*)
XkbShapePtr *shape* ; /* shape for which outlines should be allocated */
int *num_needed* ; /* number of new outlines required */

XkbAllocGeomOutlines allocates space for *num_needed* outlines in the specified *shape* . The outlines are not initialized.

To free geometry outlines, use *XkbFreeGeomOutlines* .

void *XkbFreeGeomOutlines* (*shape* , *first* , *count* , *free_all*)
XkbShapePtr *shape* ; /* shape in which outlines should be freed */
int *first* ; /* first outline to be freed */
int *count* ; /* number of outlines to be freed */
Bool *free_all;* /* *True* => all outlines are freed */

If free_all is *True* , all outlines are freed regardless of the value of first or count. Otherwise, count outlines are freed beginning with the one specified by first.

To allocate space for an arbitrary number of keys to a row, use XkbAllocGeomKeys.

Status *XkbAllocGeomKeys* (*row* , *num_needed*)
XkbRowPtr *row* ; /* row to which keys should be allocated */
int *num_needed* ; /* number of new keys required */

XkbAllocGeomKeys allocates num_needed keys and adds them to the row. No initialization of the keys is done.

To free geometry keys, use *XkbFreeGeomKeys* .

void *XkbFreeGeomKeys* (*row* , *first* , *count* , *free_all*)
XkbRowPtr *row* ; /* row in which keys should be freed */
int *first* ; /* first key to be freed */
int *count* ; /* number of keys to be freed */
Bool *free_all;* /* *True* => all keys are freed */

If free_all is *True* , all keys are freed regardless of the value of first or count. Otherwise, count keys are freed beginning with the one specified by first.

To allocate geometry properties, use *XkbAllocGeomProps* .

Status *XkbAllocGeomProps* (*geom* , *num_needed*)
XkbGeometryPtr *geom* ; /* geometry for which properties should be allocated */
int *num_needed* ; /* number of new properties required */

XkbAllocGeomProps allocates space for num_needed properties and adds them to the specified geometry *geom* . No initialization of the properties is done. A geometry property associates an arbitrary string with an equally arbitrary name. Geometry properties can be used to provide hints to programs that display images of keyboards, but they are not interpreted by Xkb. No other geometry structures refer to geometry properties.

To free geometry properties, use *XkbFreeGeomProperties* .

void *XkbFreeGeomProperties* (*geom* , *first* , *count* , *free_all*)
XkbGeometryPtr *geom* ; /* geometry in which properties should be freed */
int *first* ; /* first property to be freed */
int *count* ; /* number of properties to be freed */
Bool *free_all;* /* *True* => all properties are freed */

If free_all is *True* , all properties are freed regardless of the value of first or count. Otherwise, count properties are freed beginning with the one specified by first.

To allocate geometry key aliases, use *XkbAllocGeomKeyAliases* .

Status *XkbAllocGeomKeyAliases* (*geom* , *num_needed*)
XkbGeometryPtr *geom* ; /* geometry for which key aliases should be allocated */
int *num_needed* ; /* number of new key aliases required */

XkbAllocGeomKeyAliases allocates space for num_needed key aliases and adds them to the specified geometry *geom* . A key alias is a pair of strings that associates an alternate name for a key with the real name for that key.

To free geometry key aliases, use *XkbFreeGeomKeyAliases* .

void *XkbFreeGeomKeyAliases* (*geom* , *first* , *count* , *free_all*)
XkbGeometryPtr *geom* ; /* geometry in which key aliases should be freed */
int *first* ; /* first key alias to be freed */
int *count* ; /* number of key aliases to be freed */
Bool *free_all;* /* *True* => all key aliases are freed */

If free_all is *True* , all aliases in the top level of the specified geometry *geom* are freed regardless of the value of first or count. Otherwise, count aliases in *geom* are freed beginning with the one specified by first.

To allocate geometry colors, use *XkbAllocGeomColors* .

Status *XkbAllocGeomColors* (*geom* , *num_needed*)
XkbGeometryPtr *geom* ; /* geometry for which colors should be allocated */
int *num_needed* ; /* number of new colors required. */

XkbAllocGeomColors allocates space for num_needed colors and adds them to the specified geometry *geom* . A color name is a string whose interpretation is not specified by Xkb. All other geometry data structures refer to colors using their indices in this global list or pointers to colors in this list.

To free geometry colors, use *XkbFreeGeomColors* .

void *XkbFreeGeomColors* (*geom* , *first* , *count* , *free_all*)
XkbGeometryPtr *geom* ; /* geometry in which colors should be freed */
int *first* ; /* first color to be freed */
int *count* ; /* number of colors to be freed */
Bool *free_all;* /* *True* => all colors are freed */

If free_all is *True* , all colors are freed regardless of the value of first or count. Otherwise, count colors are freed beginning with the one specified by first.

To allocate points in an outline, use *XkbAllocGeomPoints* .

Status *XkbAllocGeomPoints* (*outline* , *num_needed*)
XkbOutlinePtr *outline* ; /* outline for which points should be allocated */
int *num_needed* ; /* number of new points required */

XkbAllocGeomPoints allocates space for *num_needed* points in the specified *outline* . The points are not initialized.

To free points in a outline, use *XkbFreeGeomPoints* .

void *XkbFreeGeomPoints* (*outline* , *first* , *count* , *free_all*)
XkbOutlinePtr *outline* ; /* outline in which points should be freed */
int *first* ; /* first point to be freed. */
int *count* ; /* number of points to be freed */
Bool *free_all;* /* *True* => all points are freed */

If free_all is *True* , all points are freed regardless of the value of first and count. Otherwise, the number of points specified by count are freed, beginning with the point specified by first in the specified outline.

To allocate space for an arbitrary number of geometry shapes, use *XkbAllocGeomShapes* .

Status *XkbAllocGeomShapes* (*geom* , *num_needed*)
XkbGeometryPtr *geom* ; /* geometry for which shapes should be allocated */
int *num_needed* ; /* number of new shapes required */

XkbAllocGeomShapes allocates space for *num_needed* shapes in the specified geometry *geom* . The shapes are not initialized.

To free geometry shapes, use *XkbFreeGeomShapes* .

void *XkbFreeGeomShapes* (*geom* , *first* , *count* , *f ree_all*)
XkbGeometryPtr *geom* ; /* geometry in which shapes should be freed */
int *first* ; /* first shape to be freed */
int *count* ; /* number of shapes to be freed */
Bool *free_all;* /* *True* => all shapes are freed */

If free_all is *True* , all shapes in the geometry are freed regardless of the values of first and count. Otherwise, count shapes are freed, beginning with the shape specified by first.

To allocate geometry sections, use *XkbAllocGeomSections* .

Status *XkbAllocGeomSections* (*geom* , *num_needed*)
XkbGeometryPtr *geom* ; /*geometry for which sections should be allocated */
int *num_needed* ; /* number of new sections required */

XkbAllocGeomSections allocates num_needed sections and adds them to the geometry geom. No initialization of the sections is done.

To free geometry sections, use *XkbFreeGeomSections* .

void *XkbFreeGeomSections* (*geom* , *first* , *count* , *free_all*)
XkbGeometryPtr *geom* ; /* geometry in which sections should be freed */
int *first* ; /* first section to be freed. */
int *count* ; /* number of sections to be freed */
Bool *free_all;* /* *True* => all sections are freed */

If free_all is *True* , all sections are freed regardless of the value of first and count. Otherwise, the number of sections specified by count are freed, beginning with the section specified by first in the specified geometry.

To allocate rows in a section, use *XkbAllocGeomRows* .

Status *XkbAllocGeomRows* (*section* , *num_needed*)
XkbSectionPtr *section* ; /* section for which rows should be allocated */
int *num_needed* ; /* number of new rows required */

XkbAllocGeomRows allocates num_needed rows and adds them to the section. No initialization of the rows is done.

To free rows in a section, use *XkbFreeGeomRows* .

void *XkbFreeGeomRows* (*section* , *first* , *count* , *free_all*)
XkbSectionPtr *section* ; /* section in which rows should be freed */
int *first* ; /* first row to be freed. */
int *count* ; /* number of rows to be freed */
Bool *free_all;* /* *True* => all rows are freed */

If free_all is *True* , all rows are freed regardless of the value of first and count. Otherwise, the number of rows specified by count are freed, beginning with the row specified by first in the specified section.

To allocate overlays in a section, use *XkbAllocGeomOverlays* .

Status *XkbAllocGeomOverlays* (*section* , *num_needed*)
XkbSectionPtr *section* ; /* section for which overlays should be allocated */
int *num_needed* ; /* number of new overlays required */

XkbAllocGeomRows allocates num_needed overlays and adds them to the section. No initialization of the overlays is done.

To free rows in an section, use *XkbFreeGeomOverlays* .

void *XkbFreeGeomOverlays* (*section* , *first* , *count* , *free_all*)
XkbSectionPtr *section* ; /* section in which overlays should be freed */
int *first* ; /* first overlay to be freed. */
int *count* ; /* number of overlays to be freed */
Bool *free_all;* /* *True* => all overlays are freed */

If free_all is *True* , all overlays are freed regardless of the value of first and count. Otherwise, the number of overlays specified by count are freed, beginning with the overlay specified by first in the specified section.

To allocate rows in a overlay, use *XkbAllocGeomOverlayRows* .

Status *XkbAllocGeomOverlayRows* (*overlay* , *num_needed*)
XkbSectionPtr *overlay* ; /* section for which rows should be allocated */
int *num_needed* ; /* number of new rows required */

XkbAllocGeomOverlayRows allocates num_needed rows and adds them to the overlay. No initialization of the rows is done.

To free rows in an overlay, use *XkbFreeGeomOverlayRows* .

void *XkbFreeGeomOverlayRows* (*overlay* , *first* , *count* , *free_all*)
XkbSectionPtr *overlay* ; /* section in which rows should be freed */
int *first* ; /* first row to be freed. */
int *count* ; /* number of rows to be freed */
Bool *free_all;* /* *True* => all rows are freed */

If free_all is *True* , all rows are freed regardless of the value of first and count. Otherwise, the number of rows specified by count are freed, beginning with the row specified by first in the specified overlay.

To allocate keys in an overlay row, use *XkbAllocGeomOverlayKeys* .

Status *XkbAllocGeomOverlayKeys* (*row* , *num_needed*)
XkbRowPtr *row* ; /* section for which rows should be allocated */
int *num_needed* ; /* number of new rows required */

XkbAllocGeomOverlayKeys allocates num_needed keys and adds them to the row. No initialization of the keys is done.

To free keys in an overlay row, use *XkbFreeGeomOverlayKeys* .

void *XkbFreeGeomOverlayKeys* (*row* , *first* , *count* , *free_all*)
XkbRowPtr *row* ; /* row in which keys should be freed */
int *first* ; /* first key to be freed. */
int *count* ; /* number of keys to be freed */
Bool *free_all;* /* *True* => all keys are freed */

If free_all is *True* , all keys are freed regardless of the value of first and count. Otherwise, the number of keys specified by count are freed, beginning with the key specified by first in the specified row.

To allocate doodads that are global to a keyboard geometry, use *XkbAllocGeom-Doodads* .

Status *XkbAllocGeomDoodads* (*geom* , *num_needed*)
XkbGeometryPtr *geom* ; /* geometry for which doodads should be allocated */
int *num_needed* ; /* number of new doodads required */

XkbAllocGeomDoodads allocates num_needed doodads and adds them to the specified geometry *geom* . No initialization of the doodads is done.

To allocate doodads that are specific to a section, use *XkbAllocGeomSectionDoo-dads* .

Status *XkbAllocGeomSectionDoodads* (*section* , *num_needed*)
XkbSectionPtr *section* ; /* section for which doodads should be allocated */
int *num_needed* ; /* number of new doodads required */

XkbAllocGeomSectionDoodads allocates num_needed doodads and adds them to the specified *section* . No initialization of the doodads is done.

To free geometry doodads, use *XkbFreeGeomDoodads* .

void *XkbFreeGeomDoodads* (*doodads* , *count* , *free_all*)
XkbDoodadPtr *doodads* ; /* doodads to be freed */
int *count* ; /* number of doodads to be freed */
Bool *free_all;* /* *True* => all doodads are freed */

If *free_all* is *True* , all doodads in the array are freed, regardless of the value of count. Otherwise, count doodads are freed.

To allocate an entire geometry, use *XkbAllocGeometry* .

Status *XkbAllocGeometry* (*xkb* , *sizes*)

XkbDescPtr *xkb* ; /* keyboard description for which geometry is to be allocated */

XkbGeometrySizesPtr *sizes* ; /* initial sizes for all geometry components */

XkbAllocGeometry allocates a keyboard geometry and adds it to the keyboard description specified by xkb. The keyboard description should be obtained via the XkbGetKeyboard or XkbAllockeyboard functions. The sizes parameter specifies the number of elements to be reserved for the subcomponents of the keyboard geometry and can be zero or more. These subcomponents include the properties, colors, shapes, sections, and doodads.

To free an entire geometry, use *XkbFreeGeometry* .

void *XkbFreeGeometry* (*geom* , *which* , *free_all*)

XkbGeometryPtr *geom* ; /* geometry to be freed */

unsigned int *which* ; /* mask of geometry components to be freed */

Bool *free_all;* /* *True* => the entire geometry is freed. */

The values of which and free_all determine how much of the specified geometry is freed. The valid values for which are:

```
#define      XkbGeomPropertiesMask  (1<<0)
#define      XkbGeomColorsMask      (1<<1)
#define      XkbGeomShapesMask      (1<<2)
#define      XkbGeomSectionsMask    (1<<3)
#define      XkbGeomDoodadsMask     (1<<4)
#define      XkbGeomAllMask         (0x1f)
```

If free_all is *True* , the entire geometry is freed regardless of the value of which. Otherwise, the portions of the geometry specified by which are freed.

Chapter 14. Xkb Keyboard Mapping

The Xkb keyboard mapping contains all the information the server and clients need to interpret key events. This chapter provides an overview of the terminology used to describe an Xkb keyboard mapping and introduces common utilities for manipulating the keyboard mapping.

The mapping consists of two components, a server map and a client map. The *client* map is the collection of information a client needs to interpret key events from the keyboard. It contains a global list of key types and an array of key symbol maps, each of which describes the symbols bound to a key and the rules to be used to interpret those symbols. The *server* map contains the information the server needs to interpret key events. This includes actions and behaviors for each key, explicit components for a key, and the virtual modifiers and the per-key virtual modifier mapping.

For detailed information on particular components of the keyboard map, refer to Chapter 15, "Xkb Client Keyboard Mapping" and Chapter 16, "Xkb Server Keyboard Mapping."

Notation and Terminology

The graphic characters or control functions that may be accessed by one key are logically arranged in groups and levels, where *group* and *level* are defined as in the ISO9995 standard:

Group: A logical state of a keyboard providing access to a collection of graphic characters. Usually these graphic characters logically belong together and may be arranged on several levels within a group.

Level: One of several states (normally 2 or 3) governing which graphic character is produced when a graphic key is actuated. In certain cases the level may also affect function keys.

These definitions, taken from the ISO standard, refer to graphic keys and characters. In the context of Xkb, Group and Level are not constrained to graphic keys and characters; they may be used with any key to access any character the key is capable of generating.

Level is often referred to as "Shift Level". Levels are numbered sequentially starting at one.

Note

Shift level is derived from the modifier state, but not necessarily in the same way for all keys. For example, the *Shift* modifier selects shift level 2 on most keys, but for keypad keys the modifier bound to *Num_Lock* (that is, the *NumLock* virtual modifier) also selects shift level 2.

For example, consider the following key (the gray characters indicate symbols that are implied or expected but are not actually engraved on the key):



Shift Levels and Groups

This key has two groups, indicated by the columns, and each group has two shift levels. For the first group (Group1), the symbol shift level one is *a* , and the symbol for shift level two is *A* . For the second group, the symbol for shift level one is *æ* , and the symbol for shift level two is *Æ* .

Core Implementation

The standard interpretation rules for the core X keymap only allow clients to access keys such as the one shown in Figure 14.1. That is, clients using the standard interpretation rules can only access one of four keysyms for any given *KeyPress* event — two different symbols in two different groups.

In general, the *Shift* modifier, the *Lock* modifier, and the modifier bound to the *Num_Lock* key are used to change between shift level 1 and shift level 2. To switch between groups, the core implementation uses the modifier bound to the *Mode_switch* key. When the *Mode_switch* modifier is set, the keyboard is logically in Group 2. When the *Mode_switch* modifier is not set, the keyboard is logically in Group 1.

The core implementation does not clearly specify the behavior of keys. For example, the locking behavior of the *CapsLock* and *Num_Lock* keys depends on the vendor.

Xkb Implementation

Xkb extends the core implementation by providing access to up to four keyboard groups with up to 63 shift levels per key [1]. In addition, Xkb provides precise specifications regarding the behavior of keys. In Xkb, modifier state and the current group are independent (with the exception of compatibility mapping, discussed in Chapter 17).

Xkb handles switching between groups via key actions, independent of any modifier state information. Key actions are in the server map component and are described in detail in section 16.1.4.

Xkb handles shift levels by associating a key type with each group on each key. Each key type defines the shift levels available for the groups on keys of its type and specifies the modifier combinations necessary to access each level.

[1] The core implementation restricts the number of symbols per key to 255. With four groups, this allows for up to 63 symbols (or shift levels) per group. Most keys will only have a few shift levels.

For example, Xkb allows key types where the *Control* modifier can be used to access the shift level two of a key. Key types are in the client map component and are described in detail in section 15.2.

Xkb provides precise specification of the behavior of a key using key behaviors. Key behaviors are in the server map component and are described in detail in section 16.2.

Getting Map Components from the Server

Xkb provides two functions to obtain the keyboard mapping components from the server. The first function, *XkbGetMap* , allocates an *XkbDescRec* structure, retrieves mapping components from the server, and stores them in the *XkbDescRec* structure it just allocated. The second function, *XkbGetUpdatedMap* , retrieves mapping components from the server and stores them in an *XkbDescRec* structure that has previously been allocated.

To allocate an *XkbDescRec* structure and populate it with the server's keyboard client map and server map, use *XkbGetMap. XkbGetMap* is similar to *XkbGetKeyboard* (see section 6.2), but is used only for obtaining the address of an *XkbDescRec* structure that is populated with keyboard mapping components. It allows finer control over which substructures of the keyboard mapping components are to be populated. *XkbGetKeyboard* always returns fully populated components, while *XkbGetMap* can be instructed to return a partially populated component.

XkbDescPtr *XkbGetMap* (*display, which, device_spec*)
Display * *display* ; /* connection to X server */
unsigned int *which* ; /* mask selecting subcomponents to populate */
unsigned int *device_spec* ; /* device_id, or *XkbUseCoreKbd* */

The *which* mask is a bitwise inclusive OR of the masks defined in Table 14.1. Only those portions of the keyboard server map and the keyboard client maps that are specified in *which* are allocated and populated.

In addition to allocating and obtaining the server map and the client map, *XkbGetMap* also sets the *device_spec* , the *min_key_code* , and *max_key_code* fields of the keyboard description.

XkbGetMap is synchronous; it queries the server for the desired information, waits for a reply, and then returns. If successful , *XkbGetMap* returns a pointer to the *XkbDescRec* structure it allocated. If unsuccessful, *XkbGetMap* returns *NULL* . When unsuccessful, one of the following protocol errors is also generated: *BadAlloc* (unable to allocate the *XkbDescRec* structure), *BadValue* (some mask bits in *which* are undefined) , or *BadImplementation* (a compatible version of the Xkb extension is not available in the server). To free the returned data, use *XkbFreeClientMap* .

Xkb also provides convenience functions to get partial component definitions from the server. These functions are specified in the "convenience functions" column in Table 14.1. Refer to the sections listed in the table for more information on these functions.

Table 14.1. Xkb Mapping Component Masks and Convenience Functions

Mask	Value	Map	Fields	Convenience Functions	Section
XkbKeyTypesMask	(1<<0)	client	*types*	*XkbGetKeyTypes*	15.2
			size_types	*XkbResizeKeyType*	
			num_types	*XkbCopyKeyType*	
				XkbCopyKeyTypes	
XkbKeySymsMask	(1<<1)	client	*syms*	*XkbGetKeySyms*	15.3
			size_syms	*XkbResizeKeySyms*	
			num_syms	*XkbChangeTypesOfKey*	
			key_sym_map		
XkbModifierMapMask	(1<<2)	client	*modmap*	*XkbGetKeyModifierMap*	15.4
XkbExplicitComponentsMask	(1<<3)	server	*explicit*	*XkbGetKeyExplicitComponents*	16.3
XkbKeyActionsMask	(1<<4)	server	*key_acts*	*XkbGetKeyActions*	16.1
			acts	*XkbResizeKeyActions*	
			num_acts		
			size_acts		
XkbKeyBehaviorsMask	(1<<5)	server	*behaviors*	*XkbGetKeyBehaviors*	16.2
XkbVirtualModsMask	(1<<6)	server	*vmods*	*XkbGetVirtualMods*	16.4
XkbVirtualModMapMask	(1<<7)	server	*vmodmap*	*XkbGetVirtualModMap*	16.4

Xkb defines combinations of these masks for convenience:

```
#define  XkbResizableInfoMask      (XkbKeyTypesMask)
#define  XkbAllClientInfoMask      (XkbKeyTypesMask | XkbKeySymsMask |
                                    XkbModifierMapMask)
#define  XkbAllServerInfoMask      (XkbExplicitComponentsMask |
                                    XkbKeyActionsMask| XkbKeyBehaviorsMask |
                                    XkbVirtualModsMask | XkbVirtualModMapMask)
#define  XkbAllMapComponentsMask   (XkbAllClientInfoMask|XkbAllServerInfoMask)
```

Key types, symbol maps, and actions are all interrelated: changes in one require changes in the others. The convenience functions make it easier to edit these components and handle the interdependencies.

To update the client or server map information in an existing keyboard description, use *XkbGetUpdatedMap*.

Status *XkbGetUpdatedMap* (*display, which, xkb*)
Display * *display* ; /* connection to X server */
unsigned int *which* ; /* mask selecting subcomponents to populate */
XkbDescPtr *xkb* ; /* keyboard description to be updated */

The *which* parameter is a bitwise inclusive OR of the masks in Table 14.1. If the needed components of the *xkb* structure are not already allocated, *XkbGetUpdatedMap* allocates them. *XkbGetUpdatedMap* fetches the requested information for the device specified in the *XkbDescRec* passed in the *xkb* parameter.

XkbGetUpdatedMap is synchronous; it queries the server for the desired information, waits for a reply, and then returns. If successful , *XkbGetUpdatedMap* returns *Success* . If unsuccessful, *XkbGetUpdatedMap* returns one of the following: *BadAlloc* (unable to allocate a component in the *XkbDescRec* structure), *BadValue* (some mask bits in *which* are undefined), *BadImplementation* (a compatible version of the Xkb extension is not available in the server or the reply from the server was invalid).

Changing Map Components in the Server

There are two ways to make changes to map components: either change a local copy of the keyboard map and call *XkbSetMap* to send the modified map to the server, or, to reduce network traffic, use an *XkbMapChangesRec* structure and call *XkbChangeMap*.

Bool *XkbSetMap* (*dpy* , *which* , *xkb*)
Display * *dpy* ; /* connection to X server */
unsigned int *which* ; /* mask selecting subcomponents to update */
XkbDescPtr *xkb* ; /* description from which new values are taken */

Use *XkbSetMap* to send a complete new set of values for entire components (for example, all symbols, all actions, and so on) to the server. The *which* parameter specifies the components to be sent to the server, and is a bitwise inclusive OR of the masks listed in Table 14.1. The *xkb* parameter is a pointer to an *XkbDescRec* structure and contains the information to be copied to the server. For each bit set in the *which* parameter, *XkbSetMap* takes the corresponding structure values from the *xkb* parameter and sends it to the server specified by *dpy*.

If any components specified by *which* are not present in the *xkb* parameter, *XkbSetMap* returns *False* . Otherwise, it sends the update request to the server and returns *True* . *XkbSetMap* can generate *BadAlloc* , *BadLength* , and *BadValue* protocol errors.

Key types, symbol maps, and actions are all interrelated; changes in one require changes in the others. Xkb provides functions to make it easier to edit these components and handle the interdependencies. Table 14.1 lists these helper functions and provides a pointer to where they are defined.

The XkbMapChangesRec Structure

Use the *XkbMapChangesRec* structure to identify and track partial modifications to the mapping components and to reduce the amount of traffic between the server and clients.

```
typedef struct _XkbMapChanges {
      unsigned short    changed;             /* identifies valid components
                                                in structure */
      KeyCode           min_key_code;        /* lowest numbered keycode for
                                                device */
      KeyCode           max_key_code;        /* highest numbered keycode for
                                                device */
      unsigned char     first_type;          /* index of first key type
                                                modified */
      unsigned char     num_types;           /* # types modified */
      KeyCode           first_key_sym;       /* first key whose key_sym_map
                                                changed */
      unsigned char     num_key_syms;        /* # key_sym_map
                                                entries changed */
      KeyCode           first_key_act;       /* first key whose key_acts
                                                entry changed */
      unsigned char     num_key_acts;        /* # key_acts
                                                entries changed */
      KeyCode           first_key_behavior;  /* first key whose behaviors
                                                changed */
      unsigned char     num_key_behaviors;   /* # behaviors
                                                entries changed */
      KeyCode           first_key_explicit;  /* first key whose explicit
                                                entry changed */
      unsigned char     num_key_explicit;    /* #  explicit
                                                entries changed */
      KeyCode           first_modmap_key;    /* first key whose modmap
                                                entry changed */
      unsigned char     num_modmap_keys;     /* # modmap
                                                entries changed */
      KeyCode           first_vmodmap_key;   /* first key whose vmodmap
                                                changed */
      unsigned char     num_vmodmap_keys;    /* #  vmodmap
                                                entries changed */
      unsigned char     pad1;                /* reserved */
      unsigned short    vmods;               /* mask indicating which vmods
                                                changed */
} XkbMapChangesRec,*XkbMapChangesPtr;
```

The *changed* field identifies the map components that have changed in an *XkbDescRec* structure and may contain any of the bits in Table 14.1, which are also shown in Table 14.2. Every 1 bit in *changed* also identifies which other fields in the *XkbMapChangesRec* structure contain valid values, as indicated in Table 14.2. The *min_key_code* and *max_key_code* fields are for reference only; they are ignored on any requests sent to the server and are always updated by the server whenever it returns the data for an *XkbMapChangesRec* .

Table 14.2. XkbMapChangesRec Masks

Mask	Valid XkbMapChanges-Rec Fields	XkbDescRec Field Containing Changed Data
XkbKeyTypesMask	first_type , num_types	map->type[first_type] .. map->type[first_type + num_types - 1]
XkbKeySymsMask	first_key_sym , num_key_syms	map->key_sym_map[first_key_sym] .. map->key_sym_map[first_key_sym + num_key_syms - 1]
XkbModifierMapMask	first_modmap_key , num_modmap_keys	map->modmap[first_modmap_key] .. map->modmap[first_modmap_key + num_modmap_keys-1]
XkbExplicitComponents-Mask	first_key_explicit , num_key_explicit	server->explicit[first_key_explicit] .. server->explicit[first_key_explicit + num_key_explicit - 1]
XkbKeyActionsMask	first_key_act, num_key_acts	server->key_acts[first_key_act] .. server->key_acts[first_key_act + num_key_acts - 1]
XkbKeyBehaviorsMask	first_key_behavior, num_key_behaviors	server->behaviors[first_key_behavior] .. server->behaviors[first_key_behavior + num_key_behaviors - 1]
XkbVirtuawModsMask	vmods	server->vmods[*]
XkbVirtualModMapMask	first_vmodmap_key, num_vmodmap_keys	server->vmodmap[first_vmodmap_key] .. server->vmodmap[first_vmodmap_key + num_vmodmap_keys - 1]

To update only partial components of a keyboard description, modify the appropriate fields in the server and map components of a local copy of the keyboard description, then call *XkbChangeMap* with an *XkbMapChangesRec* structure indicating which components have changed.

Bool *XkbChangeMap* (*dpy* , *xkb* , *changes*)

Display * *dpy* ; /* connection to X server */

XkbDescPtr *xkb* ; /* description from which new values are taken */

XkbMapChangesPtr *changes* ; /*identifies component parts to update */

XkbChangeMap copies any components specified by the *changes* structure from the keyboard description, *xkb* , to the X server specified by *dpy* .

If any components specified by *changes* are not present in the *xkb* parameter, *XkbChangeMap* returns *False* . Otherwise, it sends a request to the server and returns *True* .

XkbChangeMap can generate *BadAlloc* , *BadLength* , and *BadValue* protocol errors.

Tracking Changes to Map Components

The Xkb extension reports *XkbMapNotify* events to clients wanting notification whenever a map component of the Xkb description for a device changes. There are many different types of Xkb keyboard map changes. Xkb uses an event detail mask to identify each type of change. The event detail masks are identical to the masks listed in Table 14.1.

To receive *XkbMapNotify* events under all possible conditions, use *XkbSelectEvents* (see section 4.3) and pass *XkbMapNotifyMask* in both *bits_to_change* and *values_for_bits* .

To receive *XkbMapNotify* events only under certain conditions, use *XkbSelectEventDetails* using *XkbMapNotify* as the *event_type* and specifying the desired map changes in *bits_to_change* and *values_for_bits* using mask bits from Table 14.1.

The structure for *XkbMapNotify* events is:

```
typedef struct {
      int            type;         /* Xkb extension base event code */
      unsigned long  serial;       /* X server serial number for event */
      Bool           send_event;   /* True => synthetically generated */
      Display *      display;      /* server connection where event generated */
      Time           time;         /* server time when event generated */
      int            xkb_type;     /*  XkbMapNotify */
      int            device;       /* Xkb device ID, will not be XkbUseCoreKbd */
      unsigned int   changed;      /* identifies valid fields in rest of event */
      unsigned int   resized;      /* reserved */
      int            first_type;   /* index of first key  type modified */
      int            num_types     /* # types modified */
      KeyCode        min_key_code; /* minimum keycode for device */
      KeyCode        max_key_code; /* maximum keycode for device */
      KeyCode        first_key_sym; /* first key whose key_sym_map changed */
      KeyCode        first_key_act; /* first key whose  key_acts entry changed */
      KeyCode        first_key_behavior; /* first key whose  behaviors changed */
```

```
        KeyCode         first_key_explicit; /* first key whose  explicit  entry chang
        KeyCode         first_modmap_key;   /* first key whose  modmap entry changed
        KeyCode         first_vmodmap_key;  /* #  modmap entries changed */
        int             num_key_syms;       /* # key_sym_map entries changed */
        int             num_key_acts;       /* #  key_acts entries changed */
        int             num_key_behaviors;  /* #  behaviors entries changed */
        int             num_key_explicit;   /* #  explicit entries changed */
        int             num_modmap_keys;    /* #  modmap entries changed */
        int             num_vmodmap_keys;   /* #  vmodmap entries changed */
        unsigned in       t       vmods;    /* mask indicating which  vmods changed *
} XkbMapNotifyEvent;
```

The *changed* field specifies the map components that have changed and is the bitwise inclusive OR of the mask bits defined in Table 14.1. The other fields in this event are interpreted as the like-named fields in an *XkbMapChangesRec* (see section 14.3.1). The *XkbMapNotifyEvent* structure also has an additional *resized* field that is reserved for future use.

Allocating and Freeing Client and Server Maps

Calling *XkbGetMap* (see section 14.2) should be sufficient for most applications to get client and server maps. As a result, most applications do not need to directly allocate client and server maps.

If you change the number of key types or construct map components without loading the necessary components from the X server, do not allocate any map components directly using *malloc* or *Xmalloc* . Instead, use the Xkb allocators, *XkbAllocClientMap,* and *XkbAllocServerMap* .

Similarly, use the Xkb destructors, *XkbFreeClientMap,* and *XkbFreeServerMap* instead of *free* or *Xfree* .

Allocating an Empty Client Map

To allocate and initialize an empty client map description record, use *XkbAllocClientMap.*

Status *XkbAllocClientMap* (*xkb, which, type_count*)
XkbDescPtr *xkb* ; /* keyboard description in which to allocate client map */
unsigned int *which* ; /* mask selecting map components to allocate */
unsigned int *type_count* ; /* value of *num_types* field in map to be allocated */

XkbAllocClientMap allocates and initializes an empty client map in the *map* field of the keyboard description specified by *xkb* . The *which* parameter specifies the particular components of the client map structure to allocate and is a mask composed by a bitwise inclusive OR of one or more of the masks shown in Table 14.3.

Table 14.3. XkbAllocClientMap Masks

Mask	Effect
XkbKeyTypesMask	The *type_count* field specifies the number of entries to preallocate for the *types* field of the client map. If the *type_count* field is less than *XkbNumRequiredTypes* (see section 15.2.1), returns *BadValue*.
XkbKeySymsMask	The *min_key_code* and *max_key_code* fields of the *xkb* parameter are used to allocate the *syms* and *key_sym_map* fields of the client map. The fields are allocated to contain the maximum number of entries necessary for *max_key_code* - *min_key_code* + 1 keys.
XkbModifierMapMask	The *min_key_code* and *max_key_code* fields of the *xkb* parameter are used to allocate the *modmap* field of the client map. The field is allocated to contain the maximum number of entries necessary for *max_key_code* - *min_key_code* + 1 keys.

Note

The *min_key_code* and *max_key_code* fields of the *xkb* parameter must be legal values if the *XkbKeySymsMask* or *XkbModifierMapMask* masks are set in the *which* parameter. If they are not valid, *XkbAllocClientMap* returns *BadValue* .

If the client map of the keyboard description is not *NULL* , and any fields are already allocated in the client map, *XkbAllocClientMap* does not overwrite the existing values; it simply ignores that part of the request. The only exception is the *types* array. If *type_count* is greater than the current *num_types* field of the client map, *XkbAllocClientMap* resizes the *types* array and resets the *num_types* field accordingly.

If *XkbAllocClientMap* is successful, it returns *Success* . Otherwise, it can return either *BadMatch* , *BadAlloc* , or *BadValue* errors.

Freeing a Client Map

To free memory used by the client map member of an *XkbDescRec* structure, use *XkbFreeClientMap.*

void *XkbFreeClientMap* (*xkb, which, free_all*)
XkbDescPtr *xkb* ; /* keyboard description containing client map to free */
unsigned int *which* ; /* mask identifying components of map to free */
Bool *free_all* ; /* *True* => free all client components and map itself */

XkbFreeClientMap frees the components of client map specified by *which* in the *XkbDescRec* structure specified by the *xkb* parameter and sets the corresponding structure component values to *NULL* . The *which* parameter specifies a combination of the client map masks shown in Table 14.3.

If *free_all* is *True* , *which* is ignored; *XkbFreeClientMap* frees every non- *NULL* structure component in the client map, frees the *XkbClientMapRec* structure ref-

erenced by the *map* member of the *xkb* parameter, and sets the *map* member to *NULL.*

Allocating an Empty Server Map

To allocate and initialize an empty server map description record, use *XkbAllocServerMap.*

Status *XkbAllocServerMap* (*xkb, which, count_acts*)

XkbDescPtr *xkb* ; /* keyboard description in which to allocate server map */

unsigned int *which* ; /* mask selecting map components to allocate */

unsigned int *count_acts* ; /* value of *num_acts* field in map to be allocated */

XkbAllocServerMap allocates and initializes an empty server map in the *server* field of the keyboard description specified by *xkb* . The *which* parameter specifies the particular components of the server map structure to allocate, as specified in Table 14.4.

Table 14.4. XkbAllocServerMap Masks

Mask	Effect
XkbExplicitComponentsMask	The *min_key_code* and *max_key_code* fields of the *xkb* parameter are used to allocate the *explicit* field of the server map.
XkbKeyActionsMask	The *min_key_code* and *max_key_code* fields of the *xkb* parameter are used to allocate the *key_acts* field of the server map. The *count_acts* parameter is used to allocate the *acts* field of the server map.
XkbKeyBehaviorsMask	The *min_key_code* and *max_key_code* fields of the *xkb* parameter are used to allocate the *behaviors* field of the server map.
XkbVirtualModMapMask	The *min_key_code* and *max_key_code* fields of the *xkb* parameter are used to allocate the *vmodmap* field of the server map.

Note

The *min_key_code* and *max_key_code* fields of the *xkb* parameter must be legal values. If they are not valid, *XkbAllocServerMap* returns *BadValue* .

If the server map of the keyboard description is not *NULL* and any fields are already allocated in the server map, *XkbAllocServerMap* does not overwrite the existing values. The only exception is with the *acts* array. If the *count_acts* parameter is greater than the current *num_acts* field of the server map, *XkbAllocServerMap* resizes the *acts* array and resets the *num_acts* field accordingly.

If *XkbAllocServerMap* is successful, it returns *Success* . Otherwise, it can return either *BadMatch* or *BadAlloc* errors.

Freeing a Server Map

To free memory used by the server member of an *XkbDescRec* structure, use *XkbFreeServerMap.*

void *XkbFreeServerMap* (*xkb, which, free_all*)
XkbDescPtr *xkb* ; /* keyboard description containing server map to free */
unsigned int *which* ; /* mask identifying components of map to free */
Bool *free_all* ; /* *True* => free all server map components and server itself */

The *XkbFreeServerMap* function frees the specified components of server map in the *XkbDescRec* structure specified by the *xkb* parameter and sets the corresponding structure component values to *NULL* . The *which* parameter specifies a combination of the server map masks and is a bitwise inclusive OR of the masks listed in Table 14.4. If *free_all* is *True* , *which* is ignored and *XkbFreeServerMap* frees every non- *NULL* structure component in the server map, frees the *XkbServerMapRec* structure referenced by the *server* member of the *xkb* parameter, and sets the *server* member to *NULL.*

Chapter 15. Xkb Client Keyboard Mapping

The Xkb client map for a keyboard is the collection of information a client needs to interpret key events from the keyboard. It contains a global list of key types and an array of key symbol maps, each of which describes the symbols bound to a key and the rules to be used to interpret those symbols.

Figure 15.1 shows the relationships between elements in the client map:



Xkb Client Map

The XkbClientMapRec Structure

The *map* field of the complete Xkb keyboard description (see section 6.1) is a pointer to the Xkb client map, which is of type *XkbClientMapRec* :

```
typedef struct {                        /* Client Map */
      unsigned char      size_types;    /* # occupied entries in  types */
```

```
      unsigned char      num_types;     /* # entries in types */
      XkbKeyTypePtr      types;         /* vector of key types used by this keymap
      unsigned short     size_syms;     /* length of the syms array */
      unsigned short     num_syms;      /* # entries in syms */
      KeySym *           syms;          /* linear 2d tables of keysyms, 1 per key
      XkbSymMapPtr       key_sym_map;   /* 1 per keycode, maps keycode to syms */
      unsigned char *    modmap;        /* 1 per keycode, real mods bound to key *
} XkbClientMapRec, *XkbClientMapPtr;
```

The following sections describe each of the elements of the *XkbClientMapRec* structure in more detail.

Key Types

Key types are used to determine the shift level of a key given the current state of the keyboard. The set of all possible key types for the Xkb keyboard description are held in the *types* field of the client map, whose total size is stored in *size_types*, and whose total number of valid entries is stored in *num_types*. Key types are defined using the following structures:

```
typedef struct {                        /* Key Type */
      XkbModsRec        mods;           /* modifiers used to compute shift
                                           level */
      unsigned char     num_levels;     /* total # shift levels, do not
                                           modify directly */
      unsigned char     map_count;      /* # entries in map,
                                            preserve
                                           (if non- NULL) */
      XkbKTMapEntryPtr  map;            /* vector of modifiers for each
                                           shift level */
      XkbModsPtr        preserve;       /* mods to preserve for corresponding
                                           map entry */
      Atom              name;           /* name of key type */
      Atom *            level_names;    /* array of names of each shift level */
} XkbKeyTypeRec, *XkbKeyTypePtr;


typedef struct {                    /* Modifiers for a key type */
      Bool            active;       /*  True => entry
                                        active when determining shift level */
      unsigned char   level;        /* shift level if modifiers match  mods */
      XkbModsRec      mods;         /* mods needed for this level to be
                                        selected */
} XkbKTMapEntryRec,*XkbKTMapEntryPtr;
```

The *mods* field of a key type is an *XkbModsRec* (see section 7.2) specifying the modifiers the key type uses when calculating the shift level, and can be composed of both the core modifiers and virtual modifiers. To set the modifiers associated with a key type, modify the *real_mods* and *vmods* fields of the *mods* *XkbModsRec* accordingly. The *mask* field of the *XkbModsRec* is reserved for use by Xkb and is calculated from the *real_mods* and *vmods* fields.

The *num_levels* field holds the total number of shift levels for the key type. Xkb uses *num_levels* to ensure the array of symbols bound to a key is large enough. Do

not modify *num_levels* directly to change the number if shift levels for a key type. Instead, use *XkbResizeKeyType* (see section 15.2.3).

The *map* field is a vector of *XkbKTMapEntryRec* structures, with *map_count* entries, that specify the modifier combinations for each possible shift level. Each map entry contains an *active* field, a *mods* field, and a *level* field. The *active* field determines whether the modifier combination listed in the *mods* field should be considered when determining shift level. If *active* is *False* , this *map* entry is ignored. If *active* is *True* , the *level* field of the *map* entry specifies the shift level to use when the current modifier combination matches the combination specified in the *mods* field of the *map* entry.

Any combination of modifiers not explicitly listed somewhere in the *map* yields shift level one. In addition, *map* entries specifying unbound virtual modifiers are not considered.

Any modifiers specified in *mods* are normally *consumed* by *XkbTranslateKeyCode* (see section 12.1.3). For those rare occasions a modifier *should* be considered despite having been used to look up a symbol, key types include an optional *preserve* field. If a *preserve* member of a key type is not *NULL* , it represents a list of modifiers where each entry corresponds directly to one of the key type's *map* . Each entry lists the modifiers that should *not* be consumed if the matching map entry is used to determine shift level.

Each shift level has a name and these names are held in the *level_names* array, whose length is *num_levels* . The type itself also has a name, which is held in the *name* field.

For example, consider how the server handles the following possible symbolic description of a possible key type (note that the format used to specify keyboard mappings in the server database is not specified by the Xkb extension, although this format is one possible example):

Table 15.1. Example Key Type

Symbolic Description	Key Type Data Structure
type "ALPHATHREE" {	Xkb->map->types[i].name
modifiers = Shift+Lock+LevelThree;	Xkb->map->types[i].mods
map[None]= Level1;	Xkb->map->types[i].map[0]
map[Lock]= Level1;	Xkb->map->types[i].map[1]
map[Shift]= Level2;	Xkb->map->types[i].map[2]
map[LevelThree]= Level3;	Xkb->map->types[i].map[3]
map[Shift+LevelThree]= Level3;	Xkb->map->types[i].map[4]
preserve[None]= None;	Xkb->map->types[i].perserve[0]
preserve[Lock]= Lock;	Xkb->map->types[i].preserve[1]
preserve[Shift]= None;	Xkb->map->types[i].preserve[2]
preserve[LevelThree]= None;	Xkb->map->types[i].preserve[3]
preserve[Shift+Level3]= None;	Xkb->map->types[i].preserve[4]
level_name[Level1]= "Base";	Xkb->map->types[i].level_names[0]
level_name[Level2]= "Caps";	Xkb->map->types[i].level_names[1]
level_name[Level3]= "Level3";	Xkb->map->types[i].level_names[2]
};	

The *name* of the example key type is "ALPHATHREE," and the modifiers it pays attention to are *Shift* , *Lock* , and the virtual modifier *LevelThree* . There are three shift levels. The name of shift level one is "Base," the name of shift level two is "Caps," and the name of shift level three is "Level3."

Given the combination of the *map* and *preserve* specifications, there are five *map* entries. The first map entry specifies that shift level one is to be used if no modifiers are set. The second entry specifies the *Lock* modifier alone also yields shift level one. The third entry specifies the *Shift* modifier alone yields shift level two. The fourth and fifth entries specify that the virtual *LevelThree* modifier alone, or in combination with the *Shift* modifier, yields shift level three.

Note

Shift level three can be reached only if the virtual modifier *LevelThree* is bound to a real modifier (see section 16.4). If *LevelThree* is not bound to a real modifier, the *map* entries associated with it are ignored.

Because the *Lock* modifier is to be preserved for further event processing, the *preserve* list is not *NULL* and parallels the *map* list. All *preserve* entries, except for the one corresponding to the *map* entry that specifies the *Lock* modifier, do not list any modifiers. For the *map* entry that specifies the *Lock* modifier, the corresponding *preserve* list entry lists the *Lock* modifier, meaning do not consume the *Lock* modifier. In this particular case, the preserved modifier is passed to Xlib translation functions and causes them to notice that the *Lock* modifier is set; consequently, the Xlib functions apply the appropriate capitalization rules to the symbol. Because this preserve entry is set only for a modifier that yields shift level one, the capitalization occurs only for level-one symbols.

The Canonical Key Types

Xkb allows up to *XkbMaxKeyTypes* (255) key types to be defined, but requires at least *XkbNumRequiredTypes* (4) predefined types to be in a key map. These predefined key types are referred to as the canonical key types and describe the types of keys available on most keyboards. The definitions for the canonical key types are held in the first *XkbNumRequiredTypes* entries of the *types* field of the client map and are indexed using the following constants:

XkbOneLevelIndex
XkbTwoLevelIndex
XkbAlphabeticIndex
XkbKeypadIndex

ONE_LEVEL

The ONE_LEVEL key type describes groups that have only one symbol. The default ONE_LEVEL key type has no map entries and does not pay attention to any modifiers. A symbolic representation of this key type could look like the following:

```
type "ONE_LEVEL" {
    modifiers = None;
    map[None]= Level1;
    level_name[Level1]= "Any";
};
```

The description of the ONE_LEVEL key type is stored in the *types* [*XkbOneLevelIndex*] entry of the client key map.

TWO_LEVEL

The TWO_LEVEL key type describes groups that consist of two symbols but are neither alphabetic nor numeric keypad keys. The default TWO_LEVEL type uses only the *Shift* modifier. It returns shift level two if *Shift* is set, and level one if it is not. A symbolic representation of this key type could look like the following:

```
type "TWO_LEVEL" {
    modifiers = Shift;
    map[Shift]= Level2;
    level_name[Level1]= "Base";
    level_name[Level2]= "Shift";
};
```

The description of the TWO_LEVEL key type is stored in the *types* [*XkbTwoLevelIndex*] entry of the client key map.

ALPHABETIC

The ALPHABETIC key type describes groups consisting of two symbols: the lowercase form of a symbol followed by the uppercase form of the same symbol. The de-

fault ALPHABETIC type implements locale-sensitive "Shift cancels CapsLock" behavior using both the *Shift* and *Lock* modifiers as follows:

- If *Shift* and *Lock* are both set, the default ALPHABETIC type yields level one.
- If *Shift* alone is set, it yields level two.
- If *Lock* alone is set, it yields level one, but preserves the *Lock* modifier so Xlib notices and applies the appropriate capitalization rules. The Xlib functions are locale-sensitive and apply different capitalization rules for different locales.
- If neither *Shift* nor *Lock* is set, it yields level one.

A symbolic representation of this key type could look like the following:

```
type "ALPHABETIC" {
    modifiers = Shift+Lock;
    map[Shift]= Level2;
    preserve[Lock]= Lock;
    level_name[Level1]= "Base";
    level_name[Level2]= "Caps";
};
```

The description of the ALPHABETIC key type is stored in the *types* [*XkbAlphabeticIndex*] entry of the client key map.

KEYPAD

The KEYPAD key type describes groups that consist of two symbols, at least one of which is a numeric keypad symbol. The numeric keypad symbol is assumed to reside at level two. The default KEYPAD key type implements "Shift cancels NumLock" behavior using the Shift modifier and the real modifier bound to the virtual modifier named "NumLock," known as the *NumLock* modifier, as follows:

- If *Shift* and *NumLock* are both set, the default KEYPAD type yields level one.
- If *Shift* alone is set, it yields level two.
- If *NumLock* alone is set, it yields level two.
- If neither *Shift* nor *NumLock* is set, it yields level one.

A symbolic representation of this key type could look like the following:

```
type "KEYPAD" {
    modifiers = Shift+NumLock;
    map[None]= Level1;
    map[Shift]= Level2;
    map[NumLock]= Level2;
    map[Shift+NumLock]= Level1;
    level_name[Level1]= "Base";
    level_name[Level2]= "Caps";
};
```

The description of the KEYPAD key type is stored in the *types* [*XkbKeypadIndex*] entry of the client key map.

Initializing the Canonical Key Types in a New Client Map

To set the definitions of the canonical key types in a client map to their default values, use *XkbInitCanonicalKeyTypes*.

```
Status XkbInitCanonicalKeyTypes ( xkb, which, keypadVMod )
XkbDescPtr xkb ; /* keyboard description containing client map to initialize */
unsigned int which ; /* mask of types to initialize */
int keypadVMod ; /* index of NumLock virtual modifier */
```

XkbInitCanonicalKeyTypes initializes the first *XkbNumRequiredTypes* key types of the keyboard specified by the *xkb* parameter to their default values. The *which* parameter specifies what canonical key types to initialize and is a bitwise inclusive OR of the following masks: *XkbOneLevelMask* , *XkbTwoLevelMask* , *XkbAlphabeticMask* , and *XkbKeypadMask* . Only those canonical types specified by the *which* mask are initialized.

If *XkbKeypadMask* is set in the *which* parameter, *XkbInitCanonicalKeyTypes* looks up the *NumLock* named virtual modifier to determine which virtual modifier to use when initializing the KEYPAD key type. If the *NumLock* virtual modifier does not exist, *XkbInitCanonicalKeyTypes* creates it.

XkbInitCanonicalKeyTypes normally returns Success. It returns *BadAccess* if the Xkb extension has not been properly initialized, and *BadAccess* if the *xkb* parameter is not valid.

Getting Key Types from the Server

To obtain the list of available key types in the server's keyboard mapping, use *XkbGetKeyTypes* .

```
Status XkbGetKeyTypes ( dpy , first , num , xkb )
Display * dpy ; /* connection to X server */
unsigned int first ; /* index to first type to get, 0 => 1st type */
unsigned int num ; /* number of key types to be returned */
XkbDescPtr xkb ; /* keyboard description containing client map to update */
```

Note

XkbGetKeyTypes is used to obtain descriptions of the key types themselves, not the key types bound to individual keys. To obtain the key types bound to an individual key, refer to the *key_sym_map* field of the client map (see section 15.3.1).

XkbGetKeyTypes queries the server for the desired types, waits for a reply, and returns the desired types in the *xkb->map->types* . If successful, it returns Success.

XkbGetKeyTypes returns *BadAccess* if the Xkb extension has not been properly initialized and *BadValue* if the combination of *first* and *num* results in numbers out of valid range.

Changing the Number of Levels in a Key Type

To change the number of levels in a key type, use *XkbResizeKeyType* .

Status *XkbResizeKeyType* (*xkb* , *type_ndx* , *map_count* , *want_preserve* , *new_num_lvls*)
XkbDescPtr *xkb* ; /* keyboard description containing client map to update */
int *type_ndx* ; /* index in xkb->map->types of type to change */
int *map_count* ; /* total # of map entries needed for the type */
Bool *want_preserve* ; /* *True* => list of preserved modifiers is necessary */
int *new_num_lvls* ; /* new max # of levels for type */

XkbResizeKeyType changes the type specified by *xkb -> map->types* [*type_ndx*], and reallocates the symbols and actions bound to all keys that use the type, if necessary. *XkbResizeKeyType* updates only the local copy of the types in *xkb* ; to update the server's copy for the physical device, use *XkbSetMap* or *XkbChangeMap* after calling *XkbResizeKeyType* .

The *map_count* parameter specifies the total number of map entries needed for the type, and can be zero or greater. If *map_count* is zero, *XkbResizeKeyType* frees the existing *map* and *preserve* entries for the type if they exist and sets them to *NULL* .

The *want_preserve* parameter specifies whether a *preserve* list for the key should be created. If *want_preserve* is *True* , the *preserve* list with *map_count* entries is allocated or reallocated if it already exists. Otherwise, if *want_preserve* is *False* , the *preserve* field is freed if necessary and set to *NULL* .

The *new_num_lvls* parameter specifies the new maximum number of shift levels for the type and is used to calculate and resize the symbols and actions bound to all keys that use the type.

If *type_ndx* does not specify a legal type, *new_num_lvls* is less than 1, or the *map_count* is less than zero, *XkbResizeKeyType* returns *BadValue* . If *XkbResizeKeyType* encounters any problems with allocation, it returns *BadAlloc* . Otherwise, it returns *Success* .

Copying Key Types

Use *XkbCopyKeyType* and *XkbCopyKeyTypes* to copy one or more *XkbKeyTypeRec* structures.

Status *XkbCopyKeyType* (*from* , *into*)
XkbKeyTypePtr *from* ; /* pointer to XkbKeyTypeRec to be copied */
XkbKeyTypePtr *into* ; /* pointer to XkbKeyTypeRec to be changed */

XkbCopyKeyType copies the key type specified by *from* to the key type specified by *into* . Both must point to legal *XkbKeyTypeRec* structures. Xkb assumes *from* and

into point to different places. As a result, overlaps can be fatal. *XkbCopyKeyType* frees any existing *map* , *preserve* , and *level_names* in *into* prior to copying. If any allocation errors occur while copying *from* to *into* , *XkbCopyKeyType* returns *BadAlloc* . Otherwise, *XkbCopyKeyType* copies *from* to *into* and returns *Success* .

Status *XkbCopyKeyTypes* (*from* , *into* , *num_types*)

XkbKeyTypePtr *from* ; /* pointer to array of XkbKeyTypeRecs to copy */

XkbKeyTypePtr *into* ; /* pointer to array of XkbKeyTypeRecs to change */

int *num_types* ; /* number of types to copy */

XkbCopyKeyTypes copies *num_types* *XkbKeyTypeRec* structures from the array specified by *from* into the array specified by *into* . It is intended for copying between, rather than within, keyboard descriptions, so it doesn't check for overlaps. The same rules that apply to the *from* and *into* parameters in *XkbCopyKeyType* apply to each entry of the *from* and *into* arrays of *XkbCopyKeyTypes* . If any allocation errors occur while copying *from* to *into* , *XkbCopyKeyTypes* returns *BadAlloc* . Otherwise, *XkbCopyKeyTypes* copies *from* to *into* and returns *Success* .

Key Symbol Map

The entire list of key symbols for the keyboard mapping is held in the *syms* field of the client map. Whereas the core keyboard mapping is a two-dimensional array of *KeySyms* whose rows are indexed by keycode, the *syms* field of Xkb is a linear list of *KeySyms* that needs to be indexed uniquely for each key. This section describes the key symbol map and the methods for determining the symbols bound to a key.

The reason the *syms* field is a linear list of *KeySyms* is to reduce the memory consumption associated with a keymap; because Xkb allows individual keys to have multiple shift levels and a different number of groups per key, a single two-dimensional array of *KeySyms* would potentially be very large and sparse. Instead, Xkb provides a small two-dimensional array of *KeySyms* for each key. To store all of these individual arrays, Xkb concatenates each array together in the *syms* field of the client map.

In order to determine which *KeySyms* in the *syms* field are associated with each keycode, the client map contains an array of key symbol mappings, held in the *key_sym_map* field. The *key_sym_map* field is an array of *XkbSymMapRec* structures indexed by keycode. The *key_sym_map* array has *min_key_code* unused entries at the start to allow direct indexing using a keycode. All keycodes falling between the minimum and maximum legal keycodes, inclusive, have *key_sym_map* arrays, whether or not any key actually yields that code. The *KeySymMapRec* structure is defined as follows:

```
#define XkbNumKbdGroups           4
#define XkbMaxKbdGroup           (XkbNumKbdGroups-1)


typedef struct {                                  /* map to keysyms for a single
      unsigned char     kt_index[XkbNumKbdGroups]; /* key type index for each grou
      unsigned char     group_info;                /* # of groups and out of range
      unsigned char     width;                     /* max # of shift levels for ke
      unsigned short    offset;                    /* index to keysym table in  sy
```

```
} XkbSymMapRec, *XkbSymMapPtr;
```

These fields are described in detail in the following sections.

Per-Key Key Type Indices

The *kt_index* array of the *XkbSymMapRec* structure contains the indices of the key types (see section 15.2) for each possible group of symbols associated with the key. To obtain the index of a key type or the pointer to a key type, Xkb provides the following macros, to access the key types:

Note

The array of key types is of fixed width and is large enough to hold key types for the maximum legal number of groups (*XkbNumKbdGroups* , currently four); if a key has fewer than *XkbNumKbdGroups* groups, the extra key types are reported but ignored.

int *XkbKeyTypeIndex* (*xkb, keycode, group*) /* macro*/

XkbDescPtr *xkb* ; /* Xkb description of interest */

KeyCode *keycode* ; /* keycode of interest */

int *group* ; /* group index */

XkbKeyTypeIndex computes an index into the *types* vector of the client map in *xkb* from the given *keycode* and *group* index.

XkbKeyTypePtr *XkbKeyType* (*xkb, keycode, group*) /* macro */

XkbDescPtr *xkb* ; /* Xkb description of interest */

KeyCode *keycode* ; /* keycode of interest */

int *group* ; /* group index */

XkbKeyType returns a pointer to the key type in the *types* vector of the client map in *xkb* corresponding to the given *keycode* and *group* index.

Per-Key Group Information

The *group_info* field of an *XkbSymMapRec* is an encoded value containing the number of groups of symbols bound to the key as well as the specification of the treatment of out-of-range groups. It is legal for a key to have zero groups, in which case it also has zero symbols and all events from that key yield *NoSymbol* . To obtain the number of groups of symbols bound to the key, use *XkbKeyNumGroups* . To change the number of groups bound to a key, use *XkbChangeTypesOfKey* (see section 15.3.6). To obtain a mask that determines the treatment of out-of-range groups, use *XkbKeyGroupInfo* and *XkbOutOfRangeGroupInfo* .

The keyboard controls (see Chapter 10) contain a *groups_wrap* field specifying the handling of illegal groups on a global basis. That is, when the user performs an action causing the effective group to go out of the legal range, the *groups_wrap* field specifies how to normalize the effective keyboard group to a group that is legal for the keyboard as a whole, but there is no guarantee that the normalized group will be within the range of legal groups for any individual key. The per-key *group_info*

field specifies how a key treats a legal effective group if the key does not have a type specified for the group of concern. For example, the *Enter* key usually has just one group defined. If the user performs an action causing the global keyboard group to change to *Group2* , the *group_info* field for the *Enter* key describes how to handle this situation.

Out-of-range groups for individual keys are mapped to a legal group using the same options as are used for the overall keyboard group. The particular type of mapping used is controlled by the bits set in the *group_info* flag, as shown in Table 15.2. See section 10.7.1 for more details on the normalization methods in this table.

Table 15.2. group_info Range Normalization

Bits set in group_info	Normalization method
XkbRedirectIntoRange	XkbRedirectIntoRange
XkbClampIntoRange	XkbClampIntoRange
none of the above	XkbWrapIntoRange

Xkb provides the following macros to access group information:

int *XkbKeyNumGroups* (*xkb, keycode*) /* macro */
XkbDescPtr *xkb* ; /* Xkb description of interest */
KeyCode *keycode* ; /* keycode of interest */

XkbKeyNumGroups returns the number of groups of symbols bound to the key corresponding to *keycode* .

unsigned char *XkbKeyGroupInfo* (*xkb, keycode*) /*macro */
XkbDescPtr *xkb* ; /* Xkb description of interest */
KeyCode *keycode* ; /* keycode of interest */

XkbKeyGroupInfo returns the *group_info* field from the *XkbSymMapRec* structure associated with the key corresponding to *keycode* .

unsigned char *XkbOutOfRangeGroupInfo* (*grp_inf*) /* macro */
unsigned char *grp_inf* ; /* group_info field of *XkbSymMapRec* */

XkbOutOfRangeGroupInfo returns only the out-of-range processing information from the *group_info* field of an *XkbSymMapRec* structure.

unsigned char *XkbOutOfRangeGroupNumber* (*grp_inf*) /* macro */
unsigned char *grp_inf* ; /* group_info field of *XkbSymMapRec* */

XkbOutOfRangeGroupNumber returns the out-of-range group number, represented as a group index, from the *group_info* field of an *XkbSymMapRec* structure.

Key Width

The maximum number of shift levels for a type is also referred to as the width of a key type. The *width* field of the *key_sym_map* entry for a key contains the width

of the widest type associated with the key. The *width* field cannot be explicitly changed; it is updated automatically whenever the symbols or set of types bound to a key are changed.

Offset in to the Symbol Map

The key width and number of groups associated with a key are used to form a small two-dimensional array of *KeySyms* for a key. This array may be different sizes for different keys. The array for a single key is stored as a linear list, in row-major order. The arrays for all of the keys are stored in the *syms* field of the client map. There is one row for each group associated with a key and one column for each level. The index corresponding to a given group and shift level is computed as:

```
idx = group_index * key_width + shift_level
```

The *offset* field of the *key_sym_map* entry for a key is used to access the beginning of the array.

Xkb provides the following macros for accessing the *width* and *offset* for individual keys, as well as macros for accessing the two-dimensional array of symbols bound to the key:

```
int XkbKeyGroupsWidth ( xkb, keycode ) /* macro */
XkbDescPtr xkb ; /* Xkb description of interest */
KeyCode keycode ; /* keycode of interest */
```

XkbKeyGroupsWidth computes the maximum width associated with the key corresponding to *keycode* .

```
int XkbKeyGroupWidth ( xkb, keycode, grp ) /* macro */
XkbDescPtr xkb ; /* Xkb description of interest */
KeyCode keycode ; /* keycode of interest */
int grp ; /* group of interest */
```

XkbKeyGroupWidth computes the width of the type associated with the group *grp* for the key corresponding to *keycode* .

```
int XkbKeySymsOffset ( xkb, keycode ) /* macro */
XkbDescPtr xkb ; /* Xkb description of interest */
KeyCode keycode ; /* keycode of interest */
```

XkbKeySymsOffset returns the offset of the two-dimensional array of keysyms for the key corresponding to *keycode* .

```
int XkbKeyNumSyms ( xkb, keycode ) /* macro */
XkbDescPtr xkb ; /* Xkb description of interest */
KeyCode keycode ; /* keycode of interest */
```

XkbKeyNumSyms returns the total number of keysyms for the key corresponding to *keycode* .

KeySym * *XkbKeySymsPtr* (*xkb, keycode*) /* macro */
XkbDescPtr *xkb* ; /* Xkb description of interest */
KeyCode *keycode* ; /* keycode of interest */

XkbKeySymsPtr returns the pointer to the two-dimensional array of keysyms for the key corresponding to *keycode* .

KeySym *XkbKeySymEntry* (*xkb, keycode, shift, grp*) /* macro */
XkbDescPtr *xkb* ; /* Xkb description of interest */
KeyCode *keycode* ; /* keycode of interest */
int *shift* ; /* shift level of interest */
int *grp* ; /* group of interest */

XkbKeySymEntry returns the *keysym* corresponding to shift level *shift* and group *grp* from the two-dimensional array of keysyms for the key corresponding to *keycode*

Getting the Symbol Map for Keys from the Server

To obtain the symbols for a subset of the keys in a keyboard description, use *XkbGetKeySyms* :

Status *XkbGetKeySyms* (*dpy* , *first* , *num* , *xkb*)
Display * *dpy* ; /* connection to X server */
unsigned int *first* ; /* keycode of first key to get */
unsigned int *num* ; /* number of keycodes for which syms desired */
XkbDescPtr *xkb* ; /* Xkb description to be updated */

XkbGetKeySyms sends a request to the server to obtain the set of keysyms bound to *num* keys starting with the key whose keycode is *first* . It waits for a reply and returns the keysyms in the *map.syms* field of *xkb* . If successful, *XkbGetKeySyms* returns *Success* . The *xkb* parameter must be a pointer to a valid Xkb keyboard description.

If the client *map* in the *xkb* parameter has not been allocated, *XkbGetKeySyms* allocates and initializes it before obtaining the symbols.

If a compatible version of Xkb is not available in the server or the Xkb extension has not been properly initialized, *XkbGetKeySyms* returns *BadAccess* . If *num* is less than 1 or greater than *XkbMaxKeyCount* , *XkbGetKeySyms* returns *BadValue* . If any allocation errors occur, *XkbGetKeySyms* returns *BadAlloc* .

Changing the Number of Groups and Types Bound to a Key

To change the number of groups and the types bound to a key, use *XkbChangeTypesOfKey* .

Status *XkbChangeTypesOfKey* (*xkb* , *key* , *n_groups* , *groups* , *new_types_in* , *p_changes*)

XkbDescPtr *xkb* ; /* keyboard description to be changed */
int *key* ; /* keycode for key of interest */
int *n_groups* ; /* new number of groups for key */
unsigned int *groups* ; /* mask indicating groups to change */
int * *new_types_in* ; /* indices for new groups specified in *groups* */
XkbMapChangesPtr *p_changes* ; /* notes changes made to *xkb* */

XkbChangeTypesOfKey reallocates the symbols and actions bound to the key, if necessary, and initializes any new symbols or actions to *NoSymbol* or *NoAction* , as appropriate. If the *p_changes* parameter is not *NULL* , *XkbChangeTypesOfKey* adds the *XkbKeySymsMask* to the *changes* field of *p_changes* and modifies the *first_key_sym* and *num_key_syms* fields of *p_changes* to include the *key* that was changed. See section 14.3.1 for more information on the *XkbMapChangesPtr* structure. If successful, *XkbChangeTypesOfKey* returns *Success* .

The *n_groups* parameter specifies the new number of groups for the key. The *groups* parameter is a mask specifying the groups for which new types are supplied and is a bitwise inclusive OR of the following masks: *XkbGroup1Mask* , *XkbGroup2Mask* , *XkbGroup3Mask* , and *XkbGroup4Mask* .

The *new_types_in* parameter is an integer array of length *n_groups* . Each entry represents the type to use for the associated group and is an index into *xkb -> map->types* . The *new_types_in* array is indexed by group index; if *n_groups* is four and *groups* only has *Group1Mask* and *Group3Mask* set, *new_types_in* looks like this:

```
new_types_in[0] = type for Group1
new_types_in[1] = ignored
new_types_in[2] = type for Group3
new_types_in[3] = ignored
```

For convenience, Xkb provides the following constants to use as indices to the groups:

Table 15.3. Group Index Constants

Constant Name	Value
XkbGroup1Index	0
XkbGroup2Index	1
XkbGroup3Index	2
XkbGroup4Index	3

If the Xkb extension has not been properly initialized, *XkbChangeTypesOfKey* returns *BadAccess* . If the *xkb* parameter it not valid (that is, it is *NULL* or it does not contain a valid client map), *XkbChangeTypesOfKey* returns *Bad* Match. If the *key* is not a valid keycode, *n_groups* is greater than *XkbNumKbdGroups* , or the *groups* mask does not contain any of the valid group mask bits, *XkbChangeType-*

sOfKey returns *BadValue* . If it is necessary to resize the key symbols or key actions arrays and any allocation errors occur, *XkbChangeTypesOfKey* returns *BadAlloc* .

Changing the Number of Symbols Bound to a Key

To change the number of symbols bound to a key, use *XkbResizeKeySyms* .

KeySym * *XkbResizeKeySyms* (*xkb* , *key* , *needed*)
XkbDescRec * *xkb* ; /* keyboard description to be changed */
int *key* ; /* keycode for key to modify */
int *needed* ; /* new number of keysyms required for key */

XkbResizeKeySyms reserves the space needed for *needed* keysyms and returns a pointer to the beginning of the new array that holds the keysyms. It adjusts the *offset* field of the *key_sym_map* entry for the key if necessary and can also change the *syms* , *num_syms* , and *size_syms* fields of *xkb - >map* if it is necessary to reallocate the *syms* array. *XkbResizeKeySyms* does not modify either the width or number of groups associated with the key.

If *needed* is greater than the current number of keysyms for the key, *XkbResizeKeySyms* initializes all new keysyms in the array to *NoSymbol* .

Because the number of symbols needed by a key is normally computed as width * number of groups, and *XkbResizeKeySyms* does not modify either the width or number of groups for the key, a discrepancy exists upon return from *XkbResizeKeySyms* between the space allocated for the keysyms and the number required. The unused entries in the list of symbols returned by *XkbResizeKeySyms* are not preserved across future calls to any of the map editing functions, so you must update the key symbol mapping (which updates the width and number of groups for the key) before calling another allocator function. A call to *XkbChangeTypesOfKey* will update the mapping.

If any allocation errors occur while resizing the number of symbols bound to the key, *XkbResizeKeySyms* returns *NULL* .

Note

A change to the number of symbols bound to a key should be accompanied by a change in the number of actions bound to a key. Refer to section 16.1.16 for more information on changing the number of actions bound to a key.

The Per-Key Modifier Map

The *modmap* entry of the client map is an array, indexed by keycode, specifying the real modifiers bound to a key. Each entry is a mask composed of a bitwise inclusive OR of the legal real modifiers: *ShiftMask* , *LockMask* , *ControlMask* , *Mod1Mask* , *Mod2Mask* , *Mod3Mask* , *Mod4Mask* , and *Mod5Mask* . If a bit is set in a *modmap* entry, the corresponding key is bound to that modifier.

Pressing or releasing the key bound to a modifier changes the modifier set and unset state. The particular manner in which the modifier set and unset state changes is determined by the behavior and actions assigned to the key (see Chapter 16).

Getting the Per-Key Modifier Map from the Server

To update the modifier map for one or more of the keys in a keyboard description, use *XkbGetKeyModifierMap* .

```
Status XkbGetKeyModifierMap ( dpy , first , num , xkb )
Display * dpy ; /* connection to X server */
unsigned int first ; /* keycode of first key to get */
unsigned int num ; /* number of keys for which information is desired */
XkbDescPtr xkb ; /* keyboard description to update */
```

XkbGetKeyModifierMap sends a request to the server for the modifier mappings for *num* keys starting with the key whose keycode is *first* . It waits for a reply and places the results in the *xkb* ->map->modmap array. If successful, *XkbGetKeyModifier* returns *Success* .

If the map component of the *xkb* parameter has not been allocated, *XkbGetKeyModifierMap* allocates and initializes it.

If a compatible version of Xkb is not available in the server or the Xkb extension has not been properly initialized, *XkbGetKeySyms* returns *BadAccess* . If any allocation errors occur while obtaining the modifier map, *XkbGetKeyModifierMap* returns *BadAlloc* .

Chapter 16. Xkb Server Keyboard Mapping

The *server* field of the complete Xkb keyboard description (see section 6.1) is a pointer to the Xkb server map.

Figure 16.1 shows the relationships between elements in the server map:



Server Map Relationships

The Xkb server map contains the information the server needs to interpret key events and is of type *XkbServerMapRec* :

```
#define XkbNumVirtualMods           16

typedef struct {                        /* Server Map */
      unsigned short     num_acts;      /* # of occupied entries in  acts */
      unsigned short     size_acts;     /* # of entries in  acts */
      XkbAction *        acts;          /* linear 2d tables of key actions, 1 per
```

```
    XkbBehavior *      behaviors;      /* key behaviors,1 per keycode */
    unsigned short *   key_acts;       /* index into  acts , 1 per keycode */
    unsigned char *    explicit;       /* explicit overrides of core remapping,
    unsigned char      vmods[XkbNumVirtualMods];  /* real mods bound to virtual
    unsigned short *   vmodmap;        /* virtual mods bound to key, 1 per keyco
} XkbServerMapRec, *XkbServerMapPtr;
```

The *num_acts* , *size_acts* , *acts* , and *key_acts* fields specify the key actions, defined in section 16.1. The *behaviors* field describes the behavior for each key and is defined in section 16.2. The *explicit* field describes the explicit components for a key and is defined in section 16.3. The *vmods* and the *vmodmap* fields describe the virtual modifiers and the per-key virtual modifier mapping and are defined in section 16.4.

Key Actions

A key action defines the effect key presses and releases have on the internal state of the server. For example, the expected key action associated with pressing the *Shift* key is to set the *Shift* modifier. There is zero or one key action associated with each keysym bound to each key.

Just as the entire list of key symbols for the keyboard mapping is held in the *syms* field of the client map, the entire list of key actions for the keyboard mapping is held in the *acts* array of the server map. The total size of *acts* is specified by *size_acts* , and the number of entries is specified by *num_acts*.

The *key_acts* array, indexed by keycode, describes the actions associated with a key. The *key_acts* array has *min_key_code* unused entries at the start to allow direct indexing using a keycode. If a *key_acts* entry is *zero* , it means the key does not have any actions associated with it. If an entry is not *zero* , the entry represents an index into the *acts* field of the server map, much as the *offset* field of a *KeySymMapRec* structure is an index into the *syms* field of the client map.

The reason the *acts* field is a linear list of *XkbAction* s is to reduce the memory consumption associated with a keymap. Because Xkb allows individual keys to have multiple shift levels and a different number of groups per key, a single two-dimensional array of *KeySyms* would potentially be very large and sparse. Instead, Xkb provides a small two-dimensional array of *XkbAction* s for each key. To store all of these individual arrays, Xkb concatenates each array together in the *acts* field of the server map.

The key action structures consist only of fields of type char or unsigned char. This is done to optimize data transfer when the server sends bytes over the wire. If the fields are anything but bytes, the server has to sift through all of the actions and swap any nonbyte fields. Because they consist of nothing but bytes, it can just copy them out.

Xkb provides the following macros, to simplify accessing information pertaining to key actions:

Bool *XkbKeyHasActions* (*xkb, keycode*) /* macro */

XkbDescPtr *xkb* ; /* Xkb description of interest */

KeyCode *keycode* ; /* keycode of interest */

XkbKeyHasActions returns *True* if the key corresponding to *keycode* has any actions associated with it; otherwise, it returns *False* .

int *XkbKeyNumActions* (*xkb, keycode*) /* macro */
XkbDescPtr *xkb* ; /* Xkb description of interest */
KeyCode *keycode* ; /* keycode of interest */

XkbKeyNumActions computes the number of actions associated with the key corresponding to *keycode* . This should be the same value as the result of *XkbKeyNumSyms* (see section 15.3.3).

XkbKeyActionPtr *XkbKeyActionsPtr* (*xkb, keycode*) /* macro */
XkbDescPtr *xkb* ; /* Xkb description of interest */
KeyCode *keycode* ; /* keycode of interest */

XkbKeyActionsPtr returns a pointer to the two-dimensional array of key actions associated with the key corresponding to *keycode* . Use *XkbKeyActionsPtr* only if the key actually has some actions associated with it, that is, *XkbKeyNumActions* (xkb, keycode) returns something greater than zero.

XkbAction *XkbKeyAction* (*xkb, keycode, idx*) /* macro */
XkbDescPtr *xkb* ; /* Xkb description of interest */
KeyCode *keycode* ; /* keycode of interest */
int *idx* ; /* index for group and shift level */

XkbKeyAction returns the key action indexed by *idx* in the two-dimensional array of key actions associated with the key corresponding to *keycode* . *idx* may be computed from the group and shift level of interest as follows:

```
idx = group_index * key_width + shift_level
```

XkbAction *XkbKeyActionEntry* (*xkb, keycode, shift, grp*) /* macro */
XkbDescPtr *xkb* ; /* Xkb description of interest */
KeyCode *keycode* ; /* keycode of interest */
int *shift* ; /* shift level within group */
int *grp* ; /* group index for group of interest */

XkbKeyActionEntry returns the key action corresponding to group *grp* and shift level *lvl* from the two-dimensional table of key actions associated with the key corresponding to *keycode* .

The XkbAction Structure

The description for an action is held in an *XkbAction* structure, which is a union of all possible Xkb action types:

```
typedef union _XkbAction {
      XkbAnyAction              any;
      XkbModAction              mods;
      XkbGroupAction            group;
      XkbISOAction              iso;
      XkbPtrAction              ptr;
      XkbPtrBtnAction           btn;
      XkbPtrDfltAction          dflt;
      XkbSwitchScreenAction     screen;
      XkbCtrlsAction            ctrls;
      XkbMessageAction          msg;
      XkbRedirectKeyAction      redirect;
      XkbDeviceBtnAction        devbtn;
      XkbDeviceValuatorAction   devval;
      unsigned char             type;
} XkbAction;
```

The *type* field is provided for convenience and is the same as the type field in the individual structures. The following sections describe the individual structures for each action in detail.

The XkbAnyAction Structure

The *XkbAnyAction* structure is a convenience structure that refers to any of the actions:

```
#define      XkbAnyActionDataSize       7


typedef struct _XkbAnyAction {
   unsigned char    type;            /* type of action; determines interpretation
   unsigned char    data[XkbAnyActionDataSize];
} XkbAnyAction;
```

The *data* field represents a structure for an action, and its interpretation depends on the *type* field. The valid values for the *type* field, and the data structures associated with them are shown in Table 16.1:

Table 16.1. Action Types

Type	Structure for Data	XkbAction Union Member	Section
XkbSA_NoAction	*XkbSA_NoAction* means the server does not perform an action for the key; this action does not have an associated data structure.	any	
XkbSA_SetMods	*XkbModAction*	mods	16.1.3
XkbSA_LatchMods			
XkbSA_LockMods			
XkbSA_SetGroup	*XkbGroupAction*	group	16.1.4
XkbSA_LatchGroup			
XkbSA_LockGroup			
XkbSA_MovePtr	*XkbPtrAction*	ptr	16.1.5
XKbSA_PtrBtn	*XkbPtrBtnAction*	btn	16.1.6
XkbSA_LockPtrBtn			
XkbSA_SetPtrDflt	*XkbPtrDfltAction*	dflt	16.1.7
XkbSA_ISOLock	*XkbISOAction*	iso	16.1.8
XkbSA_SwitchScreen	*XkbSwitchScreenAction*	screen	16.1.9
XkbSA_SetControls	*XkbCtrlsAction*	ctrls	16.1.10
XkbSA_LockControls			
XkbSA_ActionMessage	*XkbMessgeAction*	msg	16.1.11
XkbSA_RedirectKey	*XkbRedirectKeyAction*	redirect	16.1.12
XkbSA_DeviceBtn	*XkbDeviceBtnAction*	devbtn	16.1.13
XKbSA_LockDeviceBtn			
XkbSA_DeviceValuator	*XkbDeviceValuatorAction*	devval	16.1.14

Actions for Changing Modifiers' State

Actions associated with the *XkbModAction* structure change the state of the modifiers when keys are pressed and released (see Chapter 7 for a discussion of modifiers):

```
typedef struct _XkbModAction {
      unsigned char     type;         /*  XkbSA_{Set|Latch|Lock}Mods */
      unsigned char     flags;        /* with  type , controls the effect on modif
      unsigned char     mask;         /* same as  mask field of a modifier descrip
      unsigned char     real_mods;    /* same as  real_mods field of a modifier de
      unsigned char     vmods1;       /* derived from  vmods field of a modifier d
      unsigned char     vmods2;       /* derived from  vmods field of a modifier d
```

```
} XkbModAction;
```

In the following description, the term *action modifiers* means the real modifier bits associated with this action. Depending on the value of *flags* (see Table 16.3), these are designated either in the *mask* field of the *XkbModAction* structure itself or the real modifiers bound to the key for which the action is being used. In the latter case, this is the client *map -> modmap* [*keycode*] field.

The *type* field can have any of the values shown in Table 16.2.

Table 16.2. Modifier Action Types

Type	Effect
XkbSA_SetMods	• A key press adds any action modifiers to the keyboard's base modifiers. • A key release clears any action modifiers in the keyboard's base modifiers, provided no other key affecting the same modifiers is logically down. • If no other keys are physically depressed when this key is released, and *XkbSA_ClearLocks* is set in the *flags* field, the key release unlocks any action modifiers.
XkbSA_LatchMods	• Key press and key release events have the same effect as for *XkbSA_SetMods* ; if no keys are physically depressed when this key is released, key release events have the following additional effects: • Modifiers unlocked due to *XkbSA_ClearLocks* have no further effect. • If *XkbSA_LatchToLock* is set in the *flags* field, a key release locks and then unlatches any remaining action modifiers that are already latched. • A key release latches any action modifiers not used by the *XkbSA_ClearLocks* and *XkbSA_LatchToLock* flags.
XkbSA_LockMods	• A key press sets the base state of any action modifiers. If *XkbSA_LockNoLock* is set in the *flags* field, a key press also sets the locked state of any action modifiers. • A key release clears any action modifiers in the keyboard's base modifiers, provided no other key that affects the same modifiers is down. If *XkbSA_LockNoUnlock* is not set in the *flags* field, and any of the action modifiers were locked before the corresponding key press occurred, a key release unlocks them.

The *flags* field is composed of the bitwise inclusive OR of the masks shown in Table 16.3. A general meaning is given in the table, but the exact meaning depends on the action *type*.

Table 16.3. Modifier Action Flags

Flag	Meaning
XkbSA_UseModMapMods	If set, the action modifiers are determined by the modifiers bound by the modifier mapping of the key. Otherwise, the action modifiers are set to the modifiers specified by the *mask* , *real_mods* , *vmod1* , and *vmod2* fields.
XkbSA_ClearLocks	If set and no keys are physically depressed when this key transition occurs, the server unlocks any action modifiers.
XkbSA_LatchToLock	If set, and the action type is *XkbSA_LatchMods* , the server locks the action modifiers if they are already latched.
XkbSA_LockNoLock	If set, and the action type is *XkbSA_LockMods* , the server only unlocks the action modifiers.
XkbSA_LockNoUnlock	If set, and the action is *XkbSA_LockMods* , the server only locks the action modifiers.

If *XkbSA_UseModMapMods* is not set in the *flags* field, the *mask* , *real_mods* , *vmods1* , and *vmods2* fields are used to determine the action modifiers. Otherwise they are ignored and the modifiers bound to the key (client *map* -> *modmap* [*keycode*]) are used instead.

The *mask* , *real_mods* , *vmods1* , and *vmods2* fields represent the components of an Xkb modifier description (see section 7.2). While the *mask* and *real_mods* fields correspond directly to the *mask* and *real_mods* fields of an Xkb modifier description, the *vmods1* and *vmods2* fields are combined to correspond to the *vmods* field of an Xkb modifier description. Xkb provides the following macros, to convert between the two formats:

unsigned short *XkbModActionVMods* (*act*) /* macro */
XkbAction *act* ; /* action from which to extract virtual mods */

XkbModActionVMods returns the *vmods1* and *vmods2* fields of *act* converted to the *vmods* format of an Xkb modifier description.

void *XkbSetModActionVMods* (*act, vmods*) /* macro */
XkbAction *act* ; /* action in which to set vmods */
unsigned short *vmods* ; /* virtual mods to set */

XkbSetModActionVMods sets the *vmods1* and *vmods2* fields of *act* using the *vmods* format of an Xkb modifier description.

Note

Despite the fact that the first parameter of these two macros is of type XkbAction, these macros may be used only with Actions of type *XkbModAction* and *XkbISOAction* .

Actions for Changing Group State

Actions associated with the *XkbGroupAction* structure change the current group state when keys are pressed and released (see Chapter 5 for a description of groups and keyboard state):

```
typedef struct _XkbGroupAction {
      unsigned char   type;       /*  XkbSA_{Set|Latch|Lock}Group */
      unsigned char   flags;      /* with  type , controls the effect on groups */
      char            group_XXX;  /* represents a group index or delta */
} XkbGroupAction;
```

The *type* field can have any of the following values:

Table 16.4. Group Action Types

Type	Effect
XkbSA_SetGroup	• If the *XkbSA_GroupAbsolute* bit is set in the *flags* field, key press events change the base keyboard group to the group specified by the *group_XXX* field. Otherwise, key press events change the base keyboard group by adding the *group_XXX* field to the base keyboard group. In either case, the resulting effective keyboard group is brought back into range depending on the value of the *groups_wrap* field of the controls structure (see section 10.7.1). • If a key with an *XkbSA_ISOLock* action (see section 16.1.8) is pressed while this key is down, the key release of this key has no effect. Otherwise, the key release cancels the effects of the key press. • If the *XkbSA_ClearLocks* bit is set in the flags field, and no keys are physically depressed when this key is released, the key release also sets the locked keyboard group to *Group1* .
XkbSA_LatchGroup	• Key press and key release events have the same effect as for *XkbSA_SetGroup* ; if no keys are physically depressed when this key is released, key release events have the following additional effects. • If the *XkbSA_LatchToLock* bit is set in the *flags* field and the latched keyboard group index is nonzero, the key release adds the delta applied by the corresponding key press to the locked keyboard group and subtracts it from the latched keyboard group. The locked and effective keyboard group are brought back into range according to the value of the *groups_wrap* field of the controls structure. • Otherwise, the key press adds the key press delta to the latched keyboard group.
XkbSA_LockGroup	• If the *XkbSA_GroupAbsolute* is set in the *flags* field, key press events set the locked keyboard group to the group specified by the *group_XXX* field. Otherwise, key press events add the group specified by the *group_XXX* field to the locked keyboard group. In either case, the resulting locked and effective keyboard groups are brought back into range depending on the value of the *groups_wrap* field of the controls structure. • A key release has no effect.

The *flags* field is composed of the bitwise inclusive OR of the masks shown in Table 16.5. A general meaning is given in the table, but the exact meaning depends on the action *type* .

Table 16.5. Group Action Flags

Flag	Meaning
XkbSA_ClearLocks	If set and no keys are physically depressed when this key transition occurs, the server sets the locked keyboard group to *Group1* on a key release.
XkbSA_LatchToLock	If set, and the action type is *SA_LatchGroup* , the server locks the action group if it is already latched.
XkbSA_GroupAbsolute	If set, the *group_XXX* field represents an absolute group number. Otherwise, it represents a group delta to be added to the current group to determine the new group number.

The *group_XXX* field represents a signed character. Xkb provides the following macros to convert between a signed integer value and a signed character:

int *XkbSAGroup* (*act*) /* macro */
XkbAction *act* ; /* action from which to extract group */

XkbSAGroup returns the *group_XXX* field of *act* converted to a signed int.

void *XkbSASetGroup* (*act, grp*) /* macro */
XkbAction *act* ; /* action from which to set group */
int *grp* ; /* group index to set in *group_XXX* */

XkbSASetGroup sets the *group_XXX* field of *act* from the group index *grp* .

Note

Despite the fact that the first parameter of these two macros is of type XkbAction, these macros may only be used with Actions of type *XkbGroupAction* and *XkbISOAction* .

Actions for Moving the Pointer

Actions associated with the *XkbPtrAction* structure move the pointer when keys are pressed and released:

```
typedef struct _XkbPtrAction {
      unsigned char      type;      /*  XkbSA_MovePtr */
      unsigned char      flags;     /* determines type of pointer motion */
      unsigned char      high_XXX;  /* x coordinate, high bits*/
      unsigned char      low_XXX;   /* y coordinate, low bits */
      unsigned char      high_YYY;  /* x coordinate, high bits */
      unsigned char      low_YYY;   /* y coordinate, low bits */
} XkbPtrAction;
```

If the *MouseKeys* control is not enabled (see section 10.5.1), *KeyPress* and *KeyRelease* events are treated as though the action is *XkbSA_NoAction*.

If the *MouseKeys* control is enabled, a server action of type *XkbSA_MovePtr* instructs the server to generate core pointer *MotionNotify* events rather than the usual *KeyPress* event, and the corresponding *KeyRelease* event disables any mouse keys timers that were created as a result of handling the *XkbSA_MovePtr* action.

The *type* field of the *XkbPtrAction* structure is always *XkbSA_MovePtr* .

The *flags* field is a bitwise inclusive OR of the masks shown in Table 16.6.

Table 16.6. Pointer Action Types

Action Type	Meaning
XkbSA_NoAcceleration	If not set, and the *MouseKeysAccel* control is enabled (see section 10.5.2), the *KeyPress* initiates a mouse keys timer for this key; every time the timer expires, the cursor moves.
XkbSA_MoveAbsoluteX	If set, the X portion of the structure specifies the new pointer X coordinate. Otherwise, the X portion is added to the current pointer X coordinate to determine the new pointer X coordinate.
XkbSA_MoveAbsoluteY	If set, the Y portion of the structure specifies the new pointer Y coordinate. Otherwise, the Y portion is added to the current pointer Y coordinate to determine the new pointer Y coordinate.

Each of the X and Y coordinantes of the *XkbPtrAction* structure is composed of two signed 16-bit values, that is, the X coordinate is composed of *high_XXX* and *low_XXX* , and similarly for the Y coordinate. Xkb provides the following macros, to convert between a signed integer and two signed 16-bit values in *XkbPtrAction* structures:

int *XkbPtrActionX* (*act*) /* macro */
XkbPtrAction *act* ; /* action from which to extract X */

XkbPtrActionX returns the *high_XXX* and *low_XXX* fields of *act* converted to a signed int.

int *XkbPtrActionY* (*act*) /* macro */
XkbPtrAction *act* ; /* action from which to extract Y */

XkbPtrActionY returns the *high_YYY* and *low_YYY* fields of *act* converted to a signed int.

void *XkbSetPtrActionX* (*act* , *x*) /* macro */
XkbPtrAction *act* ; /* action in which to set X */
int *x;* /* new value to set */

XkbSetPtrActionX sets the *high_XXX* and *low_XXX* fields of *act* from the signed integer value *x* .

void *XkbSetPtrActionY* (*act, y*) /* macro */
XkbPtrAction *act* ; /* action in which to set Y */
int *y* ; /* new value to set */

XkbSetPtrActionX sets the *high_YYY* and *low_YYY* fields of *act* from the signed integer value *y* .

Actions for Simulating Pointer Button Press and Release

Actions associated with the *XkbPtrBtnAction* structure simulate the press and release of pointer buttons when keys are pressed and released:

```
typedef struct _XkbPtrBtnAction {
      unsigned char   type;     /* XkbSA_PtrBtn, XkbSA_LockPtrBtn */
      unsigned char   flags;    /* with  type , controls the effect on pointer but
      unsigned char   count;    /* controls number of ButtonPress and ButtonReleas
      unsigned char   button;   /* pointer button to simulate */
} XkbPtrBtnAction;
```

If the *MouseKeys* (see section 10.5.1) control is not enabled, *KeyPress* and *KeyRelease* events are treated as though the action is *XkbSA_NoAction* .

The *type* field can have any one of the values shown in Table 16.7.

Table 16.7. Pointer Button Action Types

Type	Effect
XkbSA_PtrBtn	• If *XkbSA_UseDfltButton* is set in the *flags* field, the event is generated for the pointer button specified by the *mk_dflt_btn* attribute of the *MouseKeys* control (see section 10.5.1). Otherwise, the event is generated for the button specified by the *button* field. • If the mouse button specified for this action is logically down, the key press and corresponding key release are ignored and have no effect. Otherwise, a key press causes one or more core pointer button events instead of the usual *KeyPress* event. If *count* is *zero* , a key press generates a single *ButtonPress* event; if *count* is greater than *zero* , a key press generates *count* pairs of *ButtonPress* and *ButtonRelease* events. • If *count* is *zero* , a key release generates a core pointer *ButtonRelease* that matches the event generated by the corresponding *KeyPress* ; if *count* is nonzero, a key release does not cause a *ButtonRelease* event. A key release never generates a key *KeyRelease* event.
XkbSA_LockPtrBtn	• If the button specified by the *MouseKeys* default button or *button* is not locked, a key press causes a *ButtonPress* event instead of a *KeyPress* event and locks the button. If the button is already locked or if *XkbSA_LockNoUnlock* is set in the *flags* field, a key press is ignored and has no effect. • If the corresponding key press was ignored, and if *XkbSA_LockNoLock* is not set in the *flags* field, a key release generates a *ButtonRelease* event instead of a *KeyRelease* event and unlocks the specified button. If the corresponding key press locked a button, the key release is ignored and has no effect.

The *flags* field is composed of the bitwise inclusive OR of the masks shown in Table 16.8. A general meaning is given in the table, but the exact meaning depends on the action *type.* :

Table 16.8. Pointer Button Action Flags

Flag	Meaning
XkbSA_UseDfltButton	If set, the action uses the pointer button specified by the *mk_dflt_btn* attribute of the *MouseKeys* control (see section 10.5.1). Otherwise, the action uses the pointer button specified by the *button* field.
XkbSA_LockNoLock	If set, and the action type is *XkbSA_LockPtrBtn* , the server only unlocks the pointer button.
XkbSA_LockNoUnlock	If set, and the action type is *XkbSA_LockPtrBtn* , the server only locks the pointer button.

Actions for Changing the Pointer Button Simulated

Actions associated with the *XkbPtrDfltAction* structure change the *mk_dflt_btn* attribute of the *MouseKeys* control (see section 10.5.1):

```
typedef struct _XkbPtrDfltAction {
      unsigned char   type;      /*  XkbSA_SetPtrDflt */
      unsigned char   flags;     /* controls the pointer button number */
      unsigned char   affect;    /*  XkbSA_AffectDfltBtn */
      char            valueXXX;  /* new default button member */
} XkbPtrDfltAction;
```

If the *MouseKeys* control is not enabled, *KeyPress* and *KeyRelease* events are treated as though the action is *XkbSA_NoAction* . Otherwise, this action changes the *mk_dflt_btn* attribute of the *MouseKeys* control.

The *type* field of the *XkbPtrDfltAction* structure should always be *XkbSA_SetPtrDflt* .

The *flags* field is composed of the bitwise inclusive OR of the values shown in Table 16.9 (currently there is only one value defined).

Table 16.9. Pointer Default Flags

Flag	Meaning
XkbSA_DfltBtnAbsolute	If set, the *value* field represents an absolute pointer button. Otherwise, the *value* field represents the amount to be added to the current default button.

The *affect* field specifies what changes as a result of this action. The only valid value for the *affect* field is *XkbSA_AffectDfltBtn*.

The *valueXXX* field is a signed character that represents the new button value for the *mk_dflt_btn* attribute of the *MouseKeys* control (see section 10.5.1). If *XkbSA_DfltBtnAbsolute* is set in *flags* , *valueXXX* specifies the button to be used; otherwise, *valueXXX* specifies the amount to be added to the current default button. In either case, illegal button choices are wrapped back around into range. Xkb provides the following macros, to convert between the integer and signed character values in *XkbPtrDfltAction* structures:

int *XkbSAPtrDfltValue* (*act*) /* macro */
XkbAction *act* ; /* action from which to extract group */

XkbSAPtrDfltValue returns the *valueXXX* field of *act* converted to a signed int.

void *XkbSASetPtrDfltValue* (*act, val*) /* macro */
XkbPtrDfltAction *act* ; /* action in which to set *valueXXX* */
int *val* ; /* value to set in *valueXXX* */

XkbSASetPtrDfltValue sets the *valueXXX* field of *act* from *val* .

Actions for Locking Modifiers and Group

Actions associated with the *XkbISOAction* structure lock modifiers and the group according to the ISO9995 specification.

Operated by itself, the *XkbISOAction* is just a caps lock. Operated simultaneously with another modifier key, it transforms the other key into a locking key. For example, press *ISO_Lock* , press and release *Control_L* , release *ISO_Lock* ends up locking the *Control* modifier.

The default behavior is to convert:

{Set,Latch}Mods to: LockMods
{Set,Latch}Group to: LockGroup
SetPtrBtn to: LockPtrBtn
SetControls to: LockControls

The *affects* field allows you to turn those effects on or off individually. Set *XkbSA_ISONoAffectMods* to disable the first, *XkbSA_ISONoAffectGroup* to disable the second, and so forth.

```
typedef struct _XkbISOAction {
      unsigned char   type;        /* XkbSA_ISOLock */
      unsigned char   flags;       /* controls changes to group or modifier state
      unsigned char   mask;        /* same as mask field of a modifier description
      unsigned char   real_mods;   /* same as real_mods field of a modifier descri
      char            group_XXX;   /* group index or delta group */
      unsigned char   affect;      /* specifies whether to affect mods, group, ptr
      unsigned char   vmods1;      /* derived from vmods field of a modifier descr
      unsigned char   vmods2;      /* derived from vmods field of a modifier descr
} XkbISOAction;
```

The *type* field of the *XkbISOAction* structure should always be *XkbSA_ISOLock* .

The interpretation of the *flags* field depends on whether the *XkbSA_ISODfltIsGroup* is set in the *flags* field or not.

If the *XkbSA_ISODfltIsGroup* is set in the *flags* field, the action is used to change the group state. The remaining valid bits of the *flags* field are composed of a bitwise inclusive OR using the masks shown in Table 16.10.

Table 16.10. ISO Action Flags when XkbSA_ISODfltIsGroup is Set

Flag	Meaning
XkbSA_ISODfltIsGroup	If set, the action is used to change the base group state. Must be set for the remaining bits in this table to carry their interpretations. A key press sets the base group as specified by the *group_XXX* field and the *XkbSA_GroupAbsolute* bit of the *flags* field (see section Note). If no other actions are transformed by the *XkbISO_Lock* action, a key release locks the group. Otherwise, a key release clears group set by the key press.
XkbSA_GroupAbsolute	If set, the *group_XXX* field represents an absolute group number. Otherwise, it represents a group delta to be added to the current group to determine the new group number.
XkbSA_ISONoAffectMods	If not set, any *XkbSA_SetMods* or *XkbSA_LatchMods* actions that occur simultaneously with the *XkbSA_ISOLock* action are treated as *XkbSA_LockMod* actions instead.
XkbSA_ISONoAffectGroup	If not set, any *XkbSA_SetGroup* or *XkbSA_LatchGroup* actions that occur simultaneously with the *XkbSA_ISOLock* action are treated as *XkbSA_LockGroup* actions instead.
XkbSA_ISONoAffectPtr	If not set, any *XkbSA_PtrBtn* actions that occur simultaneously with the *XkbSA_ISOLock* action are treated as *XkbSA_LockPtrBtn* actions instead.
XkbSA_ISONoAffectCtrls	If not set, any *XkbSA_SetControls* actions that occur simultaneously with the *XkbSA_ISOLock* action are treated as *XkbSA_LockControls* actions instead.

If the *XkbSA_ISODfltIsGroup* is not set in the *flags* field, the action is used to change the modifier state and the remaining valid bits of the *flags* field are composed of a bitwise inclusive OR using the masks shown in Table 16.11.

Table 16.11. ISO Action Flags when XkbSA_ISODfltIsGroup is Not Set

Flag	Meaning
XkbSA_ISODfltIsGroup	If not set, action is used to change the base modifier state. Must not be set for the remaining bits in this table to carry their interpretations. A key press sets the action modifiers in the keyboard's base modifiers using the *mask* , *real_mods* , *vmods1* , and *vmods2* fields (see section 16.1.3). If no other actions are transformed by the *XkbISO_Lock* action, a key release locks the action modifiers. Otherwise, a key release clears the base modifiers set by the key press.
XkbSA_UseModMapMods	If set, the action modifiers are determined by the modifiers bound by the modifier mapping of the key. Otherwise, the action modifiers are set to the modifiers specified by the *mask* , *real_mods* , *vmod1* , and *vmod2* fields.
XkbSA_LockNoLock	If set, the server only unlocks the action modifiers.
XkbSA_LockNoUnlock	If set, the server only locks the action modifiers.
XkbSA_ISONoAffectMods	If not set, any *XkbSA_SetMods* or *XkbSA_LatchMods* actions that occur simultaneously with the *XkbSA_ISOLock* action are treated as *XkbSA_LockMod* actions instead.
XkbSA_ISONoAffectGroup	If not set, any *XkbSA_SetGroup* or *XkbSA_LatchGroup* actions that occur simultaneously with the *XkbSA_ISOLock* action are treated as *XkbSA_LockGroup* actions instead.
XkbSA_ISONoAffectPtr	If not set, any *XkbSA_PtrBtn* actions that occur simultaneously with the *XkbSA_ISOLock* action are treated as *XkbSA_LockPtrBtn* actions instead.
XkbSA_ISONoAffectCtrls	If not set, any *XkbSA_SetControls* actions that occur simultaneously with the *XkbSA_ISOLock* action are treated as *XkbSA_LockControls* actions instead.

The *group_XXX* field represents a signed character. Xkb provides macros to convert between a signed integer value and a signed character as shown in section Note.

The *mask* , *real_mods* , *vmods1* , and *vmods2* fields represent the components of an Xkb modifier description (see section 7.2). While the *mask* and *real_mods* fields correspond directly to the *mask* and *real_mods* fields of an Xkb modifier description, the *vmods1* and *vmods2* fields are combined to correspond to the *vmods* field of an Xkb modifier description. Xkb provides macros to convert between the two formats as shown in section 16.1.3.

The *affect* field is composed of a bitwise inclusive OR using the masks shown in Table 16.11.

Table 16.12. ISO Action Affect Field Values

Affect	Meaning
XkbSA_ISODNoAffectMods	If *XkbSA_ISONoAffectMods* is not set, any *SA_SetMods* or *SA_LatchMods* actions occurring simultaneously with the *XkbISOAction* are treated as *SA_LockMods* instead.
XkbSA_ISONoAffectGroup	If *XkbSA_ISONoAffectGroup* is not set, any *SA_SetGroup* or *SA_LatchGroup* actions occurring simultaneously with the *XkbISOAction* are treated as *SA_LockGroup* instead.
XkbSA_ISONoAffectPtr	If *XkbSA_ISONoAffectPtr* is not set, any *SA_PtrBtn* actions occurring simultaneously with the *XkbISOAction* are treated as *SA_LockPtrBtn* instead.
XkbSA_ISONoAffectCtrls	If *XkbSA_ISONoAffectCtrls* is not set, any *SA_SetControls* actions occurring simultaneously with the *XkbISOAction* are treated as *SA_LockControls* instead.

Actions for Changing the Active Screen

Actions associated with the *XkbSwitchScreen* action structure change the active screen on a multiscreen display:

Note

This action is optional. Servers are free to ignore the action or any of its flags if they do not support the requested behavior. If the action is ignored, it behaves like *XkbSA_NoAction* . Otherwise, key press and key release events do not generate an event.

```
typedef struct _XkbSwitchScreenAction {
      unsigned char   type;        /*  XkbSA_SwitchScreen */
      unsigned char   flags;       /* controls screen switching */
      char            screenXXX;   /* screen number or delta */
} XkbSwitchScreenAction;
```

The *type* field of the *XkbSwitchScreenAction* structure should always be *XkbSA_SwitchScreen*.

The *flags* field is composed of the bitwise inclusive OR of the masks shown in Table 16.13.

Table 16.13. Switch Screen Action Flags

Flag	Meaning
XkbSA_SwitchAbsolute	If set, the *screenXXX* field represents the index of the new screen. Otherwise, it represents an offset from the current screen to the new screen.
XkbSA_SwitchApplication	If not set, the action should switch to another screen on the same server. Otherwise, it should switch to another X server or application that shares the same physical display.

The *screenXXX* field is a signed character value that represents either the relative or absolute screen index, depending on the state of the *XkbSA_SwitchAbsolute* bit in the *flags* field. Xkb provides the following macros to convert between the integer and signed character value for screen numbers in *XkbSwitchScreenAction* structures:

int *XkbSAScreen* (*act*) /* macro */
XkbSwitchScreenAction *act* ; /* action from which to extract screen */

XkbSAScreen returns the *screenXXX* field of *act* converted to a signed int.

void *XkbSASetScreen* (*act, s*) /* macro */
XkbSwitchScreenAction *act* ; /* action in which to set *screenXXX* */
int *s* ; /* value to set in *screenXXX* */

XkbSASetScreen sets the *screenXXX* field of *act* from *s* .

Actions for Changing Boolean Controls State

Actions associated with the *XkbCtrlsAction* structure change the state of the boolean controls (see section 10.1):

```
typedef struct _XkbCtrlsAction {
      unsigned char     type;        /*  XkbSA_SetControls,
                                        XkbSA_LockControls */
      unsigned char     flags;       /* with  type,
                                        controls enabling and disabling of control
      unsigned char     ctrls3;      /* ctrls0 through
                                         ctrls3 represent the boolean controls */
      unsigned char     ctrls2;      /* ctrls0 through
                                         ctrls3 represent the boolean controls */
      unsigned char     ctrls1;      /* ctrls0 through
                                         ctrls3 represent the boolean controls */
      unsigned char     ctrls0;      /* ctrls0 through
                                         ctrls3 represent the boolean controls */
} XkbCtrlsAction;
```

The *type* field can have any one of the values shown in Table 16.14.

Table 16.14. Controls Action Types

Type	Effect
XkbSA_SetControls	• A key press enables any boolean controls specified in the *ctrls* fields that were not already enabled at the time of the key press. • A key release disables any controls enabled by the key press. • This action can cause *XkbControlsNotify* events (see section 10.1).
XkbSA_LockControls	• If the *XkbSA_LockNoLock* bit is not set in the *flags* field, a key press enables any controls specified in the *ctrls* fields that were not already enabled at the time of the key press. • If the *XkbSA_LockNoUnlock* bit is not set in the *flags* field, a key release disables any controls specified in the *ctrls* fields that were not already disabled at the time of the key press. • This action can cause *XkbControlsNotify* events (see section 10.1).

The *flags* field is composed of the bitwise inclusive OR of the masks shown in Table 16.15.

Table 16.15. Control Action Flags

Flag	Meaning
XkbSA_LockNoLock	If set, and the action type is *XkbSA_LockControls* , the server only disables controls.
XkbSA_LockNoUnlock	If set, and the action type is *XkbSA_LockControls* , the server only enables controls.

The *XkbSA_SetControls* action implements a key that enables a boolean control when pressed and disables it when released. The *XkbSA_LockControls* action is used to implement a key that toggles the state of a boolean control each time it is pressed and released. The *XkbSA_LockNoLock* and *XkbSA_LockNoUnlock* flags allow modifying the toggling behavior to only unlock or only lock the boolean control.

The *ctrls0* , *ctrls1* , *ctrls2* , and *ctrls3* fields represent the boolean controls in the *enabled_ctrls* field of the controls structure (see section 10.1). Xkb provides the following macros, to convert between the two formats:

unsigned int *XkbActionCtrls* (*act*) /* macro */

XkbCtrlsAction *act* ; /* action from which to extract controls */

XkbActionCtrls returns the *ctrls* fields of *act* converted to an unsigned int.

void *XkbSAActionSetCtrls* (*act, ctrls*) /* macro */

XkbCtrlsAction *act* ; /* action in which to set ctrls0-ctrls3 */

unsigned int *ctrls* ; /* value to set in ctrls0-ctrls3 */

XkbSAActionSetCtrls sets the *ctrls0* through *ctrls3* fields of *act* from *ctrls* .

Actions for Generating Messages

Actions associated with the *XkbMessageAction* structure generate *XkbActionMessage* events:

```
#define            XkbActionMessageLength                 6


typedef struct _XkbMessageAction {
      unsigned char   type;             /*  XkbSA_ActionMessage */
      unsigned char   flags;            /* controls event generation via key press
      unsigned char   message[XkbActionMessageLength];    /* message */
} XkbMessageAction;
```

The *type* field of the *XkbMessageAction* structure should always be *XkbSA_ActionMessage* .

The *flags* field is composed of the bitwise inclusive OR of the masks shown in Table 16.16.

Table 16.16. Message Action Flags

Flag	Meaning
XkbSA_MessageOnPress	If set, key press events generate an *XkbActionMessage* event that reports the keycode, event type, and contents of the *message* field.
XkbSA_MessageOnRelease	If set, key release events generate an *XkbActionMessage* event that reports the keycode, event type, and contents of the *message* field.
XkbSA_MessageGenKeyEvent	If set, key press and key release events generate *KeyPress* and *KeyRelease* events, regardless of whether they generate *XkbActionMessage* events.

The *message* field is an array of *XkbActionMessageLength* unsigned characters and may be set to anything the keymap designer wishes.

Detecting Key Action Messages

To receive *XkbActionMessage* events by calling either *XkbSelectEvents* or *XkbSelectEventDetails* (see section 4.3).

To receive *XkbActionMessage* events under all possible conditions, use *XkbSelectEvents* and pass *XkbActionMessageMask* in both *bits_to_change* and *values_for_bits* .

The *XkbActionMessage* event has no event details. However, you can call *XkbSelectEventDetails* using *XkbActionMessage* as the *event_type* and specifying *XkbAllActionMessageMask* in *bits_to_change* and *values_for_bits.* This has the same effect as a call to *XkbSelectEvents*.

The structure for the *XkbActionMessage* event is defined as follows:

```
typedef struct _XkbActionMessage {
      int            type;            /* Xkb extension base event code */
      unsigned long  serial;          /* X server serial number for event */
      Bool           send_event;      /* True => synthetically generated */
      Display *      display;         /* server connection where event generated *
      Time           time;            /* server time when event generated */
      int            xkb_type;        /* XkbActionMessage */
      int            device;          /* Xkb device ID, will not be  XkbUseCoreKbd
      KeyCode        keycode;         /* keycode of key triggering event */
      Bool           press;           /* True => key press,
                                         False => release */
      Bool           key_event_follows; /* True => KeyPress/KeyRelease follows */
      char           message[XkbActionMessageLength+1];                    /* m
} XkbActionMessageEvent;
```

The *keycode* is the keycode of the key that was pressed or released. The *press* field specifies whether the event was the result of a key press or key release.

The *key_event_follows* specifies whether a *KeyPress* (if *press* is *True*) or *KeyRelease* (if *press* is *False*) event is also sent to the client. As with all other Xkb events, *XkbActionMessageEvent* s are delivered to all clients requesting them, regardless of the current keyboard focus. However, the *KeyPress* or *KeyRelease* event that conditionally follows an *XkbActionMessageEvent* is sent only to the client selected by the current keyboard focus. *key_event_follows* is *True* only for the client that is actually sent the following *KeyPress* or *KeyRelease* event.

The *message* field is set to the message specified in the action and is guaranteed to be *NULL* -terminated; the Xkb extension forces a *NULL* into *message* [*XkbActionMessageLength*].

Actions for Generating a Different Keycode

Actions associated with the *XkbRedirectKeyAction* structure generate *KeyPress* and *KeyRelease* events containing a keycode different from the key that was pressed or released:

```
typedef struct      _XkbRedirectKeyAction {
      unsigned char      type;          /*  XkbSA_RedirectKey */
      unsigned char      new_key;       /* keycode to be put in event */
      unsigned char      mods_mask;     /* mask of real mods to be reset */
      unsigned char      mods;          /* mask of real mods to take values from *
      unsigned char      vmods_mask0;   /* first half of mask of virtual mods to b
      unsigned char      vmods_mask1;   /* other half of mask of virtual mods to b
      unsigned char      vmods0;        /* first half of mask of virtual mods to t
      unsigned char      vmods1;        /* other half of mask of virtual mods to t
} XkbRedirectKeyAction;
```

The *type* field for the *XkbRedirectKeyAction* structure should always be *XkbSA_RedirectKey* .

Key presses cause a *KeyPress* event for the key specified by the *new_key* field instead of the actual key. The state reported in this event reports the current effective

modifiers changed as follows: any real modifiers selected by the *mods_mask* field are set to corresponding values from the *mods* field. Any real modifiers bound to the virtual modifiers specified by the *vmods_mask0* and *vmods_mask1* fields are either set or cleared, depending on the corresponding values in the *vmods0* and *vmods1* fields. If the real and virtual modifier definitions specify conflicting values for a single modifier, the real modifier definition has priority.

Key releases cause a *KeyRelease* event for the key specified by the *new_key* field instead of the actual key. The state for this event consists of the effective keyboard modifiers at the time of the release, changed as described previously.

The *XkbSA_RedirectKey* action normally redirects to another key on the same device as the key that caused the event, unless that device does not belong to the input extension *KeyClass* , in which case this action causes an event on the core keyboard device. (The input extension categorizes devices by breaking them into classes. Keyboards, and other input devices with keys, are classified as KeyClass devices by the input extension.)

The *vmods_mask0* and *vmods_mask1* fields actually represent one *vmods_mask* value, as described in Chapter 7. Xkb provides the following macros, to convert between the two formats:

unsigned int *XkbSARedirectVModsMask* (*act*) /* macro */
XkbRedirectKeyAction *act* ; /* action from which to extract vmods */

XkbSARedirectVModsMask returns the *vmods_mask0* and *vmods_mask1* fields of *act* converted to an unsigned int.

void *XkbSARedirectSetVModsMask* (*act, vm*) /* macro */
XkbRedirectKeyAction *act* ; /* action in which to set vmods */
unsigned int *vm* ; /* new value for virtual modifier mask */

XkbSARedirectSetVModsMask sets the *vmods_mask0* and *vmods_mask1* fields of *act* from *vm* .

Similarly, the *vmods0* and *vmods1* fields actually represent one *vmods* value, as described in Chapter 7. To convert between the two formats, Xkb provides the following convenience macros:

unsigned int *XkbSARedirectVMods* (*act*) /* macro */
XkbRedirectKeyAction *act* ; /* action from which to extract vmods */

XkbSARedirectVModsMask returns the *vmods0* and *vmods1* fields of *act* converted to an unsigned int.

void *XkbSARedirectSetVMods* (*act, vm*) /* macro */
XkbRedirectKeyAction *act* ; /* action in which to set vmods */
unsigned int *v* ; /* new value for virtual modifiers */

XkbSARedirectSetVModsMask sets the *vmods0* and *vmods1* of *act* from *v*.

Actions for Generating DeviceButtonPress and DeviceButtonRelease

Actions associated with *XkbDeviceBtnAction* structures generate *DeviceButtonPress* and *DeviceButtonRelease* events instead of normal *KeyPress* and *KeyRelease* events:

```
typedef struct _XkbDeviceBtnAction {
      unsigned char    type;      /*  XkbSA_DeviceBtn, XkbSA_LockDeviceBtn */
      unsigned char    flags;     /* with  type , specifies locking or unlocking *
      unsigned char    count;     /* controls number of DeviceButtonPress and Rele
      unsigned char    button;    /* index of button on  device */
      unsigned char    device;    /* device ID of an X input extension device */
} XkbDeviceBtnAction;
```

The *type* field can have any one of the values shown in Table 16.17.

Table 16.17. Device Button Action Types

Type	Effect
XkbSA_DeviceBtn	• If the button specified by this action is logically down, the key press and corresponding release are ignored and have no effect. If the device or button specified by this action are illegal, this action behaves like *XkbSA_NoAction*. • Otherwise, key presses cause one or more input extension device events instead of the usual key press event. If the *count* field is zero, a key press generates a single *DeviceButtonPress* event. If count is greater than zero, a key press event generates *count* pairs of *DeviceButtonPress* and *DeviceButtonRelease* events. • If *count* is zero, a key release generates an input extension *DeviceButtonRelease* event that matches the event generated by the corresponding key press. If *count* is nonzero, a key release does not cause a *DeviceButtonRelease* event. Key releases never cause *KeyRelease* events.
XkbSA_LockDeviceBtn	• If the device or button specified by this action are illegal, this action behaves like *XkbSA_NoAction*. • Otherwise, if the specified button is not locked and the *XkbSA_LockNoLock* bit is not set in the *flags* field, a key press generates an input extension *DeviceButtonPress* event instead of a *KeyPress* event and locks the button. If the button is already locked or if *XkbSA_LockNoLock* bit is set in the *flags* field, the key press is ignored and has no effect. • If the corresponding key press was ignored, and if the *XkbSA_LockNoUnlock* bit is not set in the *flags* field, a key release generates an input extension *DeviceButtonRelease* event instead of a *KeyRelease* event and unlocks the button. If the corresponding key press locked a button, the key release is ignored and has no effect.

The *flags* field is composed of the bitwise inclusive OR of the masks shown in Table 16.18.

Table 16.18. Device Button Action Flags

Flag	Meaning
XkbSA_LockNoLock	If set, and the action type is *XkbSA_LockDeviceBtn* , the server only unlocks the button.
XkbSA_LockNoUnlock	If set, and the action type is *XkbSA_LockDeviceBtn* , the server only locks the button.

Actions for Simulating Events from Device Valuators

A *valuator* manipulates a range of values for some entity, like a mouse axis, a slider or a dial. Actions associated with *XkbDeviceValuatorAction* structures are used to simulate events from one or two input extension device valuators.

```
typedef struct _XkbDeviceValuatorAction {
      unsigned char    type;        /* XkbSA_DeviceValuator */
      unsigned char    device;      /* device ID */
      unsigned char    v1_what;     /* determines how valuator is to behave for va
      unsigned char    v1_ndx;      /* specifies a real valuator */
      unsigned char    v1_value;    /* the value for valuator 1 */
      unsigned char    v2_what;     /* determines how valuator is to behave for va
      unsigned char    v2_ndx;      /* specifies a real valuator */
      unsigned char    v2_value;    /* the value for valuator 1 */
} XkbDeviceValuatorAction;
```

If *device* is illegal or if neither *v1_ndx* nor *v2_ndx* specifies a legal valuator, this action behaves like *XkbSA_NoAction*.

The low four bits of *v1_what* and *v2_what* specify the corresponding scale value (denoted *val<n>Scale* in Table 16.17), if needed. The high four bits of *v1_what* and *v2_what* specify the operation to perform to set the values. The high four bits of *v1_what* and *v2_what* can have the values shown in Table 16.17; the use of *val<n>Scale* is shown in that table also.

Table 16.19. Device Valuator v<n>_what High Bits Values

Value of high bits	Effect
XkbSA_IgnoreVal	No action
XkbSA_SetValMin	*v<n>_value* is set to its minimum legal value.
XkbSA_SetValCenter	*v<n>_value*is centered (to (max-min)/2).
XkbSA_SetValMax	*v<n>_value* is set to its maximum legal value.
XkbSA_SetValRelative	*v<n>_value* * (2 *val<n>Scale*) is added to *v<n>_value*.
XkbSA_SetValAbsolute	*v<n>_value* is set to (2 *val<n>Scale*).

Illegal values for *XkbSA_SetValRelative* or *XkbSA_SetValAbsolute* are clamped into range. Note that all of these possibilities are legal for absolute valuators. For relative valuators, only *XkbSA_SetValRelative* is permitted. Part of the input extension description of a device is the range of legal values for all absolute valuators, whence the maximum and minimum legal values shown in Table 16.17.

The following two masks are provided as a convenience to select either portion of *v1_what* or *v2_what* :

```
#define XkbSA_ValOpMask      (0x70)
#define XkbSA_ValScaleMask      (0x07)
```

v1_ndx and *v2_ndx* specify valuators that actually exists. For example, most mice have two valuators (x and y axes) so the only legal values for a mouse would be 0 and 1. For a dial box with eight dials, any value in the range 0..7 would be correct.

Obtaining Key Actions for Keys from the Server

To update the actions (the *key_acts* array) for a subset of the keys in a keyboard description, use *XkbGetKeyActions* .

Status *XkbGetKeyActions* (*dpy* , *first* , *num* , *xkb*)
Display * *dpy* ; /* connection to X server */
unsigned int *first* ; /* keycode of first key of interest */
unsigned int *num* ; /* number of keys desired */
XkbDescPtr *xkb* ; /* pointer to keyboard description where result is stored */

XkbGetKeyActions sends a request to the server to obtain the actions for *num* keys on the keyboard starting with key *first* . It waits for a reply and returns the actions in the *server -> key_acts* field of *xkb* . If successful, *XkbGetKeyActions* returns *Success* . The *xkb* parameter must be a pointer to a valid Xkb keyboard description.

If the *server* map in the *xkb* parameter has not been allocated, *XkbGetKeyActions* allocates and initializes it before obtaining the actions.

If the server does not have a compatible version of Xkb, or the Xkb extension has not been properly initialized, *XkbGetKeyActions* returns *BadAccess* . If *num* is less than 1 or greater than *XkbMaxKeyCount* , *XkbGetKeyActions* returns *BadValue* . If any allocation errors occur, *XkbGetKeyActions* returns *BadAlloc* .

Changing the Number of Actions Bound to a Key

To change the number of actions bound to a key, use *XkbResizeKeyAction* .

XkbAction * *XkbResizeKeyActions* (*xkb* , *key* , *needed*)
XkbDescRec * *xkb* ; /* keyboard description to change */
int *key* ; /* keycode of key to change */
int *needed* ; /* new number of actions required */

The *xkb* parameter points to the keyboard description containing the *key* whose number of actions is to be changed. The *key* parameter is the keycode of the key to change, and *needed* specifies the new number of actions required for the key.

XkbResizeKeyActions reserves the space needed for the actions and returns a pointer to the beginning of the new array that holds the actions. It can change the *acts* , *num_acts* , and *size_acts* fields of *xkb -> server* if it is necessary to reallocate the *acts* array.

If *needed* is greater than the current number of keysyms for the key, *XkbResizeKeyActions* initializes all new actions in the array to *NoAction* .

Because the number of actions needed by a key is normally computed as width * number of groups, and *XkbResizeKeyActions* does not modify either the width or number of groups for the key, a discrepancy exists on return from *XkbResizeKeyActions* between the space allocated for the actions and the number required. The unused entries in the list of actions returned by *XkbResizeKeyActions* are not preserved across future calls to any of the map editing functions, so you must update

the key actions (which updates the width and number of groups for the key) before calling another allocator function. A call to *XkbChangeTypesOfKey* updates these.

If any allocation errors occur while resizing the number of actions bound to the key, *XkbResizeKeyActions* returns *NULL* .

Note

A change to the number of actions bound to a key should be accompanied by a change in the number of symbols bound to a key. Refer to section 15.3.7 for more information on changing the number of symbols bound to a key.

Key Behavior

Key behavior refers to the demeanor of a key. For example, the expected behavior of the *CapsLock* key is that it logically locks when pressed, and then logically unlocks when pressed again.

Radio Groups

Keys that belong to the same radio group have the *XkbKB_RadioGroup* type in the *type* field and the radio group index specified in the *data* field in the *XkbBehavior* structure. If the radio group has a name in the *XkbNamesRec* structure, the radio group index is the index into the *radio_group* array in the *XkbNamesRec* structure. A radio group key when pressed stays logically down until another key in the radio group is pressed, when the first key becomes logically up and the new key becomes logically down. Setting the *XkbKB_RGAllowNone* bit in the behavior for all of the keys of the radio group means that pressing the logically down member of the radio group causes it to logically release, in which case none of the keys of the radio group would be logically down. If *XkbKB_RGAllowNone* is not set, there is no way to release the logically down member of the group.

The low five bits of the *data* field of the *XkbBehavior* structure are the group number, the high three bits are flags. The only flag currently defined is:

```
#define      XkbRG_AllowNone      0x80
```

The XkbBehavior Structure

The *behaviors* field of the server map is an array of *XkbBehavior* structures, indexed by keycode, and contains the behavior for each key. The *XkbBehavior* structure is defined as follows:

```
typedef struct _XkbBehavior {
      unsigned char  type;                 /* behavior type + optional
                                              XkbKB_Permanent bit */
      unsigned char  data;
} XkbBehavior;
```

The *type* field specifies the Xkb behavior, and the value of the *data* field depends on the *type* . Xkb supports the key behaviors shown in Table 16.20.

Table 16.20. Key Behaviors

Type	Effect
XkbKB_Default	Press and release events are processed normally. The *data* field is unused.
XkbKB_Lock	If a key is logically up (that is, the corresponding bit of the core key map is cleared) when it is pressed, the key press is processed normally and the corresponding release is ignored. If the key is logically down when pressed, the key press is ignored but the corresponding release is processed normally. The *data* field is unused.
XkbKB_RadioGroup	If another member of the radio group is logically down (all members of the radio group have the same index, specified in *data*) when a key is pressed, the server synthesizes a key release for the member that is logically down and then processes the new key press event normally. If the key itself is logically down when pressed, the key press event is ignored, but the processing of the corresponding key release depends on the value of the *Xkb_RGAllowNone* bit in *flags* . If it is set, the key release is processed normally; otherwise, the key release is also ignored. All other key release events are ignored.
XkbKB_Overlay1	If the *Overlay1* control is enabled (see section 10.4), *data* is interpreted as a keycode, and events from this key are reported as if they came from *data* 's keycode. Otherwise, press and release events are processed normally.
XkbKB_Overlay2	If the *Overlay2* control is enabled (see section 10.4), *data* is interpreted as a keycode, and events from this key are reported as if they came from *data* 's keycode. Otherwise, press and release events are processed normally.

Xkb also provides the mask, *XkbKB_Permanent* to specify whether the key behavior type should be simulated by Xkb or whether the key behavior describes an unalterable physical, electrical, or software aspect of the keyboard. If the *XkbKB_Permanent* bit is not set in the *type* field, Xkb simulates the behavior in software. Otherwise, Xkb relies upon the keyboard to implement the behavior.

Obtaining Key Behaviors for Keys from the Server

To obtain the behaviors (the *behaviors* array) for a subset of the keys in a keyboard description from the server, use *XkbGetKeyBehaviors* :

Status *XkbGetKeyBehaviors* (*dpy* , *first* , *num* , *xkb*)

Display * *dpy* ; /* connection to server */

unsigned int *first* ; /* keycode of first key to get */

unsigned int *num* ; /* number of keys for which behaviors are desired */

XkbDescPtr *xkb* ; /* Xkb description to contain the result */

XkbGetKeyBehaviors sends a request to the server to obtain the behaviors for *num* keys on the keyboard starting with the key whose keycode is *first* . It waits for a reply and returns the behaviors in the *server -> behaviors* field of *xkb* . If successful, *XkbGetKeyBehaviors* returns *Success* .

If the *server* map in the *xkb* parameter has not been allocated, *XkbGetKeyBehaviors* allocates and initializes it before obtaining the actions.

If the server does not have a compatible version of Xkb, or the Xkb extension has not been properly initialized, *XkbGetKeyBehaviors* returns *BadAccess* . If *num* is less than 1 or greater than *XkbMaxKeyCount* , *XkbGetKeyBehaviors* returns *BadValue* . If any allocation errors occur, *XkbGetKeyBehaviors* returns *BadAlloc* .

Explicit Components—Avoiding Automatic Remapping by the Server

Whenever a client remaps the keyboard using core protocol requests, Xkb examines the map to determine likely default values for the components that cannot be specified using the core protocol (see section 17.1.2 for more information on how Xkb chooses the default values).

This automatic remapping might replace definitions explicitly requested by an application, so the Xkb keyboard description defines an explicit components mask for each key. Any aspects of the automatic remapping listed in the explicit components mask for a key are not changed by the automatic keyboard mapping.

The explicit components masks are held in the *explicit* field of the server map, which is an array indexed by keycode. Each entry in this array is a mask that is a bitwise inclusive OR of the values shown in Table 16.21.

Table 16.21. Explicit Component Masks

Bit in Explicit Mask	Value	Protects Against
ExplicitKeyType1	(1<<0)	Automatic determination of the key type associated with *Group1.*
ExplicitKeyType2	(1<<1)	Automatic determination of the key type associated with *Group2.*
ExplicitKeyType3	(1<<2)	Automatic determination of the key type associated with *Group3.*
ExplicitKeyType4	(1<<3)	Automatic determination of the key type associated with *Group4.*
ExplicitInterpret	(1<<4)	Application of any of the fields of a symbol interpretation to the key in question.
ExplicitAutoRepeat	(1<<5)	Automatic determination of auto-repeat status for the key, as specified in a symbol interpretation.
ExplicitBehavior	(1<<6)	Automatic assignment of the *XkbKB_Lock* behavior to the key, if the *XkbSI_LockingKey* flag is set in a symbol interpretation.
ExplicitVModMap	(1<<7)	Automatic determination of the virtual modifier map for the key based on the actions assigned to the key and the symbol interpretations that match the key.

Obtaining Explicit Components for Keys from the Server

To obtain the explicit components (the *explicit* array) for a subset of the keys in a keyboard description, use *XkbGetKeyExplicitComponents*.

```
Status XkbGetKeyExplicitComponents ( dpy , first , num , xkb )
Display * dpy ; /* connection to server */
unsigned int first ; /* keycode of first key to fetch */
unsigned int num ; /* number of keys for which to get explicit info */
XkbDescPtr xkb ; /* Xkb description in which to put results */
```

XkbGetKeyExplicitComponents sends a request to the server to obtain the explicit components for *num* keys on the keyboard starting with key *first* . It waits for a reply and returns the explicit components in the *server -> explicit* array of *xkb* . If successful, *XkbGetKeyExplicitComponents* returns *Success* . The *xkb* parameter must be a pointer to a valid Xkb keyboard description.

If the *server* map in the *xkb* parameter has not been allocated, *XkbGetKeyExplicitComponents* allocates and initializes it before obtaining the actions.

If the server does not have a compatible version of Xkb, or the Xkb extension has not been properly initialized, *XkbGetKeyExplicitComponents* returns *BadMatch* .

If *num* is less than 1 or greater than *XkbMaxKeyCount* , *XkbGetKeyExplicitComponents* returns *BadValue* . If any allocation errors occur, *XkbGetKeyExplicitComponents* returns *BadAlloc* .

Virtual Modifier Mapping

The *vmods* member of the server map is a fixed-length array containing *XkbNumVirtualMods* entries. Each entry corresponds to a virtual modifier and provides the binding of the virtual modifier to the real modifier bits. Each entry in the *vmods* array is a bitwise inclusive OR of the legal modifier masks:

ShiftMask
LockMask
ControlMask
Mod1Mask
Mod2Mask
Mod3Mask
Mod4Mask
Mod5Mask

The *vmodmap* member of the server map is similar to the *modmap* array of the client map (see section 15.4), but is used to define the virtual modifier mapping for each key. Like the *modmap* member, it is indexed by keycode, and each entry is a mask representing the virtual modifiers bound to the corresponding key:

- Each of the bits in a *vmodmap* entry represents an index into the *vmods* member. That is, bit 0 of a *vmodmap* entry refers to index 0 of the *vmods* array, bit 1 refers to index 1, and so on.

- If a bit is set in the *vmodmap* entry for a key, that key is bound to the corresponding virtual modifier in the *vmods* array.

The *vmodmap* and *vmods* members of the server map are the "master" virtual modifier definitions. Xkb automatically propagates any changes to these fields to all other fields that use virtual modifier mappings.

The overall relationship of fields dealing with virtual modifiers in an Xkb keyboard description are shown in Figure 16.2.



Virtual Modifier Relationships

Obtaining Virtual Modifier Bindings from the Server

To obtain a subset of the virtual modifier bindings (the *vmods* array) in a keyboard description, use *XkbGetVirtualMods* :

Status *XkbGetVirtualMods* (*dpy* , *which* , *xkb*)
Display * *dpy* ; /* connection to server */
unsigned int *which* ; /* mask indicating virtual modifier bindings to get */
XkbDescPtr *xkb* ; /* Xkb description where results will be placed */

XkbGetVirtualMods sends a request to the server to obtain the *vmods* entries for the virtual modifiers specified in the mask, *which* , and waits for a reply. See section 7.1 for a description of how to determine the virtual modifier mask. For each bit set in *which* , *XkbGetVirtualMods* updates the corresponding virtual modifier definition in the *server->vmods* array of *xkb* . The *xkb* parameter must be a pointer to a valid Xkb keyboard description. If successful, *XkbGetVirtualMods* returns *Success* .

If the *server* map has not been allocated in the *xkb* parameter, *XkbGetVirtualMods* allocates and initializes it before obtaining the virtual modifier bindings.

If the server does not have a compatible version of Xkb, or the Xkb extension has not been properly initialized, *XkbGetVirtualMods* returns *BadMatch* . Any errors in allocation cause *XkbGetVirtualMods* to return *BadAlloc*.

Obtaining Per-Key Virtual Modifier Mappings from the Server

To obtain the virtual modifier map (the *vmodmap* array) for a subset of the keys in a keyboard description, use *XkbGetKeyVirtualModMap* :

Status *XkbGetKeyVirtualModMap* (*dpy* , *first* , *num* , *xkb*)
Display * *dpy* ; /* connection to server */
unsigned int *first* ; /* keycode of first key to fetch */
unsigned int *num* ; /* # keys for which virtual mod maps are desired */
XkbDescPtr *xkb* ; /* Xkb description where results will be placed */

XkbGetKeyVirutalModmap sends a request to the server to obtain the virtual modifier mappings for *num* keys on the keyboard starting with key *first* . It waits for a reply and returns the virtual modifier mappings in the *server -> vmodmap* array of *xkb* . If successful, *XkbGetKeyVirtualModMap* returns *Success* . The *xkb* parameter must be a pointer to a valid Xkb keyboard description

If the *server* map in the *xkb* parameter has not been allocated, *XkbGetKeyVirtualModMap* allocates and initializes it before obtaining the virtual modifier mappings.

If the server does not have a compatible version of Xkb, or the Xkb extension has not been properly initialized, *XkbGetKeyVirtualModMap* returns *BadMatch* . If *num* is less than 1 or greater than *XkbMaxKeyCount* , *XkbGetKeyVirtualModMap* returns *BadValue* . If any allocation errors occur, *XkbGetKeyVirtualModMap* returns *BadAlloc* .

Chapter 17. The Xkb Compatibility Map

As shown in Figure 17.1, the X server is normally dealing with more than one client, each of which may be receiving events from the keyboard, and each of which may issue requests to modify the keyboard in some manner. Each client may be either Xkb-unaware, Xkb-capable, or Xkb-aware. The server itself may be either Xkb-aware or Xkb-unaware. If the server is Xkb-unaware, Xkb state and keyboard mappings are not involved in any manner, and Xkb-aware clients may not issue Xkb requests to the server. If the server is Xkb-aware, the server must be able to deliver events and accept requests in which the keyboard state and mapping are compatible with the mode in which the client is operating. Consequently, for some situations, conversions must be made between Xkb state / keyboard mappings and core protocol state / keyboard mappings, and vice versa.



Server Interaction with Types of Clients

In addition to these situations involving a single server, there are cases where a client that deals with multiple servers may need to configure keyboards on different

servers to be similar and the different servers may not all be Xkb-aware. Finally, a client may be dealing with descriptions of keyboards (files, and so on) that are based on core protocol and therefore may need to be able to map these descriptions to Xkb descriptions.

An Xkb-aware server maintains keyboard state and mapping as an Xkb keyboard state and an Xkb keyboard mapping plus a compatibility map used to convert from Xkb components to core components and vice versa. In addition, the server also maintains a core keyboard mapping that approximates the Xkb keyboard mapping. The core keyboard mapping may be updated piecemeal, on a per-key basis. When the server receives a core protocol *ChangeKeyboardMapping* or *SetModifierMapping* request, it updates its core keyboard mapping, then uses the compatibility map to update its Xkb keyboard mapping. When the server receives an *XkbSetMap* request, it updates those portions of its Xkb keyboard mapping specified by the request, then uses its compatibility map to update the corresponding parts of its core keyboard map. Consequently, the server's Xkb keyboard map and also its core keyboard map may contain components that were set directly and others that were computed. Figure 17.2 illustrates these relationships.

Note

The core keyboard map is contained only in the server, not in any client-side data structures.



Server Derivation of State and Keyboard Mapping Components

There are three kinds of compatibility transformations made by the server:

1. **Xkb State to Core State**

   Keyboard state information reported to a client in the state field of various core events may be translated from the Xkb keyboard state maintained by the server, which includes a group number, to core protocol state, which does not.

   In addition, whenever the Xkb state is retrieved, the *compat_state* , *compat_grab_mods* , and *compat_lookup_mods* fields of the *XkbStateRec* returned indicate the result of applying the compatibility map to the current Xkb state in the server.

2. **Core Keyboard Mapping to Xkb Keyboard Mapping**

   After core protocol requests received by the server to change the keyboard mapping (*ChangeKeyboardMapping* and *SetModifierMapping*) have been applied to the server's core keyboard map, the results must be transformed to achieve an equivalent change of the Xkb keyboard mapping maintained by the server.

3. **Xkb Keyboard Mapping to Core Keyboard Mapping**

   After Xkb protocol requests received by the server to change the keyboard mapping (*XkbSetMap*) have been applied to the server's Xkb keyboard map, the results are transformed to achieve an approximately equivalent change to the core keyboard mapping maintained by the server.

This chapter discusses how a client may modify the compatibility map so that subsequent transformations have a particular result.

The XkbCompatMap Structure

All configurable aspects of mapping Xkb state and configuration to and from core protocol state and configuration are defined by a compatibility map, contained in an *XkbCompatMap* structure; plus a set of explicit override controls used to prevent particular components of type 2 (core-to-Xkb keyboard mapping) transformations from automatically occurring. These explicit override controls are maintained in a separate data structure discussed in section 16.3.

The *compat* member of an Xkb keyboard description (*XkbDescRec*) points to the *XkbCompatMap* structure:

```
typedef struct _XkbCompatMapRec {
      XkbSymInterpretPtr   sym_interpret;           /* symbol based key semantics
      XkbModsRec           groups[XkbNumKbdGroups]; /* group => modifier map */
      unsigned short       num_si;                  /* # structures used in
                                                       sym_interpret */
      unsigned short       size_si;                 /* # structures allocated in
                                                       sym_interpret */
} XkbCompatMapRec, *XkbCompatMapPtr;
```



Xkb Compatibility Data Structures

The subsections that follow discuss how the compatibility map and explicit override controls are used in each of the three cases where compatibility transformations are made.

Xkb State to Core Protocol State Transformation

As shown in Figure 17.3, there are four *group compatibility maps* (contained in *groups* [0..3]) in the *XkbCompatMapRec* structure, one per possible Xkb group. Each group compatibility map is a modifier definition (see section 7.2 for a description of modifier definitions). The *mask* component of the definition specifies which real modifiers should be set in the core protocol state field when the corresponding group is active. Because only one group is active at any one time, only one of the four possible transformations is ever applied at any one point in time. If the device described by the *XkbDescRec* does not support four groups, the extra groups fields are present, but undefined.

Normally, the Xkb-aware server reports keyboard state in the *state* member of events such as a *KeyPress* event and *ButtonPress* event, encoded as follows:

bits	**meaning**
15	0
13-14	Group index
8-12	Pointer Buttons
0-7	Modifiers

For Xkb-unaware clients, only core protocol keyboard information may be reported. Because core protocol does not define the group index, the group index is mapped to modifier bits as specified by the *groups* [group index] field of the compatibility map (the bits set in the compatibility map are ORed into bits 0-7 of the state), and bits 13-14 are reported in the event as zero.

Core Keyboard Mapping to Xkb Keyboard Mapping Transformation

When a core protocol keyboard mapping request is received by the server, the server's core keyboard map is updated, and then the Xkb map maintained by the server is updated. Because a client may have explicitly configured some of the Xkb keyboard mapping in the server, this automatic regeneration of the Xkb keyboard mapping from the core protocol keyboard mapping should not modify any components of the Xkb keyboard mapping that were explicitly set by a client. The client must set explicit override controls to prevent this from happening (see section 16.3). The core-to-Xkb mapping is done as follows:

1. Map the symbols from the keys in the core keyboard map to groups and symbols on keys in the Xkb keyboard map. The core keyboard mapping is of fixed width, so each key in the core mapping has the same number of symbols associated with it. The Xkb mapping allows a different number of symbols to be associated with each key; those symbols may be divided into a different number of groups (1-4) for each key. For each key, this process therefore involves partitioning the fixed number of symbols from the core mapping into a set of variable-length groups with a variable number of symbols in each group. For example, if the core protocol map is of width five, the partition for one key might result in one group with two symbols and another with three symbols. A different key might result in two groups with two symbols plus a third group with one symbol. The core protocol map requires at least two symbols in each of the first two groups.

    a. For each changed key, determine the number of groups represented in the new core keyboard map. This results in a tentative group count for each key in the Xkb map.

    b. For each changed key, determine the number of symbols in each of the groups found in step 1a. There is one explicit override control associated with each of the four possible groups for each Xkb key, *ExplicitKeyType1* through *ExplicitKeyType4* . If no explicit override control is set for a group, the number of symbols used for that group from the core map is two. If the explicit override control is set for a group on the key, the number of symbols used for that Xkb group from the core map is the width of the Xkb group with one exception: because of the core protocol requirement for at least two symbols in each of groups one and two, the number of symbols used for groups one and two is the maximum of 2 or the width of the Xkb group.

    c. For each changed key, assign the symbols in the core map to the appropriate group on the key. If the total number of symbols required by the Xkb map for a particular key needs more symbols than the core protocol map contains, the additional symbols are taken to be *NoSymbol* keysyms appended to the end of the core set. If the core map contains more symbols than are needed by the Xkb map, trailing symbols in the core map are discarded. In the absence of an explicit override for group one or two, symbols are assigned in order by group; the first symbols in the core map are assigned to group one, in order, followed

by group two, and so on. For example, if the core map contained eight symbols per key, and a particular Xkb map contained 2 symbols for G1 and G2 and three for G3, the symbols would be assigned as (G is group, L is shift level):

G1L1 G1L2 G2L1 G2L2 G3L1 G3L2 G3L3

If an explicit override control is set for group one or two, the symbols are taken from the core set in a somewhat different order. The first four symbols from the core set are assigned to G1L1, G1L2, G2L1, G2L2, respectively. If group one requires more symbols, they are taken next, and then any additional symbols needed by group two. Group three and four symbols are taken in complete sequence after group two. For example, a key with four groups and three symbols in each group would take symbols from the core set in the following order:

G1L1 G1L2 G2L1 G2L2 G1L3 G2L3 G3L1 G3L2 G3L3 G4L1 G4L2 G4L3

As previously noted, the core protocol map requires at lease two symbols in groups one and two. Because of this, if an explicit override control for an Xkb key is set and group one and / or group two is of width one, it is not possible to generate the symbols taken from the core protocol set and assigned to position G1L2 and / or G2L2.

d. For each group on each changed key, assign a key type appropriate for the symbols in the group.

e. For each changed key, remove any empty or redundant groups.

2. At this point, the groups and their associated symbols have been assigned to the corresponding key definitions in the Xkb map.

3. Apply symbol interpretations to modify key operation. This phase is completely skipped if the *ExplicitInterpret* override control bit is set in the explicit controls mask for the Xkb key (see section 16.3).

   a. For each symbol on each changed key, attempt to match the symbol and modifiers from the Xkb map to a symbol interpretation describing how to generate the symbol.

   b. When a match is found in step 2a, apply the symbol interpretation to change the semantics associated with the symbol in the Xkb key map. If no match is found, apply a default interpretation.

The symbol interpretations used in step 2 are configurable and may be specified using *XkbSymInterpretRec* structures referenced by the *sym_interpret* field of an *XkbCompatMapRec* (see Figure 17.3).

Symbol Interpretations — the XkbSymInterpretRec Structure

Symbol interpretations are used to guide the X server when it modifies the Xkb keymap in step 2. An initial set of symbol interpretations is loaded by the server when it starts. A client may add new ones using *XkbSetCompatMap* (see section 17.4).

Symbol interpretations result in key semantics being set. When a symbol interpretation is applied, the following components of server key event processing may be modified for the particular key involved:

Virtual modifier map
Auto repeat
Key behavior (may be set to *XkbKB_Lock*)
Key action (see section 16.1)

The *XkbSymInterpretRec* structure specifies a symbol interpretation:

```
typedef struct {
      KeySym          sym;          /* keysym of interest or NULL */
      unsigned char   flags;        /* XkbSI_AutoRepeat, XkbSI_LockingKey */
      unsigned char   match;        /* specifies how mods is interpreted */
      unsigned char   mods;         /* modifier bits, correspond to eight real mod
      unsigned char   virtual_mod;  /* 1 modifier to add to key virtual mod map */
      XkbAnyAction    act;          /* action to bind to symbol position on key */
} XkbSymInterpretRec,*XkbSymInterpretPtr;
```

If *sym* is not *NULL* , it limits the symbol interpretation to keys on which that particular keysym is selected by the modifiers matching the criteria specified by *mods* and *match* . If *sym* is *NULL* , the interpretation may be applied to any symbol selected on a key when the modifiers match the criteria specified by *mods* and *match* .

match must be one of the values shown in Table 17.1 and specifies how the real modifiers specified in *mods* are to be interpreted.

Table 17.1. Symbol Interpretation Match Criteria

Match Criteria	Value	Effect
XkbSI_NoneOf	(0)	None of the bits that are on in *mods* can be set, but other bits can be.
XkbSI_AnyOfOrNone	(1)	Zero or more of the bits that are on in *mods* can be set, as well as others.
XkbSI_AnyOf	(2)	One or more of the bits that are on in *mods* can be set, as well as any others.
XkbSI_AllOf	(3)	All of the bits that are on in *mods* must be set, but others may be set as well.
XkbSI_Exactly	(4)	All of the bits that are on in *mods* must be set, and no other bits may be set.

In addition to the above bits, *match* may contain the *XkbSI_LevelOneOnly* bit, in which case the modifier match criteria specified by *mods* and *match* applies only if *sym* is in level one of its group; otherwise, *mods* and *match* are ignored and the symbol matches a condition where no modifiers are set.

```
#define XkbSI_LevelOneOnly  (0x80)
```

```
/* use mods + match only if sym is level 1 */
```

If no matching symbol interpretation is found, the server uses a default interpretation where:

sym =	0
flags =	*XkbSI_AutoRepeat*
match =	*XkbSI_AnyOfOrNone*
mods =	0
virtual_mod =	*XkbNoModifier*
act =	*SA_NoAction*

When a matching symbol interpretation is found in step 2a, the interpretation is applied to modify the Xkb map as follows.

The *act* field specifies a single action to be bound to the symbol position; any key event that selects the symbol causes the action to be taken. Valid actions are defined in section 16.1.

If the Xkb keyboard map for the key does not have its *ExplicitVModMap* control set, the *XkbSI_LevelOneOnly* bit and symbol position are examined. If the *XkbSI_LevelOneOnly* bit is not set in *match* or the symbol is in position G1L1, the *virtual_mod* field is examined. If *virtual_mod* is not *XkbNoModifier* , *virtual_mod* specifies a single virtual modifier to be added to the virtual modifier map for the key. *virtual_mod* is specified as an index in the range [0..15].

If the matching symbol is in position G1L1 of the key, two bits in the flags field potentially specify additional behavior modifications:

```
#define      XkbSI_AutoRepeat    (1<<0)
                                 /* key repeats if sym is in position G1L1 */
#define      XkbSI_LockingKey    (1<<1)
                                 /* set  KB_Lock
                                    behavior if sym is in psn G1L1 */
```

If the Xkb keyboard map for the key does not have its *ExplicitAutoRepeat* control set, its auto repeat behavior is set based on the value of the *XkbSI_AutoRepeat* bit. If the *XkbSI_AutoRepeat* bit is set, the auto-repeat behavior of the key is turned on; otherwise, it is turned off.

If the Xkb keyboard map for the key does not have its *ExplicitBehavior* control set, its locking behavior is set based on the value of the *XkbSI_LockingKey* bit. If *XkbSI_LockingKey* is set, the key behavior is set to *KB_Lock* ; otherwise, it is turned off (see section 16.3).

Xkb Keyboard Mapping to Core Keyboard Mapping Transformations

Whenever the server processes Xkb requests to change the keyboard mapping, it discards the affected portion of its core keyboard mapping and regenerates it based on the new Xkb mapping.

When the Xkb mapping for a key is transformed to a core protocol mapping, the symbols for the core map are taken in the following order from the Xkb map:

G1L1 G1L2 G2L1 G2L2 G1L3-n G2L3-n G3L1-n G4L1-n

If group one is of width one in the Xkb map, G1L2 is taken to be NoSymbol; similarly, if group two is of width one in the Xkb map, G2L2 is taken to be NoSymbol.

If the Xkb key map for a particular key has fewer groups than the core keyboard, the symbols for group one are repeated to fill in the missing core components. For example, an Xkb key with a single width-three group would be mapped to a core mapping counting three groups as:

G1L1 G1L2 G1L1 G1L2 G1L3 G1L3 G1L1 G1L2 G1L3

When a core keyboard map entry is generated from an Xkb keyboard map entry, a modifier mapping is generated as well. The modifier mapping contains all of the modifiers affected by any of the actions associated with the key combined with all of the real modifiers associated with any of the virtual modifiers bound to the key. In addition, if any of the actions associated with the key affect any component of the keyboard group, all of the modifiers in the *mask* field of all of the group compatibility maps are added to the modifier mapping as well. While an *XkbSA_ISOLock* action can theoretically affect any modifier, if the Xkb mapping for a key specifies an *XkbSA_ISOLock* action, only the modifiers or group that are set by default are added to the modifier mapping.

Getting Compatibility Map Components From the Server

Use *XkbGetCompatMap* to fetch any combination of the current compatibility map components from the server. When another client modifies the compatibility map, you are notified if you have selected for *XkbCompatMapNotify* events (see section 17.5). *XkbGetCompatMap* is particularly useful when you receive an event of this type, as it allows you to update your program's version of the compatibility map to match the modified version now in the server. If your program is dealing with multiple servers and needs to configure them all in a similar manner, the updated compatibility map may be used to reconfigure other servers.

Note

To make a complete matching configuration you must also update the explicit override components of the server state.

Status *XkbGetCompatMap* (*display, which, xkb*)

Display * *display* ; /* connection to server */

unsigned int *which* ; /* mask of compatibility map components to fetch */

XkbDescRec * *xkb* ; /* keyboard description where results placed */

XkbGetCompatMap fetches the components of the compatibility map specified in *which* from the server specified by *display* and places them in the *compat* structure of the keyboard description *xkb* . Valid values for *which* are an inclusive OR of the values shown in Table 17.2.

Table 17.2. Compatibility Map Component Masks

Mask	Value	Affecting
XkbSymInterpMask	(1<<0)	Symbol interpretations
XkbGroupCompatMask	(1<<1)	Group maps
XkbAllCompatMask	(0x3)	All compatibility map components

If no compatibility map structure is allocated in *xkb* upon entry, *XkbGetCompatMap* allocates one. If one already exists, its contents are overwritten with the returned results.

XkbGetCompatMap fetches compatibility map information for the device specified by the *device_spec* field of *xkb* . Unless you have specifically modified this field, it is the default keyboard device. *XkbGetCompatMap* returns *Success* if successful, *BadAlloc* if it is unable to obtain necessary storage for either the return values or work space, *BadMatch* if the *dpy* field of the *xkb* argument is non- *NULL* and does not match the *display* argument, and *BadLength* under certain conditions caused by server or Xkb implementation errors.

Using the Compatibility Map

Xkb provides several functions that make it easier to apply the compatibility map to configure a client-side Xkb keyboard mapping, given a core protocol representation of part or all of a keyboard mapping. Obtain a core protocol representation of a keyboard mapping from an actual server (by using *XGetKeyboardMapping* , for example), a data file, or some other source.

To update a local Xkb keyboard map to reflect the mapping expressed by a core format mapping by calling the function *XkbUpdateMapFromCore* .

Bool *XkbUpdateMapFromCore* (*xkb* , *first_key* , *num_keys* , *map_width* , *core_keysyms* , *changes*)

XkbDescPtr *xkb* ; /* keyboard description to update */

KeyCode *first_key* ; /* keycode of first key description to update */

int *num_keys* ; /* number of key descriptions to update */

int *map_width* ; /* width of core protocol keymap */

KeySym * *core_keysyms* ; /* symbols in core protocol keymap */

XkbChangesPtr *changes* ; /* backfilled with changes made to Xkb */

XkbUpdateMapFromCore interprets input argument information representing a keyboard map in core format to update the Xkb keyboard description passed in *xkb* . Only a portion of the Xkb map is updated — the portion corresponding to keys with keycodes in the range *first_key* through *first_key* + *num_keys* - 1. If *XkbUpdateMapFromCore* is being called in response to a *MappingNotify* event , *first_key* and *num_keys* are reported in the *MappingNotify* event. *core_keysyms* contains the keysyms corresponding to the keycode range being updated, in core keyboard description order. *map_width* is the number of keysyms per key in *core_keysyms* . Thus, the first *map_width* entries in *core_keysyms* are for the key with keycode *first_key* , the next *map_width* entries are for key *first_key* + 1, and so on.

In addition to modifying the Xkb keyboard mapping in *xkb* , *XkbUpdateMapFromCore* backfills the changes structure whose address is passed in *changes* to indicate

the modifications that were made. You may then use *changes* in subsequent calls such as *XkbSetMap* , to propagate the local modifications to a server.

When dealing with core keyboard mappings or descriptions, it is sometimes necessary to determine the Xkb key types appropriate for the symbols bound to a key in a core keyboard mapping. Use *XkbKeyTypesForCoreSymbols* for this purpose:

int *XkbKeyTypesForCoreSymbols* (*map_width* , *core_syms* , *protected, types_inout, xkb_syms_rtrn*)

XkbDescPtr *xkb* ; /* keyboard description in which to place symbols*/

int *map_width* ; /* width of core protocol keymap in *xkb_syms_rtrn* */

KeySym * *core_syms* ; /* core protocol format array of KeySyms */

unsigned int *protected* ; /* explicit key types */

int * *types_inout;* /* backfilled with the canonical types bound to groups one and two for the key */

KeySym * *xkb_syms_rtrn* ; /* backfilled with symbols bound to the key in the Xkb mapping */

XkbKeyTypesForCoreSymbols expands the symbols in *core_syms* and types in *types_inout* according to the rules specified in section 12 of the core protocol, then chooses canonical key types (canonical key types are defined in section 15.2.1) for groups 1 and 2 using the rules specified by the Xkb protocol and places them in *xkb_syms_rtrn* , which will be non- *NULL* .

A core keymap is a two-dimensional array of keysyms. It has *map_width* columns and *max_key_code* rows. *XkbKeyTypesForCoreSymbols* takes a single row from a core keymap, determines the number of groups associated with it, the type of each group, and the symbols bound to each group. The return value is the number of groups, *types_inout* has the types for each group, and *xkb_syms_rtrn* has the symbols in Xkb order (that is, groups are contiguous, regardless of size).

protected contains the explicitly protected key types. There is one explicit override control associated with each of the four possible groups for each Xkb key, *ExplicitKeyType1* through *ExplicitKeyType4 ; protected* is an inclusive OR of these controls. *map_width* is the width of the core keymap and is not dependent on any Xkb definitions. *types_inout* is an array of four type indices. On input, *types_inout* contains the indices of any types already assigned to the key, in case they are explicitly protected from change.

Upon return, *types_inout* contains any automatically selected (that is, canonical) types plus any protected types. Canonical types are assigned to all four groups if there are enough symbols to do so. The four entries in *types_inout* correspond to the four groups for the key in question.

If the groups mapping does not change, but the symbols assigned to an Xkb keyboard compatibility map do change, the semantics of the key may be modified. To apply the new compatibility mapping to an individual key to get its semantics updated, use *XkbApplyCompatMapToKey* .

Bool *XkbApplyCompatMapToKey* (*xkb* , *key* , *changes*)

XkbDescPtr *xkb;* /* keyboard description to be updated */

KeyCode *key* ; /* key to be updated */

XkbChangesPtr *changes* ; /* notes changes to the Xkb keyboard description */

XkbApplyCompatMapToKey essentially performs the operation described in section 17.1.2 to a specific key. This updates the behavior, actions, repeat status, and virtual modifier bindings of the key.

Changing the Server's Compatibility Map

To modify the server's compatibility map, first modify a local copy of the Xkb compatibility map, then call *XkbSetCompatMap* . You may allocate a new compatibility map for this purpose using *XkbAllocCompatMap* (see section 17.6). You may also use a compatibility map from another server, although you need to adjust the *device_spec* field in the *XkbDescRec* accordingly. Note that symbol interpretations in a compatibility map (*sym_interpret* , the vector of *XkbSymInterpretRec* structures) are also allocated using this same function.

Bool *XkbSetCompatMap* (*display, which, xkb, update_actions*)
Display * *display* ; /* connection to server */
unsigned int *which* ; /* mask of compat map components to set */
XkbDescPtr *xkb* ; /* source for compat map components */
Bool *update_actions* ; /* *True* => apply to server's keyboard map */

XkbSetCompatMap copies compatibility map information from the keyboard description in *xkb* to the server specified in *display* 's compatibility map for the device specified by the *device_spec* field of *xkb* . Unless you have specifically modified this field, it is the default keyboard device. *which* specifies the compatibility map components to be set, and is an inclusive OR of the bits shown in Table 17.2.

After updating its compatibility map for the specified device, if *update_actions* is *True,* the server applies the new compatibility map to its entire keyboard for the device to generate a new set of key semantics, compatibility state, and a new core keyboard map. If *update_actions* is *False* , the new compatibility map is not used to generate any modifications to the current device semantics, state, or core keyboard map. One reason for not applying the compatibility map immediately would be if one server was being configured to match another on a piecemeal basis; the map should not be applied until everything is updated. To force an update at a later time, use *XkbSetCompatMap* specifying *which* as zero and *update_actions* as *True* .

XkbSetCompatMap returns *True* if successful and *False* if unsuccessful. The server may report problems it encounters when processing the request subsequently via protocol errors.

To add a symbol interpretation to the list of symbol interpretations in an *XkbCompatRec* , use *XkbAddSymInterpret* .

XkbSymInterpretPtr *XkbAddSymInterpret* (*xkb, si, updateMap, changes*)
XkbDescPtr *xkb* ; /* keyboard description to be updated */
XkbSymInterpretPtr *si* ; /* symbol interpretation to be added */
Bool *updateMap* ; /* *True* =>apply compatibility map to keys */
XkbChangesPtr *changes* ; /* changes are put here */

XkbAddSymInterpret adds *si* to the list of symbol interpretations in *xkb* . If *updateMap* is *True* , it (re)applies the compatibility map to all of the keys on the key-

board. If *changes* is non- *NULL* , it reports the parts of the keyboard that were affected (unless *updateMap* is *True* , not much changes). *XkbAddSymInterpret* returns a pointer to the actual new symbol interpretation in the list or *NULL* if it failed.

Tracking Changes to the Compatibility Map

The server automatically generates *MappingNotify* events when the keyboard mapping changes. If you wish to be notified of changes to the compatibility map, you should select for *XkbCompatMapNotify* events. If you select for *XkbMapNotify* events, you no longer receive the automatically generated *MappingNotify* events. If you subsequently deselect *XkbMapNotifyEvent* delivery, you again receive *MappingNotify* events.

To receive *XkbCompatMapNotify* events under all possible conditions, use *XkbSelectEvents* (see section 4.3) and pass *XkbCompatMapNotifyMask* in both *bits_to_change* and *values_for_bits* .

To receive *XkbCompatMapNotify* events only under certain conditions, use *XkbSelectEventDetails* using *XkbCompatMapNotify* as the *event_type* and specifying the desired map changes in *bits_to_change* and *values_for_bits* using mask bits from Table 17.2.

Note that you are notified of changes you make yourself, as well as changes made by other clients.

The structure for the *XkbCompatMapNotifyEvent* is:

```
typedef struct {
      int             type;          /* Xkb extension base event code */
      unsigned long   serial;        /* X server serial number for event */
      Bool            send_event;    /* True =>
                                        synthetically generated */
      Display *       display;       /* server connection where event generated */
      Time            time;          /* server time when event generated */
      int             xkb_type;      /* XkbCompatMapNotify */
      int             device;        /* Xkb device ID, will not be
                                        XkbUseCoreKbd */
      unsigned int    changed_groups;/* number of group maps changed */
      int             first_si;      /* index to 1st changed symbol
                                        interpretation */
      int             num_si;        /* number of changed symbol
                                        interpretations */
      int             num_total_si;  /* total number of valid symbol
                                        interpretations */
} XkbCompatMapNotifyEvent;
```

changed_groups is the number of group compatibility maps that have changed. If you are maintaining a corresponding copy of the compatibility map, or get a fresh copy from the server using *XkbGetCompatMap* , *changed_groups* references *groups* [0.. *changed_groups* -1] in the *XkbCompatMapRec* structure.

first_si is the index of the first changed symbol interpretation, *num_si* is the number of changed symbol interpretations, and *num_total_si* is the total number of valid

symbol interpretations. If you are maintaining a corresponding copy of the compatibility map, or get a fresh copy from the server using *XkbGetCompatMap* , *first_si* , *num_si* , and *num_total_si* are appropriate for use with the *compat.sym_interpret* vector in this structure.

Allocating and Freeing the Compatibility Map

If you are modifying the compatibility map, you need to allocate a new compatibility map if you do not already have one available. To do so, use *XkbAllocCompatMap* .

Status *XkbAllocCompatMap* (*xkb, which, num_si*)
XkbDescPtr *xkb* ; /* keyboard description in which to allocate compat map */
unsigned int *which* ; /* mask of compatibility map components to allocate */
unsigned int *num_si* ; /* number of symbol interpretations to allocate */

xkb specifies the keyboard description for which compatibility maps are to be allocated. The compatibility map is the *compat* field in this structure.

which specifies the compatibility map components to be allocated (see *XkbGetCompatMap* , in section 17.2). *which* is an inclusive OR of the bits shown in Table 17.2.

num_si specifies the total number of entries to allocate in the symbol interpretation vector (*xkb.compat.sym_interpret*).

Note that symbol interpretations in a compatibility map (the *sym_interpret* vector of *XkbSymInterpretRec* structures) are also allocated using this same function. To ensure that there is sufficient space in the symbol interpretation vector for entries to be added, use *XkbAllocCompatMap* specifying *which* as *XkbSymInterpretMask* and the number of free symbol interpretations needed in *num_si* .

XkbAllocCompatMap returns *Success* if successful, *BadMatch* if *xkb* is *NULL* , or *BadAlloc* if errors are encountered when attempting to allocate storage.

To free an entire compatibility map or selected portions of one, use *XkbFreeCompatMap* .

void *XkbFreeCompatMap* (*xkb, which, free_map*)
XkbDescPtr *xkb* ; /* Xkb description in which to free compatibility map */
unsigned int *which* ; /* mask of compatibility map components to free */
Bool *free_map* ; /* *True* => free *XkbCompatMap* structure itself */

which specifies the compatibility map components to be freed (see *XkbGetCompatMap* , in section 17.2). *which* is an inclusive OR of the bits shown in Table 17.2

free_map indicates whether the *XkbCompatMap* structure itself should be freed. If *free_map* is *True* , *which* is ignored, all non- *NULL* compatibility map components are freed, and the *compat* field in the *XkbDescRec* referenced by *xkb* is set to *NULL* .

Chapter 18. Symbolic Names

The core protocol does not provide any information to clients other than that actually used to interpret events. This makes it difficult to write an application that presents the keyboard to a user in an easy-to-understand way. Such applications have to examine the vendor string and keycodes to determine the type of keyboard connected to the server and then examine keysyms and modifier mappings to determine the effects of most modifiers (the *Shift* , *Lock* and *Control* modifiers are defined by the core protocol but no semantics are implied for any other modifiers).

To make it easier for applications to present a keyboard to the user, Xkb supports symbolic names for most components of the keyboard extension. Most of these symbolic names are grouped into the *names* component of the keyboard description.

The XkbNamesRec Structure

The names component of the keyboard description is defined as follows:

```
#define      XkbKeyNameLength      4
#define      XkbKeyNumVirtualMods  16
#define      XkbKeyNumIndicators   32
#define      XkbKeyNumKbdGroups    4
#define      XkbMaxRadioGroups     32


typedef struct {
      char      name[XkbKeyNameLength];      /* symbolic key names */
} XkbKeyNameRec,*XkbKeyNamePtr;


typedef struct {
      char      real[XkbKeyNameLength];
                /* this key name must be in the keys array */
      char      alias[XkbKeyNameLength];
                /* symbolic key name as alias for the key */
} XkbKeyAliasRec,*XkbKeyAliasPtr;


typedef struct _XkbNamesRec {
      Atom      keycodes;      /* identifies range and meaning of keycodes */
      Atom      geometry;      /* identifies physical location, size, and shape of
      Atom      symbols;       /* identifies the symbols logically bound to the ke
      Atom      types;         /* identifies the set of key types */
      Atom      compat;        /* identifies actions for keys using core protocol
      Atom      vmods[XkbNumVirtualMods]; /* symbolic names for virtual modifiers
      Atom      indicators[XkbNumIndicators];   /* symbolic names for indicators *
      Atom      groups[XkbNumKbdGroups]; /* symbolic names for keyboard groups */
      XkbKeyNamePtr      keys;         /* symbolic key name array */
      XkbKeyAliasPtr     key_aliases;  /* real/alias symbolic name pairs array */
      Atom *    radio_groups;      /* radio group name array */
      Atom      phys_symbols;      /* identifies the symbols engraved on the keybo
```

```
      unsigned char      num_keys; /* number of keys in the  keys array */
      unsigned char      num_key_aliases;  /* number of keys in the
                                              key_aliases array */
      unsigned short     num_rg;      /* number of radio groups */
} XkbNamesRec,*XkbNamesPtr;      /*
```

The *keycodes* name identifies the range and meaning of the keycodes returned by the keyboard in question. The *geometry* name, on the other hand, identifies the physical location, size and shape of the various keys on the keyboard. As an example to distinguish between these two names, consider function keys on PC-compatible keyboards. Function keys are sometimes above the main keyboard and sometimes to the left of the main keyboard, but the same keycode is used for the key that is logically F1 regardless of physical position. Thus, all PC-compatible keyboards share a similar keycodes name but may have different geometry names.

Note

The keycodes name is intended to be a very general description of the keycodes returned by a keyboard; a single keycodes name might cover keyboards with differing numbers of keys provided all keys have the same semantics when present. For example, 101 and 102 key PC keyboards might use the same name. In these cases, applications can use the keyboard *geometry* name to determine which subset of the named keycodes is in use.

The *symbols* name identifies the symbols logically bound to the keys. The symbols name is a human or application-readable description of the intended locale or usage of the keyboard with these symbols. The *phys_symbols* name, on the other hand, identifies the symbols actually engraved on the keyboard. Given this, the *symbols* name and *phys_symbols* names might be different. For example, the description for a keyboard that has English US engravings, but that is using Swiss German symbols might have a *phys_symbols* name of "en_US" and a *symbols* name of "de_CH."

The *types* name provides some information about the set of key types (see section 15.2) that can be associated with the keyboard. In addition, each key type can have a name, and each shift level of a type can have a name. Although these names are stored in the map description with each of the types, they are accessed using the same methods as the other symbolic names.

The *compat* name provides some information about the rules used to bind actions to keys that are changed using core protocol requests.

Xkb provides symbolic names for each of the 4 keyboard groups, 16 virtual modifiers, 32 keyboard indicators, and 4 keyboard groups. These names are held in the *vmods* , *indicators* , and *groups* fixed-length arrays.

Each key has a four-byte symbolic name. All of the symbolic key names are held in the *keys* array, and *num_keys* reports the number of entries that are in the keys array. For each key, the key name links keys with similar functions or in similar positions on keyboards that report different keycodes. For example, the *F1* key may emit keycode 23 on one keyboard and keycode 86 on another. By naming this key "FK01" on both keyboards, the keyboard layout designer can reuse parts of keyboard descriptions for different keyboards.

Key aliases allow the keyboard layout designer to assign multiple key names to a single key. This allows the keyboard layout designer to refer to keys using either

their position or their "function." For example, a keyboard layout designer may wish to refer to the left arrow key on a PC keyboard using the ISO9995-5 positional specification of A31 or using the functional specification of LEFT. The *key_aliases* field holds a variable-length array of real and alias key name pairs, and the total number of entries in the *key_aliases* array is held in *num_key_aliases* . For each real and alias key name pair, the *real* field refers to the a name in the keys array, and the *alias* field refers to the alias for that key. Using the previous example, the keyboard designer may use the name A31 in the keys array, but also define the name LEFT as an alias for A31 in the *key_aliases* array.

Note

Key aliases defined in the geometry component of a keyboard mapping (see Chapter 13) override those defined in the keycodes component of the server database, which are stored in the *XkbNamesRec* (*xkb->names*). Therefore, consider the key aliases defined by the geometry before considering key aliases supplied by the *XkbNamesRec* .

A radio group is a set of keys whose behavior simulates a set of radio buttons. Once a key in a radio group is pressed, it stays logically depressed until another key in the group is pressed, at which point the previously depressed key is logically released. Consequently, at most one key in a radio group can be logically depressed at one time.

Each radio group in the keyboard description can have a name. These names are held in the variable-length array *radio_groups* , and *num_rg* tells how many elements are in the *radio_groups* array.

Symbolic Names Masks

Xkb provides several functions that work with symbolic names. Each of these functions uses a mask to specify individual fields of the structures described above. These masks and their relationships to the fields in a keyboard description are shown in Table 18.1.

Table 18.1. Symbolic Names Masks

Mask Bit	Value	Keyboard Component	Field
XkbKeycodesNameMask	(1<<0)	Xkb->names	keycodes
XkbGeometryNameMask	(1<<1)	Xkb->names	geometry
XkbSymbolsNameMask	(1<<2)	Xkb->names	symbols
XkbPhysSymbolsNameMask	(1<<3)	Xkb->names	phys_symbols
XkbTypesNameMask	(1<<4)	Xkb->names	type
XkbCompatNameMask	(1<<5)	Xkb->names	compat
XkbKeyTypeNamesMask	(1<<6)	Xkb->map	type[*].name
XkbKTLevelNamesMask	(1<<7)	Xkb->map	type[*].lvl_names[*]
XkbIndicatorNamesMask	(1<<8)	Xkb->names	indicators[*]
XkbKeyNamesMask	(1<<9)	Xkb->names	keys[*], num_keys
XkbKeyAliasesMask	(1<<10)	Xkb->names	key_aliases[*], num_key_aliases
XkbVirtualModNamesMask	(1<<11)	Xkb->names	vmods[*]
XkbGroupNamesMask	(1<<12)	Xkb->names	groups[*]
XkbRGNamesMask	(1<<13)	Xkb->names	radio_groups[*], num_rg
XkbComponentNamesMask	(0x3f)	Xkb->names	keycodes, geometry, symbols, physical symbols, types, and compatibility map
XkbAllNamesMask	(0x3fff)	Xkb->names	all name components

Getting Symbolic Names From the Server

To obtain symbolic names from the server, use *XkbGetNames* .

Status *XkbGetNames* (*dpy, which, Xkb*)
Display * *dpy* ; /* connection to the X server */
unsigned int *which* ; /* mask of names or map components to be updated */
XkbDescPtr *xkb* /* keyboard description to be updated */

XkbGetNames retrieves symbolic names for the components of the keyboard extension from the X server. The *which* parameter specifies the name components to be updated in the *xkb* parameter, and is the bitwise inclusive OR of the valid names mask bits defined in Table 18.1.

If the *names* field of the keyboard description *xkb* is *NULL* , *XkbGetNames* allocates and initializes the *names* component of the keyboard description before obtaining the values specified by *which* . If the *names* field of *xkb* is not *NULL* , *XkbGetNames* obtains the values specified by *which* and copies them into the keyboard description *Xkb* .

If the *map* component of the *xkb* parameter is *NULL* , *XkbGetNames* does not retrieve type or shift level names, even if *XkbKeyTypeNamesMask* or *XkbKTLevelNamesMask* are set in *which* .

XkbGetNames can return *Success* , or *BadAlloc* , *BadLength* , *BadMatch* , and *BadImplementation* errors.

To free symbolic names, use *XkbFreeNames* (see section 18.6)

Changing Symbolic Names on the Server

To change the symbolic names in the server, first modify a local copy of the keyboard description and then use either *XkbSetNames,* or, to save network traffic, use a *XkbNameChangesRec* structure and call *XkbChangeNames* to download the changes to the server. *XkbSetNames* and *XkbChangeNames* can generate *BadAlloc* , *BadAtom* , *BadLength* , *BadMatch,* and *BadImplementation* errors.

Bool *XkbSetNames* (*dpy, which, first_type, num_types, xkb*)

Display * *dpy* ; /* connection to the X server */

unsigned int *which* ; /* mask of names or map components to be changed */

unsigned int *first_type* ; /* first type whose name is to be changed */

unsigned int *num_types* ; /* number of types for which names are to be changed */

XkbDescPtr *xkb* ; /* keyboard description from which names are to be taken */

Use *XkbSetNames* to change many names at the same time. For each bit set in *which* , *XkbSetNames* takes the corresponding value (or values in the case of arrays) from the keyboard description *xkb* and sends it to the server.

The *first_type* and *num_types* arguments are used only if *XkbKeyTypeNamesMask* or *XkbKTLevelNamesMask* is set in *which* and specify a subset of the types for which the corresponding names are to be changed. If either or both of these mask bits are set but the specified types are illegal, *XkbSetNames* returns *False* and does not update any of the names specified in *which* . The specified types are illegal if *xkb* does not include a map component or if *first_type* and *num_types* specify types that are not defined in the keyboard description.

The XkbNameChangesRec Structure

The *XkbNameChangesRec* allows applications to identify small modifications to the symbolic names and effectively reduces the amount of traffic sent to the server:

```
typedef struct _XkbNameChanges {
      unsigned int      changed;            /* name components that have
                                               changed */
      unsigned char      first_type;        /* first key type with a new
                                               name */
      unsigned char      num_types;         /* number of types with new
                                               names */
      unsigned char      first_lvl;         /* first key type with new level
                                               names */
      unsigned char      num_lvls;          /* number of key types with new
                                               level names */
      unsigned char      num_aliases;       /* if key aliases changed,
                                               total number of key aliases */
      unsigned char      num_rg;            /* if radio groups changed, total
                                               number of radio groups */
      unsigned char      first_key;         /* first key with a new name */
      unsigned char      num_keys;          /* number of keys with new names
                                               */
      unsigned short      changed_vmods;    /* mask of virtual
                                               modifiers for which names have chan
      unsigned long      changed_indicators;  /* mask of indicators
                                                 for which names were changed */
      unsigned char       changed_groups;   /* mask of groups for
                                               which names were changed */
} XkbNameChangesRec, *XkbNameChangesPtr
```

The *changed* field specifies the name components that have changed and is the bitwise inclusive OR of the valid names mask bits defined in Table 18.1. The rest of the fields in the structure specify the ranges that have changed for the various kinds of symbolic names, as shown in Table 18.2.

Table 18.2. XkbNameChanges Fields

Mask	Fields	Component	Field
XkbKeyTypeNamesMask	first_type, num_types	Xkb->map	type[*].name
XkbKTLevelNamesMask	first_lvl, num_lvls	Xkb->map	type[*].lvl_names[*]
XkbKeyAliasesMask	num_aliases	Xkb->names	key_aliases[*]
XkbRGNamesMask	num_rg	Xkb->names	radio_groups[*]
XkbKeyNamesMask	first_key, num_keys	Xkb->names	keys[*]
XkbVirtualModNames-Mask	changed_vmods	Xkb->names	vmods[*]
XkbIndicatorNamesMask	changed_indicators	Xkb->names	indicators[*]
XkbGroupNamesMask	changed_groups	Xkb->names	groups[*]

XkbChangeNames provides a more flexible method for changing symbolic names than *XkbSetNames* and requires the use of an *XkbNameChangesRec* structure.

Bool *XkbChangeNames* (*dpy, xkb, changes*)

Display * *dpy* ; /* connection to the X server */

XkbDescPtr *xkb* ; /* keyboard description from which names are to be taken */

XkbNameChangesPtr *changes* ; /* names map components to be updated on the server */

XkbChangeNames copies any names specified by *changes* from the keyboard description, *xkb* , to the X server specified by *dpy* . *XkbChangeNames* aborts and returns *False* if any illegal type names or type shift level names are specified by *changes* .

Tracking Name Changes

Whenever a symbolic name changes in the server's keyboard description, the server sends a *XkbNamesNotify* event to all interested clients. To receive name notify events, use *XkbSelectEvents* (see section 4.3) with *XkbNamesNotifyMask* in both the *bits_to_change* and *values_for_bits* parameters.

To receive events for only specific names, use *XkbSelectEventDetails* . Set the *event_type* parameter to *XkbNamesNotify* , and set both the *bits_to_change* and *values_for_bits* detail parameter to a mask composed of a bitwise OR of masks in Table 18.1.

The structure for the *XkbNamesNotify* event is defined as follows:

```
typedef struct {
      int      type;                 /* Xkb extension base event code */
      unsigned long      serial;     /* X server serial number for
                                        event */
      Bool      send_event;          /* True
                                        => synthetically generated */
      Display *      display;        /* server connection where event
                                        generated */
      Time      time;                /* server time when event generated */
      int      xkb_type;             /* XkbNamesNotify */
      int      device;               /* Xkb device ID, will not be
                                        XkbUseCoreKbd */
      unsigned int      changed;     /* mask of name components
that have changed */
      int      first_type;           /* first key type with a new name */
      int      num_types;            /* number of types with new names */
      int      first_lvl;            /* first key type with new level names */
      int      num_lvls;             /* number of key types with new level names
      int      num_aliases;          /* if key aliases changed, total number
                                        of key aliases */
      int      num_radio_groups;     /* if radio groups changed,
                                        total number of radio groups */
      unsigned int      changed_vmods;  /* mask of virtual modifiers for
                                           which names have changed */
      unsigned int      changed_groups; /* mask of groups for
                                           which names were changed */
      unsigned int      changed_indicators;  /* mask of indicators for which
```

```
                                                    names were changed */
      int      first_key;              /* first key with a new name */
      int      num_keys;               /* number of keys with new names */
} XkbNamesNotifyEvent;
```

The *changed* field specifies the name components that have changed and is the bitwise inclusive OR of the valid names mask bits defined in Table 18.1. The other fields in this event are interpreted as the like-named fields in an *XkbNameChanges-Rec* , as previously defined.

When your application receives a X *kbNamesNotify* event, you can note the changed names in a changes structure using *XkbNoteNameChanges* .

void *XkbNoteNameChanges* (*old* , *new* , *wanted*)
XkbNameChangesPtr *old* ; /* *XkbNameChanges* structure to be updated */
XkbNamesNotifyEvent * *new* ; /* event from which changes are to be copied */
unsigned int *wanted* ; /* types of names for which changes are to be noted */

The *wanted* parameter is the bitwise inclusive OR of the valid names mask bits shown in Table 18.1. *XkbNoteNameChanges* copies any changes that are reported in *new* and specified in *wanted* into the changes record specified by *old* .

To update the local copy of the keyboard description with the actual values, pass to *XkbGetNameChanges* the results of one or more calls to *XkbNoteNameChanges* .

Status *XkbGetNameChanges* (*dpy* , *xkb* , *changes*)
Display * *dpy* ; /* connection to the X server */
XkbDescPtr *xkb* ; /* keyboard description to which names are copied */
XkbNameChangesPtr *changes* ; /* names components to be obtained from the server */

XkbGetNameChanges examines the *changes* parameter, retrieves the necessary information from the server, and places the results into the *xkb* keyboard description.

XkbGetNamesChanges can generate *BadAlloc* , *BadImplementation,* and *BadMatch* errors.

Allocating and Freeing Symbolic Names

Most applications do not need to directly allocate symbolic names structures. Do not allocate a names structure directly using *malloc* or *Xmalloc* if your application changes the number of key aliases or radio groups or constructs a symbolic names structure without loading the necessary components from the X server. Instead use *XkbAllocNames* .

Status *XkbAllocNames* (*xkb, which, num_rg, num_key_aliases)*
XkbDescPtr *xkb;* /* keyboard description for which names are to be allocated */
unsigned int *which;* /* mask of names to be allocated */
int *num_rg;* /* total number of radio group names needed */
int *num_key_aliases;* /* total number of key aliases needed */

XkbAllocNames can return *BadAlloc* , *BadMatch,* and *BadValue* errors. The *which* parameter is the bitwise inclusive OR of the valid names mask bits defined in Table 18.1.

Do not free symbolic names structures directly using *free* or *XFree* . Use *XkbFreeNames* instead.

void *XkbFreeNames* (*xkb, which, free_map)*
XkbDescPtr *xkb* ; /* keyboard description for which names are to be freed */
unsigned int *which* ; /* mask of names components to be freed */
Bool *free_map* ; /* *True* => XkbNamesRec structure itself should be freed */

The *which* parameter is the bitwise inclusive OR of the valid names mask bits defined in Table 18.1.

Chapter 19. Replacing a Keyboard "On the Fly"

Some operating system and X server implementations allow "hot plugging" of input devices. When using these implementations, input devices can be unplugged and new ones plugged in without restarting the software that is using those devices. There is no provision in the standard X server for notification of client programs if input devices are unplugged and/or new ones plugged in. In the case of the X keyboard, this could result in the X server having a keymap that does not match the new keyboard.

If the X server implementation supports the X input device extension, a client program may also change the X keyboard programmatically. The XChangeKeyboardDevice input extension request allows a client to designate an input extension keyboard device as the X keyboard, in which case the old X keyboard device becomes inaccessible except via the input device extension. In this case, core protocol *XMappingNotify* and input extension *XChangeDeviceNotify* events are generated to notify all clients that a new keyboard with a new keymap has been designated.

When a client opens a connection to the X server, the server reports the minimum and maximum keycodes. The server keeps track of the minimum and maximum keycodes last reported to each client. When delivering events to a particular client, the server filters out any events that fall outside of the valid range for the client.

Xkb provides an *XkbNewKeyboardNotify* event that reports a change in keyboard geometry and/or the range of supported keycodes. The server can generate an *XkbNewKeyboardNotify* event when it detects a new keyboard or in response to an *XkbGetKeyboardByName* request that loads a new keyboard description. Selecting for *XkbNewKeyboardNotify* events allows Xkb-aware clients to be notified whenever a keyboard change occurs that may affect the keymap.

When a client requests *XkbNewKeyboardNotify* events, the server compares the range of keycodes for the current keyboard to the range of keycodes that are valid for the client. If they are not the same, the server immediately sends the client an *XkbNewKeyboardNotify* event. Even if the "new" keyboard is not new to the server, it is new to this particular client.

When the server sends an *XkbNewKeyboardNotify* event to a client to inform it of a new keycode range, it resets the stored range of legal keycodes for the client to the keycode range reported in the event; it does not reset this range for the client if it does not sent an *XkbNewKeyboardNotify* event to a client. Because Xkb-unaware clients and Xkb-aware clients that do not request *XkbNewKeyboardNotify* events are never sent these events, the server’s notion of the legal keycode range never changes, and these clients never receive events from keys that fall outside of their notion of the legal keycode range.

Clients that have not selected to receive *XkbNewKeyboardNotify* events do, however, receive the *XkbNewKeyboardNotify* event when a keyboard change occurs. Clients that have not selected to receive this event also receive numerous other events detailing the individual changes that occur when a keyboard change occurs.

Clients wishing to track changes in *min_key_code* and *max_key_code* must watch for both *XkbNewKeyboardNotify* and *XkbMapNotify* events, because a simple map-

ping change causes an *XkbMapNotify* event and may change the range of valid keycodes, but does not cause an *XkbNewKeyboardNotify* event. If a client does not select for *XkbNewKeyboardNotify* events, the server restricts the range of keycodes reported to the client.

In addition to filtering out-of-range key events, Xkb:

- Adjusts core protocol *MappingNotify* events to refer only to keys that match the stored legal range.
- Reports keyboard mappings for keys that match the stored legal range to clients that issue a core protocol *GetKeyboardMapping* request.
- Reports modifier mappings only for keys that match the stored legal range to clients that issue a core protocol *GetModifierMapping* request.
- Restricts the core protocol *ChangeKeyboardMapping* and *SetModifierMapping* requests to keys that fall inside the stored legal range.

In short, Xkb does everything possible to hide from Xkb-unaware clients the fact that the range of legal keycodes has changed, because such clients cannot be expected to deal with them. Xkb events and requests are not modified in this manner; all Xkb events report the full range of legal keycodes. No requested Xkb events are discarded, and no Xkb requests have their keycode range clamped.

The structure for the *XkbNewKeyboardNotify* event is defined as follows:

```
typedef struct _XkbNewKeyboardNotify {
      int            type;         /* Xkb extension base event code */
      unsigned long  serial;       /* X server serial number for event*/
      Bool           send_event;   /* True
                                      => synthetically generated */
      Display *      display;      /* server connection where event generated */
      Time           time;         /* server time when event generated */
      int            xkb_type;  /* XkbNewKeyboardNotify */
      int            device;       /* device ID of new keyboard */
      int            old_device;   /* device ID of old keyboard */
      int            min_key_code; /* min keycode of new keyboard */
      int            max_key_code; /* max keycode of new keyboard */
      int            old_min_key_code; /* min keycode of old keyboard */
      int            old_max_key_code; /* max keycode of old keyboard */
      unsigned int             changed; /* changed aspects - see masks below */
      char            req_major;   /* major request that caused change */
      char            req_minor;   /* minor request that caused change */
} XkbNewKeyboardNotifyEvent;
```

To receive name notify events, use *XkbSelectEvents* (see section 4.3) with *XkbNewKeyboardNotifyMask* in both the *bits_to_change* and *values_for_bits* parameters. To receive events for only specific names, use *XkbSelectEventDetails* . Set the *event_type* parameter to *XkbNewKeyboardNotify* , and set both the *bits_to_change* and *values_for_bits* detail parameter to a mask composed of a bitwise OR of masks in Table 19.1.

Table 19.1. XkbNewKeyboardNotifyEvent Details

XkbNewKeyboardNotify Event Details	Value	Circumstances
XkbNKN_KeycodesMask	(1L<<0)	Notification of keycode range changes wanted
XkbNKN_GeometryMask	(1L<<1)	Notification of geometry changes wanted
XkbNKN_DeviceIDMask	(1L<<2)	Notification of device ID changes wanted
XkbNKN_AllChangesMask	(0x7)	Includes all of the above masks

The *req_major* and *req_minor* fields indicate what type of keyboard change has occurred.

If *req_major* and *req_minor* are zero, the device change was not caused by a software request to the server — a spontaneous change has occurred, such as hot-plugging a new device. In this case, *device* is the device identifier for the new, current X keyboard device, but no implementation-independent guarantee can be made about *old_device* . *old_device* may be identical to *device* (an implementor is permitted to reuse the device specifier when the device changes); or it may be different. Note that *req_major* and *req_minor* being zero do not necessarily mean that the physical keyboard device has changed; rather, they only imply a spontaneous change outside of software control (some systems have keyboards that can change personality at the press of a key).

If the keyboard change is the result of an X Input Extension *ChangeKeyboardDevice* request, *req_major* contains the input extension major opcode, and *req_minor* contains the input extension request number for *X_ChangeKeyboardDevice* . In this case, *device* and *old_device* are different, with *device* being the identifier for the new, current X keyboard device, and *old_device* being the identifier for the former device.

If the keyboard change is the result of an *XkbGetKeyboardByName* function call, which generates an *X_kbGetKbdByName* request, *req_major* contains the Xkb extension base event code (see section 2.4), and *req_minor* contains the event code for the Xkb extension request *X_kbGetKbdByName* . *device* contains the device identifier for the new device, but nothing definitive can be said for *old_device* ; it may be identical to *device* , or it may be different, depending on the implementation.

Chapter 20. Server Database of Keyboard Components

The X server maintains a database of keyboard components, identified by component type. The database contains all the information necessary to build a complete keyboard description for a particular device, as well as to assemble partial descriptions. Table 20.1 identifies the component types and the type of information they contain.

Table 20.1. Server Database Keyboard Components

Component Type	Component Primary Contents	May also contain
Keymap	Complete keyboard description	
	Normally assembled using a complete component from each of the other types	
Keycodes	Symbolic name for each key	Aliases for some keys
		Symbolic names for indicators
	Minimum and maximum legal keycodes	Description of indicators physically present
Types	Key types	Real modifier bindings and symbolic names for some virtual modifiers
Compatibility	Rules used to assign actions to keysyms	Maps for some indicators
		Real modifier bindings and symbolic names for some virtual modifiers
Symbols	Symbol mapping for keyboard keys	Explicit actions and behaviors for some keys
	Modifier mapping	Real modifier bindings and symbolic names for some virtual modifiers
	Symbolic names for groups	
Geometry	Layout of the keyboard	Aliases for some keys; overrides keycodes component aliases
		Symbolic names for some indicators
		Description of indicators physically present

While a keymap is a database entry for a complete keyboard description, and therefore logically different from the individual component database entries, the rules for processing keymap entries are identical to those for the individual components. In the discussion that follows, the term component is used to refer to either individual components or a keymap.

There may be multiple entries for each of the component types. An entry may be either *complete* or *partial* . Partial entries describe only a piece of the corresponding keyboard component and are designed to be combined with other entries of the same type to form a complete entry.

For example, a partial symbols map might describe the differences between a common ASCII keyboard and some national layout. Such a partial map is not useful on its own because it does not include those symbols that are the same on both the ASCII and national layouts (such as function keys). On the other hand, this partial map can be used to configure *any* ASCII keyboard to use a national layout.

When a keyboard description is built, the components are processed in the order in which they appear in Table 20.1; later definitions override earlier ones.

Component Names

Component names have the form " *class(member)* " where *class* describes a subset of the available components for a particular type and the optional *member* identifies a specific component from that subset. For example, the name "atlantis(acme)" for a symbols component might specify the symbols used for the atlantis national keyboard layout by the vendor "acme." Each class has an optional *default* member — references that specify a class but not a member refer to the default member of the class, if one exists. Xkb places no constraints on the interpretation of the class and member names used in component names.

The *class* and *member* names are both specified using characters from the Latin-1 character set. Xkb implementations must accept all alphanumeric characters, minus (‘-’) and underscore (‘_’) in class or member names, and must not accept parentheses, plus, vertical bar, percent sign, asterisk, question mark, or white space. The use of other characters is implementation-dependent.

Listing the Known Keyboard Components

You may ask the server for a list of components for one or more component types. The request takes the form of a set of patterns, one pattern for each of the component types, including a pattern for the complete keyboard description. To obtain this list, use *XkbListComponents* .

XkbComponentListPtr *XkbListComponents* (*dpy* , *device_spec* , *ptrns* , *max_inout*)

Display * *dpy* ; /* connection to X server */

unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */

XkbComponentNamesPtr *ptrns* ; /* namelist for components of interest */

int * *max_inout* ; /* max # returned names, # left over */

XkbListComponents queries the server for a list of component names matching the patterns specified in *ptrns* . It waits for a reply and returns the matching component names in an *XkbComponentListRec* structure. When you are done using the structure, you should free it using *XkbFreeComponentList* . *device_spec* indicates a particular device in which the caller is interested. A server is allowed (but not required) to restrict its reply to portions of the database that are relevant for that particular device.

ptrns is a pointer to an *XkbComponentNamesRec* , described below. Each of the fields in *ptrns* contains a pattern naming the components of interest. Each of the patterns is composed of characters from the ISO *Latin1* encoding, but can contain only parentheses, the wildcard characters ' *?* ' and ' * ', and characters permitted in a component class or member name (see section 20.1). A pattern may be *NULL* , in which case no components for that type is returned. Pattern matches with component names are case sensitive. The ' *?* ' wildcard matches any single character, except a left or right parenthesis; the ' * ' wildcard matches any number of characters, except a left or right parenthesis. If an implementation allows additional characters in a component class or member name other than those required by the Xkb extension (see section 20.1), the result of comparing one of the additional characters to either of the wildcard characters is implementation-dependent.

If a pattern contains illegal characters, the illegal characters are ignored. The matching process is carried out as if the illegal characters were omitted from the pattern.

max_inout is used to throttle the amount of data passed to and from the server. On input, it specifies the maximum number of names to be returned (the total number of names in all component categories). Upon return from *XkbListComponents* , *max_inout* contains the number of names that matched the request but were not returned because of the limit.

The component name patterns used to describe the request are passed to *XkbListComponents* using an *XkbComponentNamesRec* structure. This structure has no special allocation constraints or interrelationships with other structures; allocate and free this structure using standard *malloc* and *free* calls or their equivalent:

```
typedef struct _XkbComponentNames {
      char *       keymap;    /* keymap names */
      char *       keycodes;  /* keycode names */
      char *       types;     /* type names */
      char *       compat;    /* compatibility map names */
      char *       symbols;   /* symbol names */
      char *       geometry;  /* geometry names */
} XkbComponentNamesRec, *XkbComponentNamesPtr;
```

XkbListComponents returns a pointer to an *XkbComponentListRec* :

```
typedef struct _XkbComponentList {
      int                  num_keymaps;     /* number of entries in keymap */
      int                  num_keycodes;    /* number of entries in keycodes */
      int                  num_types;       /* number of entries in types */
      int                  num_compat;      /* number of entries in compat */
```

```
      int                 num_symbols;     /* number of entries in symbols */
      int                 num_geometry;    /* number of entries in geometry;
      XkbComponentNamePtr  keymap;         /* keymap names */
      XkbComponentNamePtr  keycodes;       /* keycode names */
      XkbComponentNamePtr  types;          /* type names */
      XkbComponentNamePtr  compat;         /* compatibility map names */
      XkbComponentNamePtr  symbols;        /* symbol names */
      XkbComponentNamePtr  geometry;       /* geometry names */
} XkbComponentListRec, *XkbComponentListPtr;


typedef struct _XkbComponentName {
      unsigned short         flags;     /* hints regarding component name */
      char *                 name;      /* name of component */
} XkbComponentNameRec, *XkbComponentNamePtr;
```

Note that the structure used to specify patterns on input is an *XkbComponent-NamesRec* , and that used to hold the individual component names upon return is an *XkbComponentNameRec* (no trailing ‘s’ in Name).

When you are done using the structure returned by *XkbListComponents* , free it using *XkbFreeComponentList* .

void *XkbFreeComponentList* (list)

XkbComponentListPtr list; /* pointer to *XkbComponentListRec* to free */

Component Hints

A set of flags is associated with each component; these flags provide additional hints about the component’s use. These hints are designated by bit masks in the flags field of the *XkbComponentNameRec* structures contained in the *XkbComponentListRec* returned from *XkbListComponents* . The least significant byte of the flags field has the same meaning for all types of keyboard components; the interpretation of the most significant byte is dependent on the type of component. The flags bits are defined in Table 20.2. The symbols hints in Table 20.2 apply only to partial symbols components (those with *XkbLC_Partial* also set); full symbols components are assumed to specify all of the pieces.

The alphanumeric, modifier, keypad or function keys symbols hints should describe the primary intent of the component designer and should not be simply an exhaustive list of the kinds of keys that are affected. For example, national keyboard layouts affect primarily alphanumeric keys, but many affect a few modifier keys as well; such mappings should set only the *XkbLC_AlphanumericKeys* hint. In general, symbols components should set only one of the four flags (*XkbLC_AlternateGroup* may be combined with any of the other flags).

Table 20.2. XkbComponentNameRec Flags Bits

Component Type	Component Hints (flags)	Meaning	Value
All Components	*XkbLC_Hidden*	Do not present to user	(1L<<0)
	XkbLC_Default	Default member of class	(1L<<1)
	XkbLC_Partial	Partial component	(1L<<2)
Keymap	none		
Keycodes	none		
Types	none		
Compatibility	none		
Symbols	*XkbLC_AlphanumericKeys*	Bindings primarily for alphanumeric keyboard section	(1L<<8)
	XkbLC_ModifierKeys	Bindings primarily for modifier keys	(1L<<9)
	XkbLC_KeypadKeys	Bindings primarily for numeric keypad keys	(1L<<10)
	XkbLC_FunctionKeys	Bindings primarily for function keys	(1L<<11)
	XkbLC_AlternateGroup	Bindings for an alternate group	(1L<<12)
Geometry	none		

Building a Keyboard Description Using the Server Database

A client may request that the server fetch one or more components from its database and use those components to build a new server keyboard description. The new keyboard description may be built from scratch, or it may be built starting with the current keyboard description for a particular device. Once the keyboard description is built, all or part of it may be returned to the client. The parts returned to the client need not include all of the parts used to build the description. At the time it requests the server to build a new keyboard description, a client may also request that the server use the new description internally to replace the current keyboard description for a specific device, in which case the behavior of the device changes accordingly.

To build a new keyboard description from a set of named components, and to optionally have the server use the resulting description to replace an active one, use *XkbGetKeyboardByName* .

XkbDescPtr *XkbGetKeyboardByName* (*dpy* , *device_spec* , *names* , *want* , *need* , *load*)

Display * *dpy* ; /* connection to X server */

unsigned int *device_spec* ; /* device ID, or *XkbUseCoreKbd* */

XkbComponentNamesPtr *names* ; /* names of components to fetch */

unsigned int *want* ; /* desired structures in returned record */

unsigned int *need* ; /* mandatory structures in returned record */

Bool *load* ; /* *True* => load into *device_spec* */

names contains a set of expressions describing the keyboard components the server should use to build the new keyboard description. *want* and *need* are bit fields describing the parts of the resulting keyboard description that should be present in the returned *XkbDescRec* .

The individual fields in *names* are *component expressions* composed of keyboard component names (no wildcarding as may be used in *XkbListComponents*), the special component name symbol '%', and the special operator characters ' + ' and ' | '. A component expression is parsed left to right, as follows:

- The special component name " *computed* " may be used in *keycodes* component expressions and refers to a component consisting of a set of keycodes computed automatically by the server as needed.
- The special component name " *canonical* " may be used in *types* component expressions and refers to a partial component defining the four standard key types: *ALPHABETIC* , *ONE_LEVEL* , *TWO_LEVEL* , and *KEYPAD* .
- The special component name ' *%* ' refers to the keyboard description for the device specified in *device_spec* or the keymap names component. If a keymap names component is specified that does not begin with '+' or '|' and does not contain ' *%* ', then ' *%* ' refers to the description generated by the keymap names component. Otherwise, it refers to the keyboard description for *device_spec* .
- The ' + ' operator specifies that the following component should *override* the currently assembled description; any definitions that are present in both components are taken from the second.
- The ' | ' operator specifies that the next specified component should *augment* the currently assembled description; any definitions that are present in both components are taken from the first.
- If the component expression begins with an operator, a leading ' *%* ' is implied.
- If any unknown or illegal characters appear anywhere in the expression, the entire expression is invalid and is ignored.

For example, if *names->symbols* contained the expression "+de", it specifies that the default member of the "de" class of symbols should be applied to the current keyboard mapping, overriding any existing definitions (it could also be written "+de(default)").

Here is a slightly more involved example: the expression "acme(ascii)+de(basic)|iso9995-3" constructs a German (de) mapping for the ASCII keyboard supplied by

the "acme" vendor. The new definition begins with the symbols for the ASCII keyboard for Acme (*acme(ascii)*), overrides them with definitions for the basic German keyboard (*de(basic)*), and then applies the definitions from the default iso9995-3 keyboard (*iso9995-3*) to any undefined keys or groups of keys (part three of the iso9995 standard defines a common set of bindings for the secondary group, but allows national layouts to override those definitions where necessary).

Note

The interpretation of the above expression components (acme, ascii, de, basic, iso9995-3) is not defined by Xkb; only the operations and their ordering are.

Note that the presence of a keymap *names* component that does not contain ‘ *%* ’ (either explicit or implied by virtue of an expression starting with an operator) indicates a description that is independent of the keyboard description for the device specified in *device_spec* . The same is true of requests in which the keymap names component is empty and all five other names components contain expressions void of references to ‘ *%* ’. Requests of this form allow you to deal with keyboard definitions independent of any actual device.

The server parses all non- *NULL* fields in *names* and uses them to build a keyboard description. However, before parsing the expressions in *names* , the server ORs the bits in *want* and *need* together and examines the result in relationship to the expressions in *names* . Table 20.3 identifies the components that are required for each of the possible bits in *want* or *need* . If a required component has not been specified in the *names* structure (the corresponding field is *NULL*), the server substitutes the expression " *%* ", resulting in the component values being taken from *device_spec* . In addition, if *load* is *True* , the server modifies *names* if necessary (again using a " *%* " entry) to ensure all of the following fields are non- *NULL* : *types* , *keycodes* , *symbols* , and *compat* .

Table 20.3. Want and Need Mask Bits and Required Names Components

want or need mask bit	Required names Components	value
XkbGBN_TypesMask	Types	(1L<<0)
XkbGBN_CompatMapMask	Compat	(1L<<1)
XkbGBN_ClientSymbolsMask	Types + Symbols + Keycodes	(1L<<2)
XkbGBN_ServerSymbolsMask	Types + Symbols + Keycodes	(1L<<3)
XkbGBN_SymbolsMask	Symbols	(1L<<1)
XkbGBN_IndicatorMapMask	Compat	(1L<<4)
XkbGBN_KeyNamesMask	Keycodes	(1L<<5)
XkbGBN_GeometryMask	Geometry	(1L<<6)
XkbGBN_OtherNamesMask	Types + Symbols + Keycodes + Compat + Geometry	(1L<<7)
XkbGBN_AllComponentsMask		(0xff)

need specifies a set of keyboard components that the server must be able to resolve in order for *XkbGetKeyboardByName* to succeed; if any of the components specified in *need* cannot be successfully resolved, *XkbGetKeyboardByName* fails.

want specifies a set of keyboard components that the server should attempt to resolve, but that are not mandatory. If the server is unable to resolve any of these components, *XkbGetKeyboardByName* still succeeds. Bits specified in *want* that are also specified in *need* have no effect in the context of *want* .

If *load* is *True* , the server updates its keyboard description for *device_spec* to match the result of the keyboard description just built. If load is *False* , the server's description for device *device_spec* is not updated. In all cases, the parts specified by *want* and *need* from the just-built keyboard description are returned.

The *names* structure in an *XkbDescRec* keyboard description record (see Chapter 18) contains one field for each of the five component types used to build a keyboard description. When a keyboard description is built from a set of database components, the corresponding fields in this *names* structure are set to match the expressions used to build the component.

The entire process of building a new keyboard description from the server database of components and returning all or part of it is diagrammed in Figure 20.1:


Augment names to supply component names required by want and need but not supplied in request
load
False
True
Initial Request:
device_spec
names
want
need
load
Augment names to supply required component names not supplied in request
Build keyboard description from expressions in names
load
False
True
Replace device_spec active keyboard description with newly built description
Build keyboard description for client by extracting structures specified in want and need

Building a New Keyboard Description from the Server Database

The information returned to the client in the *XkbDescRec* is essentially the result of a series of calls to extract information from a fictitious device whose description matches the one just built. The calls corresponding to each of the mask bits are summarized in Table 20.4, together with the *XkbDescRec* components that are filled in.

Table 20.4. XkbDescRec Components Returned for Values of Want & Needs

Request (want+need)	Fills in Xkb components	Equivalent Function Call
XkbGBN_TypesMask	map.types	XkbGetUpdatedMap(dpy, XkbTypesMask, Xkb)
XkbGBN_ServerSymbolsMask	server	XkbGetUpdatedMap(dpy, XkbAllClientInfoMask, Xkb)
XkbGBN_ClientSymbolsMask	map, including map.types	XkbGetUpdatedMap(dpy, XkbAllServerInfoMask, Xkb)
XkbGBN_IndicatorMaps	indicators	XkbGetIndicatorMap(dpy, XkbAllIndicators, Xkb)
XkbGBN_CompatMapMask	compat	XkbGetCompatMap(dpy, XkbAllCompatMask, Xkb)
XkbGBN_GeometryMask	geom	XkbGetGeometry(dpy, Xkb)
XkbGBN_KeyNamesMask	names.keys names.key_aliases	XkbGetNames(dpy, XkbKeyNamesMask | XkbKeyAliasesMask, Xkb)
XkbGBN_OtherNamesMask	names.keycodes names.geometry names.symbols names.types map.types[*].lvl_names[*] names.compat names.vmods names.indicators names.groups names.radio_groups names.phys_symbols	XkbGetNames(dpy, XkbAllNamesMask & ~(XkbKeyNamesMask | XkbKeyAliasesMask), Xkb)

There is no way to determine which components specified in *want* (but not in *need*) were actually fetched, other than breaking the call into successive calls to *XkbGetKeyboardByName* and specifying individual components.

XkbGetKeyboardByName always sets *min_key_code* and *max_key_code* in the returned *XkbDescRec* structure.

XkbGetKeyboardByName is synchronous; it sends the request to the server to build a new keyboard description and waits for the reply. If successful, the return value is non-*NULL*. *XkbGetKeyboardByName* generates a *BadMatch* protocol error if errors are encountered when building the keyboard description.

If you simply want to obtain information about the current keyboard device, rather than generating a new keyboard description from elements in the server database, use *XkbGetKeyboard* (see section 6.2).

XkbDescPtr *XkbGetKeyboard* (*dpy* , *which* , *device_spec*)
Display * *dpy* ; /* connection to X server */
unsigned int *which* ; /* mask of components of *XkbDescRec* of interest */
unsigned int *device_spec* ; /* device ID */

XkbGetKeyboard is used to read the current description for one or more components of a keyboard device. It calls *XkbGetKeyboardByName* as follows:

XkbGetKeyboardByName (*dpy* , *device_spec* , *NULL* , *which* , *which* , *False*).

Chapter 21. Attaching Xkb Actions to X Input Extension Devices

The X input extension allows an X server to support multiple keyboards, as well as other input devices, in addition to the core X keyboard and pointer. The input extension categorizes devices by grouping them into classes. Keyboards and other input devices with keys are classified as KeyClass devices by the input extension. Other types of devices supported by the input extension include, but are not limited to: mice, tablets, touchscreens, barcode readers, button boxes, trackballs, identifier devices, data gloves, and eye trackers. Xkb provides additional control over all X input extension devices, whether they are *KeyClass* devices or not, as well as the core keyboard and pointer.

If an X server implements support for both the input extension and Xkb, the server implementor determines whether interaction between Xkb and the input extension is allowed. Implementors are free to restrict the effects of Xkb to only the core X keyboard device or allow interaction between Xkb and the input extension.

Several types of interaction between Xkb and the input extension are defined by Xkb. Some or all may be allowed by the X server implementation.

Regardless of whether the server allows interaction between Xkb and the input extension, the following access is provided:

- Xkb functionality for the core X keyboard device and its mapping is accessed via the functions described in the other chapters of this specification.
- Xkb functionality for the core X pointer device is accessed via the XkbGetDeviceInfo and XkbSetDeviceInfo functions described in this chapter.

If all types of interaction are allowed between Xkb and the input extension, the following additional access is provided:

- If allowed, Xkb functionality for additional *KeyClass* devices supported by the input extension is accessed via those same functions.
- If allowed, Xkb functionality for non- *KeyClass* devices supported by the input extension is also accessed via the XkbGetDeviceInfo and XkbSetDeviceInfo functions described in this chapter.

Each device has an X Input Extension device ID. Each device may have several classes of feedback. For example, there are two types of feedbacks that can generate bells: bell feedback and keyboard feedback (*BellFeedbackClass* and *KbdFeedbackClass*). A device can have more than one feedback of each type; the feedback ID identifies the particular feedback within its class.

A keyboard feedback has:

- Auto-repeat status (global and per key)
- 32 LEDs
- A bell

An indicator feedback has:

• Up to 32 LEDs

If the input extension is present and the server allows interaction between the input extension and Xkb, then the core keyboard, the core keyboard indicators, and the core keyboard bells may each be addressed using an appropriate device spec, class, and ID. The constant *XkbXIDfltID* may be used as the device ID to specify the core keyboard indicators for the core indicator feedback. The particular device ID corresponding to the core keyboard feedback and the core indicator feedback may be obtained by calling *XkbGetDeviceInfo* and specifying *XkbUseCoreKbd* as the *device_spec* ; the values will be returned in *dflt_kbd_id* and *dflt_led_id* .

If the server does not allow Xkb access to input extension *KeyClass* devices, attempts to use Xkb requests with those devices fail with a Bad *Keyboard* error. Attempts to access non- *KeyClass* input extension devices via XkbGetDeviceInfo and XkbSetDeviceInfo fail silently if Xkb access to those devices is not supported by the X server.

XkbDeviceInfoRec

Information about X Input Extension devices is transferred between a client program and the Xkb extension in an *XkbDeviceInfoRec* structure:

```
typedef struct {
      char *          name;          /* name for device */
      Atom            type;          /* name for class of devices */
      unsigned short  device_spec;   /* device of interest */
      Bool            has_own_state; /*  True =>this
                                        device has its own state */
      unsigned short  supported;     /* bits indicating supported capabilities */
      unsigned short  unsupported;   /* bits indicating unsupported capabilities *
      unsigned short  num_btns;      /* number of entries in  btn_acts */
      XkbAction *     btn_acts;      /* button actions */
      unsigned short  sz_leds;       /* total number of entries in LEDs vector */
      unsigned short  num_leds;      /* number of valid entries in LEDs vector */
      unsigned short  dflt_kbd_fb;   /* input extension ID of default (core kbd) i
      unsigned short  dflt_led_fb;   /* input extension ID of default indicator fe
      XkbDeviceLedInfoPtr  leds;     /* LED descriptions */
} XkbDeviceInfoRec, *XkbDeviceInfoPtr;


typedef struct {
      unsigned short   led_class;         /* class for this LED device*/
      unsigned short   led_id;            /* ID for this LED device */
      unsigned int     phys_indicators;   /* bits for which LEDs physically
                                             present */
      unsigned int     maps_present;      /* bits for which LEDs have maps in
                                             maps */
      unsigned int     names_present;     /* bits for which LEDs are in
                                              names */
      unsigned int     state;            /* 1 bit => corresponding LED is on */
```

```
    Atom            names[XkbNumIndicators];  /* names for LEDs */
    XkbIndicatorMapRec  maps;          /* indicator maps for each LED */
} XkbDeviceLedInfoRec, *XkbDeviceLedInfoPtr;
```

The *type* field is a registered symbolic name for a class of devices (for example, "TABLET"). If a device is a keyboard (that is, is a member of *KeyClass*), it has its own state, and *has_own_state* is *True* . If *has_own_state* is *False* , the state of the core keyboard is used. The *supported* and *unsupported* fields are masks where each bit indicates a capability. The meaning of the mask bits is listed in Table 21.1, together with the fields in the *XkbDeviceInfoRec* structure that are associated with the capability represented by each bit. The same bits are used to indicate the specific information desired in many of the functions described subsequently in this section.

Table 21.1. XkbDeviceInfoRec Mask Bits

Name	XkbDeviceInfoRec Fields Effected	Value	Capability If Set
XkbXI_KeyboardsMask		(1L << 0)	Clients can use all Xkb requests and events with *KeyClass* devices supported by the input device extension.
XkbXI_ButtonActionsMask	num_btns btn_acts	(1L <<1)	Clients can assign key actions to buttons on non- *KeyClass* input extension devices.
XkbXI_IndicatorNamesMask	leds->names	(1L <<2)	Clients can assign names to indicators on non- *KeyClass* input extension devices.
XkbXI_IndicatorMapsMask	leds->maps	(1L <<3)	Clients can assign indicator maps to indicators on non-*KeyClass* input extension devices.
XkbXI_IndicatorStateMask	leds->state	(1L <<4)	Clients can request the status of indicators on non- *KeyClass* input extension devices.
XkbXI_IndicatorsMask	sz_leds num_leds leds->*	(0x1c)	XkbXI_IndicatorNamesMask | XkbXI_IndicatorMapsMask | XkbXI_IndicatorStateMask
XkbXI_UnsupportedFeaturesMask	unsupported	(1L <<15)	
XkbXI_AllDeviceFeaturesMask	Those selected by Value column masks	(0x1e)	XkbXI_IndicatorsMask | XkbSI_ButtonActionsMask
XkbXI_AllFeaturesMask	Those selected by Value column masks	(0x1f)	XkbSI_AllDeviceFeaturesMask | XkbSI_KeyboardsMask
XkbXI_AllDetailsMask	Those selected by Value column masks	(0x801f)	XkbXI_AllFeaturesMask | XkbXI_UnsupportedFeaturesMask

The *name* , *type* , *has_own_state* , *supported* , and *unsupported* fields are always filled in when a valid reply is returned from the server involving an *XkbDeviceInfoRec* . All of the other fields are modified only if the particular function asks for them.

Querying Xkb Features for Non-KeyClass Input Extension Devices

To determine whether the X server allows Xkb access to particular capabilities of input devices other than the core X keyboard, or to determine the status of indicator maps, indicator names or button actions on a non- *KeyClass* extension device, use XkbGetDeviceInfo.

```
XkbDeviceInfoPtr XkbGetDeviceInfo ( dpy , which, device_spec, ind_class,
ind_id)
Display *  dpy ; /* connection to X server */
unsigned int which; /* mask indicating information to return */
unsigned int  device_spec ; /* device ID, or  XkbUseCoreKbd */
unsigned int  ind_class ; /* feedback class for indicator requests */
unsigned int  ind_id ; /* feedback ID for indicator requests */
```

XkbGetDeviceInfo returns information about the input device specified by *device_spec* . Unlike the *device_spec* parameter of most Xkb functions, *device_spec* does not need to be a keyboard device. It must, however, indicate either the core keyboard or a valid X Input Extension device.

The *which* parameter is a mask specifying optional information to be returned. It is an inclusive OR of one or more of the values from Table 21.1 and causes the returned *XkbDeviceInfoRec* to contain values for the corresponding fields specified in the table.

The *XkbDeviceInfoRec* returned by *XkbGetDeviceInfo* always has values for *name* (may be a null string, ""), *type* , *supported* , *unsupported* , *has_own_state* , *dflt_kbd_fd* , and *dflt_kbd_fb* . Other fields are filled in as specified by *which* .

Upon return, the *supported* field will be set to the inclusive OR of zero or more bits from Table 21.1; each bit set indicates an optional Xkb extension device feature supported by the server implementation, and a client may modify the associated behavior.

If the *XkbButtonActionsMask* bit is set in *which* , the *XkbDeviceInfoRec* returned will have the button actions (*btn_acts* field) filled in for all buttons.

If *which* includes one of the bits in XkbXI_IndicatorsMask, the feedback class of the indicators must be specified in ind_class, and the feedback ID of the indicators must be specified in ind_id. If the request does not include any of the bits in XkbXI_IndicatorsMask, the ind_class and ind_id parameters are ignored. The class and ID can be obtained via the input device extension XListInputDevices request.

If any of the *XkbXI_IndicatorsMask* bits are set in *which* , the *XkbDeviceInfoRec* returned will have filled in the portions of the *leds* structure correspond-

ing to the indicator feedback identified by *ind_class* and *ind_id* . The *leds* vector of the *XkbDeviceInfoRec* is allocated if necessary and *sz_leds* and *num_leds* filled in. The *led_class* , *led_id* and *phys_indicators* fields of the *leds* entry corresponding to *ind_class* and *ind_id* are always filled in. If *which* contains *XkbXI_IndicatorNamesMask* , the *names_present* and *names* fields of the *leds* structure corresponding to *ind_class* and *ind_id* are returned. If *which* contains *XkbXI_IndicatorStateMask* , the corresponding *state* field is updated. If *which* contains *XkbXI_IndicatorMapsMask* , the *maps_present* and *maps* fields are updated.

Xkb provides convenience functions to request subsets of the information available via *XkbGetDeviceInfo* . These convenience functions mirror some of the mask bits. The functions all take an *XkbDeviceInfoPtr* as an input argument and operate on the X Input Extension device specified by the *device_spec* field of the structure. Only the parts of the structure indicated in the function description are updated. The *XkbDeviceInfo* Rec structure used in the function call can be obtained by calling XkbGetDeviceInfo or can be allocated by calling XkbAllocDeviceInfo (see section 21.3).

These convenience functions are described as follows.

To query the button actions associated with an X Input Extension device, use XkbGetDeviceButtonActions.

Status *XkbGetDeviceButtonActions* (*dpy, device_info, all_buttons, first_button, num_buttons*)

Display * *dpy* ; /* connection to X server */

XkbDeviceInfoPtr device_info; /* structure to update with results */

Bool *all_buttons* ; /* *True* => get information for all buttons */

unsigned int first_button; /* number of first button for which info is desired */

unsigned int num_buttons; /* number of buttons for which info is desired */

XkbGetDeviceButtonActions queries the server for the desired button information for the device indicated by the *device_spec* field of *device_info* and waits for a reply. If successful, *XkbGetDeviceButtonActions* backfills the button actions (*btn_acts* field of *device_info*) for only the requested buttons, updates the *name* , *type* , *supported* , and *unsupported* fields, and returns *Success* .

all_buttons , *first_button* and *num_buttons* specify the device buttons for which actions should be returned. Setting *all_buttons* to *True* requests actions for all device buttons; if *all_buttons* is *False* , *first_button* and *num_buttons* specify a range of buttons for which actions are requested.

If a compatible version of Xkb is not available in the server or the Xkb extension has not been properly initialized, XkbGetDeviceButtonActions returns *BadAccess* . If allocation errors occur, a *BadAlloc* status is returned. If the specified device (*device_info -> device_spec*) is invalid, a BadKeyboard status is returned. If the device has no buttons, a Bad *Match* status is returned. If *first_button* and *num_buttons* specify illegal buttons, a Bad *Value* status is returned.

To query the indicator names, maps, and state associated with an LED feedback of an input extension device, use XkbGetDeviceLedInfo.

Status *XkbGetDeviceLedInfo* (*dpy, device_i* nfo, led_class, led_id, which)
Display * *dpy* ; /* connection to X server */
XkbDeviceInfoPtr device_info; /* structure to update with results */
unsigned int *led_class* ; /* LED feedback class assigned by input extension */
unsigned int led_id; /* LED feedback ID assigned by input extension */
unsigned int which; /* mask indicating desired information */

XkbGetDeviceLedInfo queries the server for the desired LED information for the feedback specified by *led_class* and *led_id* for the X input extension device indicated by *device_spec -> device_info* and waits for a reply. If successful, *XkbGetDeviceLedInfo* backfills the relevant fields of *device_info* as determined by *which* with the results and returns *Success* . Valid values for *which* are the inclusive OR of any of *XkbXI_IndicatorNamesMask* , *XkbXI_IndicatorMapsMask* , and *XkbXI_IndicatorStateMask* .

The fields of *device_info* that are filled in when this request succeeds are *name, type, supported* , and *unsupported* , and portions of the *leds* structure corresponding to *led_class* and *led_id* as indicated by the bits set in *which* . The *device_info->leds* vector is allocated if necessary and *sz_leds* and *num_leds* filled in. The *led_class* , *led_id* and *phys_indicators* fields of the *device_info -> leds* entry corresponding to *led_class* and *led_id* are always filled in.

If *which* contains *XkbXI_IndicatorNamesMask* , the *names_present* and *names* fields of the *device_info -> leds* structure corresponding to *led_class* and *led_id* are updated, if *which* contains *XkbXI_IndicatorStateMask* , the corresponding *state* field is updated, and if *which* contains *XkbXI_IndicatorMapsMask* , the *maps_present* and *maps* fields are updated.

If a compatible version of Xkb is not available in the server or the Xkb extension has not been properly initialized, *XkbGetDeviceLedInfo* returns *BadAccess* . If allocation errors occur, a BadAlloc status is returned. If the device has no indicators, a BadMatch error is returned. If *ledClass* or *ledID* have illegal values, a Bad *Value* error is returned. If they have legal values but do not specify a feedback that contains LEDs and is associated with the specified device, a Bad *Match* error is returned.

Allocating, Initializing, and Freeing the XkbDeviceInfoRec Structure

To obtain an *XkbDeviceInfoRec* structure, use XkbGetDeviceInfo or XkbAllocDeviceInfo.

XkbDeviceInfoPtr *XkbAllocDeviceInfo* (device_spec, n_buttons, sz_leds)
unsigned int device_spec; /* device ID with which structure will be used */
unsigned int *n_buttons* ; /* number of button actions to allocate space for*/
unsigned int *sz_leds* ; /* number of LED feedbacks to allocate space for */

XkbAllocDeviceInfo allocates space for an *XkbDeviceInfoRec* structure and initializes that structure's *device_spec* field with the device ID specified by device_spec. If *n_buttons* is nonzero, *n_buttons XkbActions* are linked into the *XkbDeviceInfoRec* structure and initialized to zero. If sz_leds is nonzero, *sz_leds XkbDeviceLedIn-*

foRec structures are also allocated and linked into the *XkbDeviceInfoRec* structure. If you request *XkbDeviceLedInfoRec* structures be allocated using this request, you must initialize them explicitly.

To obtain an *XkbDeviceLedInfoRec* structure, use XkbAllocDeviceLedInfo.

Status *XkbAllocDeviceLedInfo* (devi, num_needed)
XkbDeviceInfoPtr *device_info* ; /* structure in which to allocate LED space */
int *num_needed* ; /* number of indicators to allocate space for */

XkbAllocDeviceLedInfo allocates space for an *XkbDeviceLedInfoRec* and places it in *device_info* . If num_needed is nonzero, *num_needed* *XkbIndicatorMapRec* structures are also allocated and linked into the *XkbDeviceLedInfoRec* structure. If you request *XkbIndicatorMapRec* structures be allocated using this request, you must initialize them explicitly. All other fields are initialized to zero.

To initialize an *XkbDeviceLedInfoRec* structure, use XkbAddDeviceLedInfo.

XkbDeviceLedInfoPtr *XkbAddDeviceLedInfo* (device_info, led_class, led_id)
XkbDeviceInfoPtr device_info; /* structure in which to add LED info */
unsigned int *led_class* ; /* input extension class for LED device of interest */
unsigned int *led_id* ; /* input extension ID for LED device of interest */

XkbAddDeviceLedInfo first checks to see whether an entry matching *led_class* and *led_id* already exists in the *device_info->leds* array. If it finds a matching entry, it returns a pointer to that entry. Otherwise, it checks to be sure there is at least one empty entry in *device_info -> leds* and extends it if there is not enough room. It then increments *device_info -> num_leds* and fills in the next available entry in *device_info -> leds* with *led_class* and *led_id* .

If successful, *XkbAddDeviceLedInfo* returns a pointer to the *XkbDeviceLedInfoRec* structure that was initialized. If unable to allocate sufficient storage, or if *device_info* points to an invalid *XkbDeviceInfoRec* structure, or if *led_class* or *led_id* are inappropriate, *XkbAddDeviceLedInfo* returns *NULL* .

To allocate additional space for button actions in an *XkbDeviceInfoRec* structure, use XkbResizeDeviceButtonActions.

Status *XkbResizeDeviceButtonActions* (device_info, new_total)
XkbDeviceInfoPtr device_info; /* structure in which to allocate button actions */
unsigned int *new_total* ; /* new total number of button actions needed */

XkbResizeDeviceButton reallocates space, if necessary, to make sure there is room for a total of *new_total* button actions in the *device_info* structure. Any new entries allocated are zeroed. If successful, *XkbResizeDeviceButton* returns Success. If new_total is zero, all button actions are deleted, *device_info -> num_btns* is set to zero, and *device_info -> btn_acts* is set to *NULL* . If device_info is invalid or new_total is greater than 255, BadValue is returned. If a memory allocation failure occurs, a *BadAlloc* is returned.

To free an *XkbDeviceInfoRec* structure, use XkbFreeDeviceInfo.

void *XkbFreeDeviceInfo* (device_info, which, free_all)

XkbDeviceInfoPtr device_info; /* pointer to *XkbDeviceInfoRec* in which to free items */

unsigned int *which* ; /* mask of components of *device_info* to free */

Bool *free_all* ; /* *True* => free everything, including device_info */

If free_all is *True* , the *XkbFreeDeviceInfo* frees all components of *device_info* and the *XkbDeviceInfoRec* structure pointed to by *device_info* itself. If free_all is *False* , the value of which determines which subcomponents are freed. *which* is an inclusive OR of one or more of the values from Table 21.1. If which contains XkbXI_ButtonActionsMask, all button actions associated with *device_info* are freed, *device_info -> btn_acts* is set to *NULL* , and *device_info -> num_btns* is set to zero. If which contains all bits in XkbXI_IndicatorsMask, all *XkbDeviceLedInfoRec* structures associated with *device_info* are freed, *device_info -> leds* is set to *NULL* , and *device_info -> sz_leds* and *device_info -> num_leds* are set to zero. If which contains XkbXI_IndicatorMapsMask, all indicator maps associated with *device_info* are cleared, but the number of LEDs and the leds structures themselves are preserved. If which contains XkbXI_IndicatorNamesMask, all indicator names associated with device_info are cleared, but the number of LEDs and the leds structures themselves are preserved. If which contains XkbXI_IndicatorStateMask, the indicator state associated with the *device_info* leds are set to zeros but the number of LEDs and the leds structures themselves are preserved.

Setting Xkb Features for Non-KeyClass Input Extension Devices

The Xkb extension allows clients to assign any key action to either core pointer or input extension device buttons. This makes it possible to control the keyboard or generate keyboard key events from extension devices or from the core pointer.

Key actions assigned to core X pointer buttons or input extension device buttons cause key events to be generated as if they had originated from the core X keyboard.

Xkb implementations are required to support key actions for the buttons of the core pointer device, but support for actions on extension devices is optional. Implementations that do not support button actions for extension devices must not set the *XkbXI_ButtonActionsMask* bit in the *supported* field of an *XkbDeviceInfoRec* structure.

If a client attempts to modify valid characteristics of a device using an implementation that does not support modification of those characteristics, no protocol error is generated. Instead, the server reports a failure for the request; it also sends an *XkbExtensionDeviceNotify* event to the client that issued the request if the client has selected to receive these events.

To change characteristics of an X Input Extension device in the server, first modify a local copy of the device structure and then use either *XkbSetDeviceInfo,* or, to save network traffic, use an *XkbDeviceChangesRec* structure (see section 21.6) and call *XkbChangeDeviceInfo* to download the changes to the server.

To modify some or all of the characteristics of an X Input Extension device, use XkbSetDeviceInfo.

Bool *XkbSetDeviceInfo* (*dpy* , which, device_info)

Display * *dpy* ; /* connection to X server */

unsigned int *which* ; /* mask indicating characteristics to modify */

XkbDeviceInfoPtr device_info; /* structure defining the device and modifications */

XkbSetDeviceInfo sends a request to the server to modify the characteristics of the device specified in the *device_info* structure. The particular characteristics modified are identified by the bits set in *which* and take their values from the relevant fields in *device_info* (see Table 21.1). *XkbSetDeviceInfo* returns *True* if the request was successfully sent to the server. If the X server implementation does not allow interaction between the X input extension and the Xkb Extension, the function does nothing and returns *False* .

The *which* parameter specifies which aspects of the device should be changed and is a bitmask composed of an inclusive OR or one or more of the following bits: *XkbXI_ButtonActionsMask* , *XkbXI_IndicatorNamesMask* , *XkbXI_IndicatorMapsMask* . If the features requested to be manipulated in *which* are valid for the device, but the server does not support assignment of one or more of them, that particular portion of the request is ignored.

If the device specified in *device_info -> device_spec* does not contain buttons and a request affecting buttons is made, or the device does not contain indicators and a request affecting indicators is made, a *BadMatch* protocol error results.

If the *XkbXI_ButtonActionsMask* bit is set in the supported mask returned by XkbGetDeviceInfo, the Xkb extension allows applications to assign key actions to buttons on input extension devices other than the core keyboard device. If the *XkbXI_ButtonActionsMask* is set in *which* , the actions for all buttons specified in device_info are set to the *XkbAction* s specified in *device_info -> btn_acts* . If the number of buttons requested to be updated is not valid for the device, *XkbSetDeviceInfo* returns *False* and a *BadValue* protocol error results.

If the *XkbXI_IndicatorMaps* and / or *XkbXI_IndicatorNamesMask* bit is set in the supported mask returned by XkbGetDeviceInfo, the Xkb extension allows applications to assign maps and / or names to the indicators of nonkeyboard extension devices. If supported, maps and / or names can be assigned to all extension device indicators, whether they are part of a keyboard feedback or part of an indicator feedback.

If the *XkbXI_IndicatorMapsMask* and / or *XkbXI_IndicatorNamesMask* flag is set in *which* , the indicator maps and / or names for all *device_info -> num_leds* indicator devices specified in *device_info -> leds* are set to the maps and / or names specified in *device_info -> leds* . *device_info -> leds -> led_class* and *led_id* specify the input extension class and device ID for each indicator device to modify; if they have invalid values, a *BadValue* protocol error results and *XkbSetDeviceInfo* returns *False* . If they have legal values but do not specify a keyboard or indicator class feedback for the device in question, a *BadMatch* error results. If any of the values in *device_info -> leds -> names* are not a valid Atom or *None* , a *BadAtom* protocol error results.

Xkb provides convenience functions to modify subsets of the information accessible via *XkbSetDeviceInfo* . Only the parts of the structure indicated in the function description are modified. These convenience functions are described as follows.

To change only the button actions for an input extension device, use XkbSetDeviceButtonActions.

Bool *XkbSetDeviceButtonActions* (*dpy* , device, first_button, num_buttons, actions)

Display * *dpy* ; /* connection to X server */

XkbDeviceInfoPtr device_info; /* structure defining the device and modifications */

unsigned int first_button; /* number of first button to update, 0 relative */

unsigned int num_buttons; /* number of buttons to update */

XkbSetDeviceButtonActions assigns actions to the buttons of the device specified in device_info-> *device_spec* . Actions are assigned to *num_buttons* buttons beginning with *first_button* and are taken from the actions specified in *device_info -> btn_acts* .

If the server does not support assignment of Xkb actions to extension device buttons, *XkbSetDeviceButtonActions* has no effect and returns *False* . If the device has no buttons or if *first_button* or *num_buttons* specify buttons outside of the valid range as determined by *device_info -> num_btns* , the function has no effect and returns *False* . Otherwise, *XkbSetDeviceButtonActions* sends a request to the server to change the actions for the specified buttons and returns *True* .

If the actual request sent to the server involved illegal button numbers, a *BadValue* protocol error is generated. If an invalid device identifier is specified in device_info-> *device_spec* , a BadKeyboard protocol error results. If the actual device specified in *device_info -> device_spec* does not contain buttons and a request affecting buttons is made, a *BadMatch* protocol error is generated.

XkbExtensionDeviceNotify Event

The Xkb extension generates *XkbExtensionDeviceNotify* events when the status of an input extension device changes or when an attempt is made to use an Xkb feature that is not supported by a particular device.

Note

Events indicating an attempt to use an unsupported feature are delivered only to the client requesting the event.

To track changes to the status of input extension devices or attempts to use unsupported features of a device, select to receive *XkbExtensionDeviceNotify* events by calling either *XkbSelectEvents* or *XkbSelectEventDetails* (see section 4.3).

To receive *XkbExtensionDeviceNotify* events under all possible conditions, call *XkbSelectEvents* and pass *XkbExtensionDeviceNotifyMask* in both *bits_to_change* and *values_for_bits* .

The *XkbExtensionDeviceNotify* event has no event details. However, you can call *XkbSelectEventDetails* using *XkbExtensionDeviceNotify* as the *event_type* and specifying *XkbAllExtensionDeviceMask* in *bits_to_change* and *values_for_bits*. This has the same effect as a call to *XkbSelectEvents* .

The structure for *XkbExtensionDeviceNotify* events is:

```
typedef struct {
      int      type;           /* Xkb extension base event code */
      unsigned long  serial;   /* X server serial number for event */
      Bool     send_event;     /* True
                                  => synthetically generated*/
      Display *      display;  /* server connection where event generated */
      Time     time;           /* server time when event generated */
      int      xkb_type;  /* XkbExtensionDeviceNotifyEvent */
      int      device;         /* Xkb device ID, will not be
                                  XkbUseCoreKbd */
      unsigned int   reason;   /* reason for the event */
      unsigned int   supported;  /* mask of supported features */
      unsigned int   unsupported;  /* unsupported features this client
                                      attempted to use */
      int      first_btn;      /* first button that changed */
      int      num_btns;       /* number of buttons that changed */
      unsigned int   leds_defined;  /* indicators with names or maps */
      unsigned int       led_state; /* current state of the indicators */
      int       led_class;          /* feedback class for LED changes */
      int       led_id;             /* feedback ID for LED changes */
} XkbExtensionDeviceNotifyEvent;
```

The *XkbExtensionDeviceNotify* event has fields enabling it to report changes in the state (on/off) of all of the buttons for a device, but only for one LED feedback associated with a device. You will get multiple events when more than one LED feedback changes state or configuration.

Tracking Changes to Extension Devices

Changes to an Xkb extension device may be tracked by listening to *XkbDeviceExtensionNotify* events and accumulating the changes in an *XkbDeviceChangesRec* structure. The changes noted in the structure may then be used in subsequent operations to update either a server configuration or a local copy of an Xkb extension device configuration. The changes structure is defined as follows:

```
typedef struct _XkbDeviceChanges {
      unsigned int    changed;   /* bits indicating what has changed */
      unsigned short  first_btn; /* number of first button which changed,
                                    if any */
      unsigned short  num_btns;  /* number of buttons that have changed */
      XkbDeviceLedChangesRec leds;
} XkbDeviceChangesRec,*XkbDeviceChangesPtr;


typedef struct _XkbDeviceLedChanges {
      unsigned short  led_class; /* class of this indicator feedback bundle */
      unsigned short  led_id;    /* ID of this indicator feedback bundle */
      unsigned int    names;     /* bits indicating which names have changed */
      unsigned int    maps;      /* bits indicating which maps have changed */
      struct _XkbDeviceLedChanges *next; /* link to indicator change record
```

```
                                                    for next set */
} XkbDeviceLedChangesRec,*XkbDeviceLedChangesPtr;
```

A local description of the configuration and state of a device may be kept in an *XkbDeviceInfoRec* structure. The actual state or configuration of the device may change because of XkbSetDeviceInfo and XkbSetButtonActions requests made by clients or by user interaction with the device. The X server sends an XkbExtensionDeviceNotify event to all interested clients when the state of any buttons or indicators or the configuration of the buttons or indicators on the core keyboard or any input extension device changes. The event reports the state of indicators for a single indicator feedback, and the state of up to 128 buttons. If more than 128 buttons or more than one indicator feedback are changed, the additional buttons and indicator feedbacks are reported in subsequent events. Xkb provides functions with which you can track changes to input extension devices by noting the changes that were made and then requesting the changed information from the server.

To note device changes reported in an *XkbExtensionDeviceNotify* event, use XkbNoteDeviceChanges.

void *XkbNoteDeviceChanges* (*old, new, wanted*)

XkbDeviceChangesPtr *old* ; /* structure tracking state changes */

XkbExtensionDeviceNotifyEvent * *new* ; /* event indicating state changes */

unsigned int *wanted* ; /* mask indicating changes to note */

The wanted field specifies the changes that should be noted in *old* , and is composed of the bitwise inclusive OR of one or more of the masks from Table 21.1 . The *reason* field of the event in *new* indicates the types of changes the event is reporting. *XkbNoteDeviceChanges* updates the *XkbDeviceChangesRec* specified by *old* with the changes that are both specified in *wanted* and contained in *new -> reason* .

To update a local copy of the state and configuration of an X input extension device with the changes previously noted in an *XkbDeviceChangesRec* structure, use XkbGetDeviceInfoChanges.

To query the changes that have occurred in the button actions or indicator names and indicator maps associated with an input extension device, use XkbGetDeviceInfoChanges.

Status *XkbGetDeviceInfoChanges* (*dpy* , *device_info* , changes)

Display * *dpy* ; /* connection to X server */

XkbDeviceInfoPtr device_info; /* structure to update with results */

XkbDeviceChangesPtr *changes* ; /* contains notes of changes that have occurred */

The changes->changed field indicates which attributes of the device specified in *changes -> device* have changed. The parameters describing the changes are contained in the other fields of *changes* . *XkbGetDeviceInfoChanges* uses that information to call XkbGetDeviceInfo to obtain the current status of those attributes that have changed. It then updates the local description of the device in *device_info* with the new information.

To update the server’s description of a device with the changes noted in an XkbDeviceChangesRec, use XkbChangeDeviceInfo.

Bool *XkbChangeDeviceInfo* (*dpy, device_info, changes*)

Display * *dpy* ; /* connection to X server */

XkbDeviceInfoPtr *device_info* ; /* local copy of device state and configuration */

XkbDeviceChangesPtr *changes* ; /* note specifying changes in *device_info* */

XkbChangeDeviceInfo updates the server's description of the device specified in *device_info -> device_spec* with the changes specified in *changes* and contained in *device_info* . The update is made by an XkbSetDeviceInfo request.

Chapter 22. Debugging Aids

The debugging aids are intended for use primarily by Xkb implementors and are optional in any implementation.

There are two bitmasks that may be used to control debugging. One bitmask controls the output of debugging information, and the other controls behavior. Both bitmasks are initially all zeros.

To change the values of any of the debug controls, use *XkbSetDebuggingFlags* .

Bool *XkbSetDebuggingFlags* (*display, mask, flags, msg, ctrls_mask, ctrls, ret_flags, ret_ctrls*)
Display * *display* ; /* connection to X server */
unsigned int *mask* ; /* mask selecting debug output flags to change */
unsigned int *flags* ; /* values for debug output flags selected by *mask* */
char * *msg* ; /* message to print right now */
unsigned int *ctrls_mask* ; /* mask selecting debug controls to change */
unsigned int *ctrls* ; /* values for debug controls selected by *ctrls_mask* */
unsigned int * *ret_flags* ; /* resulting state of all debug output flags */
unsigned int * *ret_ctrls* ; /* resulting state of all debug controls */

XkbSetDebuggingFlags modifies the debug output flags as specified by *mask* and *flags* , modifies the debug controls flags as specified by *ctrls_mask* and *ctrls* , prints the message *msg* , and backfills *ret_flags* and *ret_ctrls* with the resulting debug output and debug controls flags.

When bits are set in the debug output masks, *mask* and *flags* , Xkb prints debug information corresponding to each bit at appropriate points during its processing. The device to which the output is written is implementation-dependent, but is normally the same device to which X server error messages are directed; thus the bits that can be set in *mask* and *flags* is implementation-specific. To turn on a debug output selection, set the bit for the output in the *mask* parameter and set the corresponding bit in the *flags* parameter. To turn off event selection for an event, set the bit for the output in the *mask* parameter and do not set the corresponding bit in the *flags* parameter.

When bits are set in the debug controls masks, *ctrls_mask* and *ctrls* , Xkb modifies its behavior according to each controls bit. *ctrls_mask* and *ctrls* are related in the same way that *mask* and *flags* are. The valid controls bits are defined in Table 22.1.

Table 22.1. Debug Control Masks

Debug Control Mask	Value	Meaning
XkbDF_DisableLocks	(1 << 0)	Disable actions that lock modifiers

XkbSetDebuggingFlags returns *True* if successful and *False* otherwise. The only protocol error it may generate is *BadAlloc* , if for some reason it is unable to allocate storage.

XkbSetDebuggingFlags is intended for developer use and may be disabled in production X servers. If it is disabled, *XkbSetDebuggingFlags* has no effect and does not generate any protocol errors.

The message in *msg* is written immediately. The device to which it is written is implementation dependent but is normally the same device where X server error messages are directed.

Glossary

Allocator	Xkb provides functions, known as allocators, to create and initialize Xkb data structures.
Audible Bell	An audible bell is the sound generated by whatever bell is associated with the keyboard or input extension device, as opposed to any other audible sound generated elsewhere in the system.
Autoreset Controls	The autoreset controls configure the boolean controls to automatically be enabled or disabled at the time a program exits.
Base Group	The group in effect as a result of all actions other than a previous lock or latch request; the base group is transient. For example, the user pressing and holding a group shift key that shifts to Group2 would result in the base group being group 2 at that point in time. Initially, base group is always Group1.
Base Modifiers	Modifiers that are turned on as a result of some actions other than previous lock or latch requests; base modifiers are transient. For example, the user pressing and holding a key bound to the Shift modifier would result in Shift being a base modifier at that point in time.
Base Event Code	A number assigned by the X server at run time that is assigned to the extension to identify events from that extension.
Base State	The base group and base modifiers represent keys that are physically or logically down; these constitute the base state.
Boolean Controls	Global keyboard controls that may be selectively enabled and disabled under program control and that may be automatically set to an on or off condition upon client program exit.
Canonical Key Types	The canonical key types are predefined key types that describe the types of keys available on most keyboards. The definitions for the canonical key types are held in the first *XkbNumRequiredTypes* entries of the *types* field of the client map and are indexed using the following constants: • *XkbOneLevelIndex* • *XkbTwoLevelIndex* • *XkbAlphabeticIndex* • *XkbKeypadIndex*
Client Map	The key mapping information needed to convert arbitrary keycodes to symbols.
Compat Name	The *compat* name is a string that provides some information about the rules used to bind actions to keys that are changed using core protocol requests.

Compatibility State	When an Xkb-extended X server connects to an Xkb-unaware client, the compatibility state remaps the keyboard group into a core modifier whenever possible.
Compatibility Grab State	The grab state that results from applying the compatibility map to the Xkb grab state.
Compatibility Map	The definition of how to map core protocol keyboard state to Xkb keyboard state.
Component Expression	An expression used to describe server keyboard database components to be loaded. It describes the order in which the components should be loaded and the rules by which duplicate attributes should be resolved.
Compose Processing	The process of mapping a series of keysyms to a string is known as compose processing.
Consumed Modifier	Xkb normally consumes modifiers in determining the appropriate symbol for an event, that is, the modifiers are not considered during any of the later stages of event processing. For those rare occasions when a modifier *should* be considered despite having been used to look up a symbol, key types include an optional *preserve* field.
Core Event	An event created from the core X server.
Detectable Auto-Repeat	Detectable auto-repeat allows a client to detect an auto-repeating key. If a client requests and the server supports detectable auto-repeat, Xkb generates *KeyRelease* events only when the key is physically released. Thus the client receives a number of *KeyPress* events for that key without intervening *KeyRelease* events until the key is finally released, when a *KeyRelease* event is received.
Effective Group	The effective group is the arithmetic sum of the locked, latched, and base groups. The effective keyboard group is always brought back into range depending on the value of the *GroupsWrap* control for the keyboard. If an event occurs with an effective group that is legal for the keyboard as a whole, but not for the key in question, the group *for that event only* is normalized using the algorithm specified by the *group_info* member of the key symbol map (*XkbSymMapRec*).
Effective Mask	An Xkb modifier definition consists of a set of bit masks corresponding to the eight real modifiers; a similar set of bitmasks corresponding to the 16 named virtual modifiers; and an effective mask. The effective mask represents the set of all real modifiers that can logically be set either by setting any of the real modifiers or by setting any of the virtual modifiers in the definition.
Effective Modifier	The effective modifiers are the bitwise union of the base, latched and locked modifiers.
Extension Device	Any keyboard or other input device recognized by the X input extension.

Global Keyboard Controls

Controls that affect the way Xkb generates key events. The controls affect all keys, as opposed to per-key controls that are for a single key. Global controls include

- RepeatKeys Control
- DetectableAuto-repeat
- SlowKeys
- BounceKeys
- StickyKeys
- MouseKeys
- MouseKeysAccel
- AccessXKeys
- AccessXTimeout
- AccessXFeedback
- Overlay1
- Overlay2
- EnabledControls

Grab State

The grab state is the state used when matching events to passive grabs. It consists of the grab group and the grab modifiers.

Group

See Keysym Group

Group Index

A number used as the internal representation for a group number. Group1 through Group 4 have indices of 0 through 3.

Groups Wrap Control

If a group index exceeds the maximum number of groups permitted for the specified keyboard, it is wrapped or truncated back into range as specified by the global *GroupsWrap* control. *GroupsWrap* can have the following values:

WrapIntoRange
ClampIntoRange
RedirectIntoRange

Key Type

An attribute of a key that identifies which modifiers affect the shift level of a key and the number of groups on the key.

Key Width

The maximum number of shift levels in any group for the key type associated with a key.

Keysym Group

A keysym group is a logical state of the keyboard providing access to a collection of characters. A group usually contains a set of characters that logically belong together and that may

	be arranged on several shift levels within that group. For example, Group1 could be the English alphabet, and Group2 could be Greek. Xkb supports up to four different groups for an input device or keyboard. Groups are in the range 1-4 (Group1 - Group4), and are often referred to as G1 - G4 and indexed as 0 - 3.
Indicator	An indicator is a feedback mechanism such as an LED on an input device. Using Xkb, a client application can determine the names of the various indicators, determine and control the way that the individual indicators should be updated to reflect keyboard changes, and determine which of the 32 keyboard indicators reported by the protocol are actually present on the keyboard.
Indicator Feedback	An indicator feedback describes the state of a bank of up to 32 lights. It has a mask where each bit corresponds to a light and an associated value mask that specifies which lights are on or off.
Indicator Map	An indicator has its own set of attributes that specify whether clients can explicitly set its state and whether it tracks the keyboard state. The indicator map is the collection of these attributes for each indicator and is held in the *maps* array, which is an array of *XkbIndicatorRec* structures.
Input Extension	An extension to the core X protocol that allows an X server to support multiple keyboards, as well as other input devices, in addition to the core X keyboard and pointer. Other types of devices supported by the input extension include, but are not limited to: mice, tablets, touchscreens, barcode readers, button boxes, trackballs, identifier devices, data gloves, and eye trackers.
Key Action	A key action consists of an operator and some optional data. Once the server has applied the global controls and per-key behavior and has decided to process a key event, it applies key actions to determine the effects of the key on the internal state of the server. Xkb supports actions that do the following: • Change base, latched, or locked modifiers or group • Move the core pointer or simulate core pointer button events • Change most aspects of keyboard behavior • Terminate or suspend the server • Send a message to interested clients • Simulate events on other keys
Key Alias	A key alias is a symbolic name for a specific physical key. Key aliases allow the keyboard layout designer to assign multiple key names to a single key. This allows the keyboard layout designer to refer to keys using either their position or their "function." Key aliases can be specified both in the symbolic names component and in the keyboard geometry. Both sets of aliases are always valid, but key alias definitions in the keyboard geometry have

priority; if both symbolic names and geometry include aliases, you should consider the definitions from the geometry before considering the definitions from the symbolic names section.

Key Behavior

The *behaviors* field of the server map is an array of *XkbBehavior* , indexed by keycode, and contains the behavior for each key. The X server uses key behavior to determine whether to process or filter out any given key event; key behavior is independent of keyboard modifier or group state. Each key has exactly one behavior.

Key behaviors include:

- XkbKB_Default
- XkbKB_Lock
- XkbKB_RadioGroup
- XkbKB_Overlay1
- XkbKB_Overlay2

Key Symbol Map

A key symbol map describes the symbols bound to a key and the rules to be used to interpret those symbols. It is an array of *XkbSymMapRec* structures indexed by keycode.

Key Type

Key types are used to determine the shift level of a key given the current state of the keyboard. There is one key type for each group for a key. Key types are defined using the *XkbKeyTypeRec* and *XkbKTMapEntryRec* structures. Xkb allows up to *XkbMaxKeyTypes* (255) key types to be defined, but requires at least *XkbNumRequiredTypes* (4) predefined types to be in a key map.

Keyboard Bells

The sound the default bell makes when rung is the system bell or the default keyboard bell. Some input devices may have more than one bell, identified by *bell_class* and *bell_id*.

Keyboard Components

There are five types of components stored in the X server database of keyboard components. They correspond to the *symbols, geometry, keycodes, compat,* and *types* symbolic names associated with a keyboard.

Keyboard Feedback

A keyboard feedback includes the following:

Keyclick volume
Bell volume
Bell pitch
Bell duration
Global auto-repeat
Per key auto-repeat
32 LEDs

Key Width, Key Type Width

The maximum number of shift levels for a type is referred to as the width of a key type.

Keyboard Geometry	Keyboard geometry describes the physical appearance of the keyboard, including the shape, location, and color of all keyboard keys or other visible keyboard components such as indicators and is stored in a *XkbGeometryRec* structure. The information contained in a keyboard geometry is sufficient to allow a client program to draw an accurate two-dimensional image of the keyboard.
Keyboard Geometry Name	The keyboard geometry name describes the physical location, size, and shape of the various keys on the keyboard and is part of the *XkbNamesRec* structure.
Keyboard State	Keyboard state encompasses all of the transitory information necessary to map a physical key press or release to an appropriate event.
Keycode	A numeric value returned to the X server when a key on a keyboard is pressed or released, indicating which key is being modulated. Keycode numbers are in the range 1 <= keycode <= max, where max is the number of physical keys on the device.
Keycode Name	The keycode name describes the range and meaning of the keycodes returned by the keyboard and is part of the *XkbNamesRec* structure.
Latched Group	A latched group is a group index that is combined with the base and locked group to form the effective group. It applies only to the next key event that does not change the keyboard state. The latched group can be changed by keyboard activity or via Xkb extension library functions.
Latched Modifier	Latched modifiers are the set of modifiers that are combined with the base modifiers and the locked modifiers to form the effective modifiers. It applies only to the next key event that does not change the keyboard state.
LED	A light emitting diode. However, for the purposes of the X keyboard extension specification, a LED is any form of visual two-state indicator that is either on or off.
Locked Group	A locked group is a group index that is combined with the base and latched group to form the effective group. When a group is locked, it supersedes any previous locked group and remains the locked group for all future key events, until a new group is locked. The locked group can be changed by keyboard activity or via Xkb extension library functions.
Locked Modifiers	Locked modifiers are the set of modifiers that are combined with the base modifiers and the latched modifiers to form the effective modifiers. A locked modifier applies to all future key events until it is explicitly unlocked.
Lookup State	The lookup state is composed of the lookup group and the lookup modifiers, and it is the state an Xkb-capable or Xkb-aware client should use to map a keycode to a keysym.

Modifier	A modifier is a logical condition that is either set or unset. The modifiers control the Shift Level selected when a key event occurs. Xkb supports the core protocol eight modifiers (*Shift* , *Lock* , *Control* , and *Mod1* through *Mod5*), called the *real* modifiers. In addition, Xkb extends modifier flexibility by providing a set of sixteen named virtual modifiers, each of which can be bound to any set of the eight real modifiers.
Modifier Key	A modifier key is a key whose operation has no immediate effect, but that, for as long as it is held down, modifies the effect of other keys. A modifier key may be, for example, a shift key or a control key.
Modifier Definition	An Xkb modifier definition, held in an *XkbModsRec* , consists of a set of real modifiers, a set of virtual modifiers, and an effective mask. The mask is the union of the real modifiers and the set of real modifiers to which the virtual modifiers map; the mask cannot be explicitly changed.
Nonkeyboard Extension Device	An input extension device that is not a keyboard. Other types of devices supported by the input extension include, but are not limited to: mice, tablets, touchscreens, barcode readers, button boxes, trackballs, identifier devices, data gloves, and eye trackers.
Outlines	An outline is a list of one or more points that describes a single closed polygon, used in the geometry specification for a keyboard.
Physical Indicator Mask	The physical indicator mask is a field in the *XkbIndicatorRec* that indicates which indicators are bound to physical LEDs on the keyboard; if a bit is set in *phys_indicators* , then the associated indicator has a physical LED associated with it. This field is necessary because some indicators may not have corresponding physical LEDs on the keyboard.
Physical Symbol Keyboard Name	The *symbols* keyboard name identifies the symbols logically bound to the keys. The symbols name is a human or application-readable description of the intended locale or usage of the keyboard with these symbols. The *phys_symbols* keyboard name, on the other hand, identifies the symbols actually engraved on the keyboard.
Preserved Modifier	Xkb normally consumes modifiers in determining the appropriate symbol for an event, that is, the modifiers are not considered during any of the later stages of event processing. For those rare occasions when a modifier *should* be considered despite having been used to look up a symbol, key types include an optional *preserve* field. If a modifier is present in the *preserve* list, it is a preserved modifier.
Radio Group	A radio group is a set of keys whose behavior simulates a set of radio buttons. Once a key in a radio group is pressed, it stays logically depressed until another key in the group is pressed, at which point the previously depressed key is logically released.

	Consequently, at most one key in a radio group can be logically depressed at one time.
Real Modifier	Xkb supports the eight core protocol modifiers (*Shift* , *Lock* , *Control* , and *Mod1* through *Mod5*); these are called the *real* modifiers, as opposed to the set of sixteen named virtual modifiers that can be bound to any set of the eight real modifiers.
Server Internal Modifiers	Modifiers that the server uses to determine the appropriate symbol for an event; internal modifiers are normally consumed by the server.
Shift Level	One of several states (normally 2 or 3) governing which graphic character is produced when a key is actuated.
Symbol Keyboard Name	The *symbols* keyboard name identifies the symbols logically bound to the keys. The symbols name is a human or application-readable description of the intended locale or usage of the keyboard with these symbols. The *phys_symbols* keyboard name, on the other hand, identifies the symbols actually engraved on the keyboard.
Symbolic Name	Xkb supports symbolic names for most components of the keyboard extension. Most of these symbolic names are grouped into the *names* component of the keyboard description.
State Field	The portion of a client-side core protocol event that holds the modifier, group, and button state information pertaining to the event.
Types Name	The *types* name provides some information about the set of key types that can be associated with the keyboard. In addition, each key type can have a name, and each shift level of a type can have a name.
Valuator	A valuator reports a range of values for some entity, like a mouse axis, a slider, or a dial.
Virtual Modifier	Xkb provides a set of sixteen named virtual modifiers that can be bound to any set of the eight real modifiers. Each virtual modifier can be bound to any set of the real modifiers (*Shift* , *Lock* , *Control,* and *Mod1 - Mod5*).
Virtual Modifier Mapping	Xkb maintains a virtual modifier mapping, which lists the virtual modifiers associated with each key.
Xkb-aware Client	A client application that initializes Xkb extension and is consequently bound to an Xlib that includes the Xkb extension.
Xkb-capable Client	A client application that makes no Xkb extension Xlib calls but is bound to an Xlib that includes the Xkb extension.
Xkb-unaware Client	A client application that makes no Xkb extension Xlib calls and is bound to an Xlib that does not include the Xkb extension.